



Business Services

Contracts Office

5735 47th Avenue • Sacramento, CA 95824

(916) 643-2464

Rose Ramos, Chief Business Officer

Jessica Sulli, Contract Specialist

ADDENDUM NO. 4

Date: January 26, 2021

Issued by: Sacramento City Unified School District

Project: 0844-439, Transportation Electric Bus Infrastructure

You are hereby notified of the following changes, clarifications, or modifications to the original Contract Documents, Specifications, and Drawings. This Addendum shall supersede the original project documents, and shall take precedence over anything to the contrary therein. All Addenda shall be acknowledged in the Bid Form. Failure to do so may result in disqualification of the bid. All other conditions remain unchanged.

1. The Time for Completion of the project has been extended to 90 calendar days to account for equipment lead time.
2. Responses to RFIs are attached.

END OF ADDENDUM NO. 4

#	Subject	Question	Response
1	Owner Furnished Equipment	Will the district be procuring and providing all of the Electric Vehicle Charging Equipment needed to complete the project?	CFCI
2	Sheet E1.1	Please provide specifications for the EV charging stations shown on Sht. E1.1.	Secified on drawings.
3	Sheet E1.1	Please clarify if the EV charging stations are OFOI, OFCI, or CFCI.	CFCI
4	Electrical	Plan page E1.1 calls for (N) SMUD UG Primary Service, during the job walk it was stated that there was existing SMUD UG conduit installed under San Joaquin St and stubbed on to the property. Please confirm that the SMUD primary tie in point will be on the site property and we will not need to run conduit across the street to the nearest pole.	All SMUD underground conduits crossing San Joaquin Street are new.
5	Electrical	Please confirm that the design/service commitment process has been started with SMUD.	SMUD commitment has been processed.
6	Electrical	Please confirm that contractor will not be responsible for delays in project completion due to SMUD coordination and scope.	Confirmed.
7	Electrical	Due to the majority of work being electrical, would the district consider allowing C-10 contractors to bid as prime if a qualified A-Licensed contractor is listed as a sub for the civil/engineering scope?	A or B license is required.
8	Electrical	Please confirm that the Field Office specification 01 52 13 does not apply to this project.	Field office for District will not be required.
9	Electrical	Plan page E1.1 calls for new bus chargers to be installed. Please confirm if new bus chargers are OFCI or CFCI. If contractor is responsible to provide new chargers please provide detailed specifications.	CFCI
10	Electrical Specs 2.03	Electrical specs 2.03 C States Switchboards needs to be made available for inspection at manufacturer's facility and to allow witnessing of factory inspections. Does this pertain to this project.	Spec section does not apply and has been deleted.
11	Sheet E1.1	You are asking on E1.1 Note 3 to provide new breakers for existing gear do you have any information on existing equipment?	Note 3 deleted.
12	SMUD	Is SMUD providing the Transformer ahead of Switchboard 'MSEV'?	Yes, it's SMUD service transformer fed from across the street.
13	Owner Furnished Equipment	Is the District providing all the Chargers and the Pedestals?	CFCI
14	Sheet E1.1	The pull box count shown on the One Line (E2.1) does not match the site layout on E1.1, which shall we use?	Use pull box count on site plan.
15	Add Alt 2	Are disconnects needed for the (3) existing chargers shown to be replaced fed from Switchboard 'EVC'?	No.
16	Sheet E1.1	Does the conduit run shown on E1.1 between the (2) PB2 boxes stub into each pad or just run between the pullboxes?	The conduit feed from (2) PB2 homerun to main switchboard "DEV" does not stub into pedestal pad. Make this conduit 4"C.O. stub.
17	Time to Complete	28 working days is not compatible with shipping requirements for gear. Will this be adjusted to reflect?	Yes.
18	General Conditions	Will the on-site project trailer be required?	No.
19	General Conditions	Are the insurance requirements from the general conditions accurate for this project?	Yes.