



**Capital Asset Management Services
Planning and Construction**

425 First Avenue • Sacramento, CA 95818
(916) 264-4075 • FAX (916) 264-3107

*Jonathan P. Raymond, Superintendent
James C. Dobson, Director II, Planning and Construction*

Via Facsimile

TWO PAGES

ADDENDUM NO. 2

Date: August 16, 2010
Issued by: Sacramento City Unified School District
Project: PC11-03, Fire Service at Luther Drive

You are hereby notified of the following changes, clarifications, or modifications to the original Contract Documents, Specifications, and Drawings. This Addendum shall supersede the original project documents, and shall take precedence over anything to the contrary therein. All Addenda shall be acknowledged in the Bid Form. Failure to do so may result in disqualification of the bid. All other conditions remain unchanged.

- 1) Will a jumper for testing be required in the road at the 12" W P.O.C.?
A-Yes.

- 2) If so, what size backflow will be required for the jumper?
A-Sacramento City Utilities will rent the contractor a certified backflow that the contractor can use.

- 3) If no jumper is required, may the section of pipe upstream of the 8" DDCV be swabbed by hand for disinfection?
A- Before acceptance of the potable water system, disinfect each unit of completed service line in accordance with AWWA C601 and criteria of the local Owner/City.
 - i. Proposed method shall be submitted to the Owner's Representative for review and acceptance.
 - ii. Perform all tests and disinfection in a manner acceptable to governmental agencies having jurisdiction.

Furnish two copies of a Certificate of Compliance to the Owner.

- 4) If no jumper is required, may we test against the (E) 12" G.V.?
A-Jumper will be required.

END OF ADDENDUM NO. 2