

Business Services Contracts Office

5735 47th Avenue ● Sacramento, CA 95824 (916) 643-2464

Rose Ramos, Chief Business Officer Robert Aldama, Purchasing Manager II

ADDENDUM NO. 2.0

Date: 07/17/2023

Issued by: Sacramento City Unified School District

Project: Project #: 0035-464

Camellia ES Telecenter Upgrade Project

This addendum shall supersede the original Information, attachments, and specifications regarding Project No. <u>0035-464</u> where it adds to, deletes from, clarifies or otherwise modifies them. All other conditions and any previous addenda shall remain unchanged.

Part A - Bidding and Contract Requirements

AD 2.10:

Question: The Equipment Appendix in the addenda 1 specifications lists a Cisco part number that is not available for public purchase. It can only be purchased by Educational / governmental entities. Please provide alternate part number.

Answer:

Cisco integrator is able to purchase network and licensing equipment listed.

AD 2.11:

Question: There is no symbol legend present on the current plans. Can one please be provided that clearly identifies the make/model of the devices and the number of CAT 6A drops required for each device type? Please see the attached symbol legend as an example.

Project No: 0035-464 Camellia ES Telecenter Upgrade Project ADDENDUM NO. 2

	1.1 m - 1.00 (12 A 12 65 10 3 A 7 (4 10 1)	PART	NOTES / DETAIL
SYMBOL	DESCRIPTION	MANUFACTURER	NUMBER	REFERENCES
	(N) SURFACE MOUNTED CONDUIT	GRC	GENERIC	GREY = EXISTING
	(E) UNDERGROUND CONDUIT	N/A	N/A	N/A
	(N) HIGH CAPACITY SURFACE MOUNTED CABLE RACEWAY	WIREMOLD	5500 SERIES	GREY = EXISTING
2300	(N) MEDIUM CAPACITY SURFACE MOUNTED CABLE RACEWAY	WIREMOLD	2300 SERIES	GREY = EXISTING
	(N) J-HOOK PATHWAY	COMMERCIAL GENERIC	N/A	GREY = EXISTING
MDF / [IDF]	(E) DATA RACK	DAMAC	SEE SHEET T400	GREY = EXISTING
G	(E) GROUND BOX	N/A	N/A	N/A
J	(E) JUNCTION BOX	N/A	N/A	N/A
DH / (D)	(E) SURFACE MOUNTED 4-SQUARE JUNCTION BOX, WALL / CEILING	N/A	N/A	N/A
	(E) INTERCOM SPEAKER/CLOCK COMBO	N/A	N/A	16" = 16" CLOCK
	(E) INTERIOR INTERCOM SPEAKER	N/A	N/A	N/A
	(E) EXTERIOR INTERCOM SPEAKER	N/A	N/A	N/A
(3)	(E) FLUSH MOUNTED CLOCK	N/A	N/A	N/A
	(N) CAT6A DATA DROP LOCATION - IP CLOCK	LOWELL & SAPLING	SEE SHEET T400	16" = 16" CLOCK
	(N) CAT6A DATA DROP LOCATION (QTY = 2) -IP CLOCK/SPEAKER/IP MODULE COMBO BOX	LOWELL, SAPLING, RAULAND & TCU	SEE SHEET T400	N/A
	(N) CAT6A DATA DROP LOCATION - WALL MOUNTED SPEAKER/IP MODULE	RAULAND & TELECENTER U	SEE SHEET T400	N/A
c [【]◀	(N) CAT6A DATA DROP LOCATION - DROP CEILING INTERCOM SPKR/IP MOD	RAULAND & TELECENTER U	SEE SHEET T400	N/A
4	(N) CAT6A DATA DROP LOCATION - EXTERIOR INTERCOM SPEAKER/IP MODULE	LOWELL, RAULAND & TELECENTER U	SEE SHEET T400	N/A
4G	(N) SURFACE MOUNTED 4 GANG BACKBOX - WHITE	FSR	SEE SHEET T400	N/A
DIG	(N) SURFACE MOUNTED DIGITAL CLOCK	SAPLING	SBP-31S-254-OW	N/A
TEL	(N) ADMIN. CONSOLE PHONE	RAULAND	SEE SHEET T400	N/A

<u>Answer</u>: The keyed notes explain the scope of work for each of the items noted but a legend of symbols is below:

S with circle - speaker

C with circle - clock

S and C in box - combination speaker and clock

MSG with box - digital message display

AD 2.12:

Question: Sheet Notes 5 and 14 call for a new 24-port Cisco switch to be installed at the IDFs only. There is no indication of new switch gear or UPS units required at the MDF. Can you please reconfirm if any switches, related switch components, and UPS units are required for the MDF? Please see the attached Equipment Appendix and provide updated quantities, if needed. This will ensure that all bidding contractors will provide the correct quantity of components to the District.

Project No: 0035-464 Camellia ES Telecenter Upgrade Project ADDENDUM NO. 2

Equipment Appendix - Provide the following network and UPS equipment for Camellia Elementary as shown below:

230235 - Camellia E.S. Tele-Center Upgrade Project				
MODEL	DESCRIPTION	QTY		
C9300L-24P-4X-EDU	Cisco - C9300L-24P-4X-EDU Catalyst Full PoE, 4x10G/1G fixed uplinks	4		
C9300L-DNA-E-24-3Y	Cisco - C9300L DNA Essentials, 24 Port, 3 year term	4		
SFP-H1GB-CU1M	Cisco - 1GB, 1meter fiber cable	4		
GLC-SX-MM SFP	Cisco - GLC-SX-MM-1000Base-SX-SFP Transceiver, 1GB fiber module	8		
SMC15002URM	Tripp-Lite - UPS (IDF) with network monitoring	3		

<u>Answer</u>: Will need to add (1) 24 port switch which will receive 4 fiber modules already listed in equipment listing. No additional UPS equipment is required for MDF.

AD 2.13:

<u>Question</u>: Section 27 21 00 - 5 3.07 (Configuration) states that, "Any information needed from the District for configuration of equipment (i.e. VLAN, etc.) needs to be requested in writing 2 weeks prior. All equipment to be fully configured and tested for functionality by the Contractor prior to District acceptance testing."

Can the District please clarify what level of switch configuration is required to be deemed "fully configured". The programming of switches can be a time-consuming process, depending on what exactly needs to be configured. A list of requirements will help ensure all bidding contractors factor in the appropriate amount of configuration labor required for this project.

<u>Answer:</u> Network switches used for clock and speaker intercom system shall be configured as managed switches on separate vlan with IP scheme and setting configurations provided by the district.

AD 2.14:

Question: During the site walk it was mentioned that a link to all the photos taken by the consulting engineer can be provided to contractors. Can you please provide this link?

Answer:

You will find photos on the District's eBuilder by going to Documents tab and choosing the project (i.e. Camellia Telecenter Upgrade), then go to left column called Folders, scroll down to Project Construction Folder and open, then scroll down to Site Photos.

AD 2.15:

<u>Question:</u> Can we change out the Round Clocks to the Message Board clocks? This will save district money as there will only need to be 1 Cat6A pulled to each Clock/Speaker Location, instead of the current requirement for 2. This will also eliminate some additional conduit run at certain locations to fit additional cables?

Project No: 0035-464 Camellia ES Telecenter Upgrade Project ADDENDUM NO. 2

Answer:

For this project, the district will accept a combination speaker/message board clock model. At locations where a combination clock/speaker are currently shown on the drawings, contractor shall provide TCC2011B IP module, ACC3011S-US0188 speaker and TCC3011S clock/message board, all installed in ACC3011SBB surface mount backbox. Contractor can also revise number of data drops needed to one per classroom speaker unit in lieu of the two drops needed for the clock and speaker installation as originally shown.

AD 2.20:

<u>Question</u>: Is the District willing to consider amending the plans and specifications with an addendum such that the network active components (Switches, UPS, licensing, etc.) will be OFCI (Owner Furnished, Contractor Installed)?

Answer: No, Contractor is able to purchase equipment listed.

Message obtained from CDWG regarding this:

"In this circumstance I have the contractor order the HW/licenses under the districts account, then utilize a credit card or a form of Pre-payment. This way it meets the requirements of it being EDU, because it is on your account, then I work with the contractor to issue 1 of the 2 payments above directly to CDW"

Other vendors available also.

AD 2.21: Refer to DOCUMENT 00 11 16 NOTICE TO BIDDERS

REVISE **#6.** /Notice To Bidders as follows:

6. Electronic Bids will be received until 2:00 pm on July 20, 2023, after which time the bids will be opened and posted on eBuilder and SCUSD website.

END OF ADDENDUM NO. 2.0

Acknowledgement of this Addendum will be required at time of bid.