SECTION 27 00 00

COMMUNICATIONS BASIC REQUIREMENTS

PART 1 - GENERAL

1.01 SUMMARY

A. This Section specifies the common administration basic requirements and common methods for all low voltage systems installation work included under Division 27 and 28 (and other Divisions). Where those requirements differ from the requirements of this section, the more stringent shall govern.

1.02 STANDARDS, REGULATIONS, AND CODES REFERENCES

- A. The following Standards, Regulations and Codes apply to work specified in the Contract Documents.
 - 1. Applicable State and Local Codes.
 - 2. California Building Code and California Electrical Code, Current Editions.
 - 3. BICSI TDMM (Telecommunications Distribution Methods Manual), 11th Edition 2006.
 - 4. ANSI/TIA/EIA-568-B.1. Commercial Building Telecommunications Cabling Standard,
 - ANSI/TIA/EIA-568-B.1-2. Commercial Building Telecommunications Cabling Standard, Part 1: General Requirements, Addendum 2, Grounding and Bonding Specifications for Screened Balanced Twisted-Pair Horizontal Cabling.
 - ANSI/TIA/EIA-568-B.1-3. Commercial Building Telecommunications Cabling Standard.
 - 7. ANSI/TIA/EIA-568-B.1-4. Commercial Building Telecommunications Cabling Standard, Part 1: General Requirements, Addendum 4, Recognition of Category 6 and Category Cat 6A and 50 nm Laser-Optimized 50/125 um Multimode Optical Fiber Cabling.
 - 8. ANSI/TIA/EIA-568-B.1-2. Commercial Building Telecommunications Cabling Standard, Part 2: Balanced Twisted-Pair Cabling Components.
 - ANSI/TIA/EIA-568-B.2-1. Commercial Building Telecommunications Cabling Standard, Part 2: Balanced Twisted-Pair Cabling Components, Addendum 1, Transmission Performance Specifications for 4-Pair 100 Ohm Category 6 Cabling.
 - ANSI/TIA/EIA-568-B.2-10 (draft 2.0). Commercial Building Telecommunications Cabling Standard, Part 2: Balanced Twisted-Pair Cabling Components, Addendum 10, Transmission Performance Specifications for 4-Pair 100 Ohm Augmented Category 6 Cabling.
 - 11. ANSI/TIA/EIA-568-B3.3 Optical Fiber Cabling Components Standard.
 - 12. TIA-569-B. Commercial Building Standard for Telecommunications Pathways and Spaces.
 - 13. ANSI/TIA/EIA-606-A. Administration Standard for Commercial Telecommunications Infrastructure.
 - 14. ANSI/TIA/EIA-607-A. Commercial Building Grounding (Earthing) and Bonding Requirements for Telecommunications.

- 15. TIA/EIA TSB-67 Transmission Performance Specifications for Field Testing of Unshielded Twisted-Pair Cabling Systems.
- 16. TIA/EIA TSB-72 Centralized Optical Fiber Cabling Guidelines.

1.03 DEFINITIONS

- A. The following is a list of abbreviations generally used in Divisions 27 & 28:
 - 1. ADA Americans with Disabilities Act
 - 2. AHJ Authority Having Jurisdiction
 - 3. ANSI American National Standards Institute
 - 4. APWA American Public Works Association
 - 5. ASTM American Society for Testing and Materials
 - 6. CBC California Building Code
 - 7. CEC California Electrical Code
 - 8. CFC California Fire Code
 - 9. FCC Federal Communications Commission
 - 10. HVAC Heating, Ventilating and Air Conditioning
 - 11. IEC International Electro-technical Commission
 - 12. IEEE Institute of Electrical and Electronics Engineers.
 - 13. IETA International Electrical Testing Association
 - 14. FM FM Global
 - 15. NEMA National Electrical Manufacturers Association
 - 16. NFPA National Fire Protection Association
 - 17. OSHA Occupational Safety and Health Administration
 - 18. UL Underwriters Laboratories Inc.
- B. Provide: To furnish and install, complete and ready for the intended use.
- C. Furnish: Supply and deliver to the project site, ready for unpacking, assembly, and installation.
- D. Install: Includes unloading, unpacking, assembling, erecting, installing, applying, finishing, protecting, cleaning, and similar operations at the project site to complete items of work furnished by others.
- E. Following is a list of commonly used terms:
 - 1. Active Equipment: Electronic equipment used to develop various WAN and LAN services.
 - 2. Backbone: Collective term sometimes used to describe the campus and vertical distribution subsystem facilities and media interconnecting service entrances, communications rooms, and communications cabinets.
 - 3. Bonding: Permanent joining of metallic parts to form an electrically conductive path which will assure electrical continuity and the capacity to safely conduct currents likely to be imposed on it.
 - 4. Cabinet: Wall-mounted modular enclosure designed to house and protect electronic equipment.

- 5. Cable Tray: Vertical or horizontal open supports, usually made of aluminum or steel, that are fastened to a building ceiling or wall. Cables are laid in and fastened to the trays. A cable tray is not a raceway.
- 6. Campus: Grounds and buildings of a multi-building premises environment.
- Channel: The end-to-end transmission path between two points at which application specific equipment is connected; may include one or more links, cross-connect jumper and/or patch cords, and work area station cords. Does not include connections to active equipment.
- 8. Cross-Connect: Equipment used to terminate and tie together communications circuits.
- 9. Cross-Connect Jumper: A cluster of twisted-pair conductors without connectors used to establish a circuit by linking two cross-connect termination points.
- 10. Fiber Optic Distribution Unit (FDU): Cabinet with terminating equipment used to develop fiber optic cross-connect facilities. Also known as LIU.
- 11. Grounding: a conducting connection to earth, or to some conducting body that serves in place of earth.
- 12. Hinged Cover Enclosure: Wall-mounted box with a hinged cover that is used to house and protect electrical devices.
- 13. Horizontal: Pathway facilities and media connecting the MDF or IDF to Telecommunications Outlets.
- 14. Intermediate Distribution Frame (IDF): Data networking equipment rack and/or location that serves an individual area, floor or building. Downstream from the MDF.
- 15. Jack: Receptacle used in conjunction with a plug to make electrical contact between communications circuits, e.g., eight-position/eight-contact modular jacks.
- 16. Link: A transmission path between two points, not including terminal equipment, work area cables, and equipment cables; one continuous section of conductors or fiber, including the connecting hardware at each end.
- 17. Local Area Network (LAN): Data transmission facility connecting several communicating devices, typically Ethernet and the network is limited to a single campus.
- 18. Main Distribution Frame (MDF): Initial (main) data network equipment rack and/or location. Only one MDF occurs per site and may serve many downstream IDFs.
- 19. Media: The type of cable (e.g., twisted-pair, coaxial, or fiber optic) used to provide signal transmission paths.
- 20. Minimum Point of Entry (MPOE): The location where the service provider hands off connection and responsibility for service to on-premise customer owned equipment.
- 21. Modular plug: An eight-position, eight-conductor end-of-wire electrical connector used with Category rated cable.
- 22. Passive Equipment: Non-electronic hardware and apparatus, e.g., equipment racks, cable trays, electrical protection, wiring blocks, FDUs, etc.
- 23. Patch Cord: A length of copper or fiber cable with connectors on both ends used to join communications circuits at MDF/IDF and end stations.
- 24. Patch Panel: System of terminal blocks or connectors used with patch cords that facilitate the administration of cross-connect fields.

- 25. Pathway: Facility for the placement of communications cable. A pathway facility can be composed of several components including conduit, wireway, cable tray, surface raceway, underfloor systems, raised floor, ceiling support wires, etc.
- 26. Protectors: Electrical protection devices used to limit foreign voltages on metallic communications circuits.
- 27. Raceway: An enclosed channel designed expressly for holding wires or cables; may either conductive metal or insulating plastic. The term includes conduit, tubing, wireway, underfloor raceway, and surface raceway; does not include cable tray.
- 28. Rack: An open or enclosed structure, typically made of aluminum or steel, used to mount equipment; usually referred to as an equipment rack. Maybe freestanding and floor mounted or a wall mounted cabinet. Industry standard 19" width spacing.
- 29. Wiring Block: Punch down terminating equipment used to develop twisted pair cross-connect facilities.

1.04 PRODUCT AVAILABILITY

A. Products with long lead times are to be brought to the attention of the project manager.

1.05 PRODUCT SUBMITTALS

A. See Division 01 Submittals for more requirements

1.06 SUBSTITUTION LIMITATIONS

- A. Equivalent product(s) may be considered for substitution for those products specified, however, the equivalent product(s) must be approved, and show demonstrated and documented equivalence to the product(s) specified. Documentation includes, but is not limited to, product samples, data sheets, and actual test data. The request for product substitution, and supporting documentation, must be submitted to the Project Manager/Designer in writing.
- B. See Division 01 Substitutions for more requirements

1.07 QUALITY ASSURANCE

- A. The Contractor is to conform to requirements of the latest adopted version of the CEC with amendments by local AHJs.
- B. The Contractor is to conform to the latest adopted version of the CBC with amendments by local AHJs.
- C. The Contractor is to obtain and pay for electrical permits, plan review, and inspections from local AHJs.

- D. The Contractor is to furnish products listed by UL or other testing firm acceptable to AHJ.
- E. The Contractor is to conform to requirements of the Service Providers (i.e., electric, telephone, broadband and cable television).

F. Contractor Qualifications:

- 1. The Contractor shall have a minimum of five years' experience in the design, installation, testing, and maintenance of low-voltage systems.
- 2. The Contractor shall maintain a local service facility which stocks spare devices and/or components for servicing systems.
- 3. The Contractor shall have performed successful installation and maintenance of at least three projects similar in scope and size. The Contractor must be able to provide project references for these three projects, including scope of Work, project type, owner/user contact name and telephone number.
- 4. For sections requiring installation personnel to be certified by the manufacturer, the Contractor selected for this project shall provide current certificates for all technicians working on the project.
- 5. The Contractor shall hold and maintain a valid California C-7 or C-10 State Contractors License, and can exhibit validity upon request.
- 6. The Contractor shall provide a list of test equipment proposed for use in verifying the installed integrity of copper and fiber optic cable systems used.
- 7. The Contractor shall provide the resume for the contractor's Project Manager and onsite Installation Supervisor who will be assigned to this project.
- 8. The Contractor shall provide a list of technical product training attended by the contractor's personnel that will install the specified manufacturer system.
- 9. The Contractor shall provide a list of Sub-Contractor(s) who will assist the Contractor in the performance of this work.

1.08 SEQUENCING AND SCHEDULING

- A. For the proper execution of the work, the Contractor shall cooperate with other tradecrafts and contracts as needed.
- B. To avoid installation conflicts, the Contractor shall thoroughly examine the complete set of Contract Documents, and resolve conflicts with Project Manager/Designer prior to installation.
- C. Prior to installation of communications cable to equipment requiring connections, examine the manufacturer's shop drawings, wiring diagrams, product data, and installation instructions. Verify that the electrical characteristics detailed in the Contract Documents are consistent with the electrical characteristics of the actual equipment being installed. When

inconsistencies do occur, the Contractor shall request clarification from Project Manager/Designer.

1.09 SHOP DRAWINGS

A. Shop Drawings: When required by individual Specification Sections, the Contractor shall provide shop drawings which include physical characteristics, electrical characteristics, device layout plans, point-to-point wiring diagrams for all connections, and the like. Refer to individual Specification Sections for additional requirements for the shop drawings.

1.10 WARRANTY

A. The Contractor shall provide an extended manufacturer's warranty on the Backbone and Horizontal Communications systems as specified in other sections of Division 27.

1.11 CLOSE OUT DOCUMENTS

- A. The Contractor shall provide final coordination drawings, with as-built information added, which are to be submitted as record drawings at completion of project.
- B. Record Drawings:
 - 1. Show changes and deviations from the Construction Drawings (including Addendums and change order documents).
 - 2. Show exact routes of pathway facilities and service entrance conduits.
 - 3. Show the exact location of racks, cabinets, mounting frames and the like.
- C. Operation and Maintenance Documentation: Provide copies of certificates of code authority acceptance, product data, guarantees, warranties, installation guides, maintenance guides and the like.
- D. Inspection and/or testing: Submit testing reports for testing that was performed.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Provide like items from one manufacturer, such as wire/cable, jacks, modular plugs, patch panels, equipment connection cords, wall plates, and the like. See individual sections for detailed information.

2.02 MATERIALS

- A. Provide new electrical materials of the type and quality detailed, listed by UL, bearing their label wherever standards have been established. Indicated brand names and catalog numbers are used to establish standards of performance and quality.
- B. Provide material and equipment that is acceptable to AHJ as suitable for the use indicated. For example, provide plenum rated cable in ceilings that are utilized as air return plenums.
- C. Include special features, finishes, accessories, and other requirements as described in the Contract Documents regardless of the item's listed catalog number.
- D. Provide incidentals not specifically mentioned herein or noted on Drawings, but needed to complete the system, in a safe and satisfactory working condition.

PART 3 - EXECUTION

3.01 EXAMINATION

A. Construction Documents:

- 1. Drawings are diagrammatic with symbols representing communications equipment, outlets, accessories, and wiring.
- 2. Examine the entire set of Drawings to avoid conflicts with other systems. Determine the exact route and installation of communications wiring and equipment with conditions of construction.

3.02 INSTALLATION

- A. Install communications equipment completely as directed by manufacturer's installation instructions. Obtain installation instructions from manufacturer prior to rough-in of the communications equipment, and examine the instructions thoroughly. When requirements of the installation instructions conflict with the Contract Documents, request clarification from Project Manager/Designer prior to proceeding with the installation.
- B. Do not install communications equipment in obvious passages, doorways, scuttles, or crawl spaces, which would impede or block the passage's intended usage.
- C. Do not install communications equipment in locations where it would obviously be subject to damage during normal use.

3.03 FIELD QUALITY CONTROL

A. Tests: Conduct tests of equipment and systems to demonstrate compliance with requirements specified in Division 27 & 28. Refer to individual Specification Sections for required tests. Testing documentation is to be included in Closeout Documents.

3.04 CLEANING

- A. Remove all dirt and debris caused by the execution of the work.
- B. Leave the entire communications system installed under this Contract in a clean, dust-free, and proper working order.
- C. Vacuum and clean interiors of new and modified electrical signal and communication equipment enclosures.

END OF SECTION

SECTION 27 05 00 COMMON WORK RESULTS FOR COMMUNICATIONS

PART 1 - GENERAL

1.01 SUMMARY

- A. This section specifies the basic materials and methods for all low voltage pathways installation work included under Division 27 and 28. Where those requirements differ from the requirements of this section, the more stringent shall govern.
- B. This section adds refinements to Division 26 that apply to Communications and extra-low-voltage systems.

1.02 SCOPE

- A. Materials and/or methods for the following.
 - 1. Communication services
 - 2. Grounding
 - 3. Fasteners
 - 4. Hangers and supports
 - 5. Conduits/Backboxes/Raceways
 - 6. Underground
 - 7. Sleeves and penetrations

1.03 SUBMITTALS

A. Submittals shall be done in accordance with District submittal procedures, see Division 01 Submittals for requirements.

1.04 RELATED REQUIREMENTS

- A. Division 07 Thermal and Moisture Protection
- B. Section 09 91 00 Painting
- C. Division 26 Electrical
- D. 27 00 00 Communications Basic Requirements

1.05 REFERENCES

COMMON WORK RESULTS FOR COMMUNICATIONS

27 05 00 - 2

- A. ANSI American Nation Standards Institute
- B. NFPA 70 National Electrical Code
- C. UL Underwriters Laboratory
- D. California Building Code (CBC)
- E. California Electrical Code (CEC)

1.06 WARRANTY

A. Refer to Division 01 -- Warranties

PART 2 - PRODUCTS

2.01 All products used on this project shall bear the label of- and be approved by Underwriters Laboratories unless otherwise approved in writing by District.

2.02 FASTENERS

- A. Mounting hardware and anchors recommended by the manufacturer of any material that shall be mounted to the building or structure.
 - 1. Sheet rock / drywall / wall board: Easy Anchor, toggle bolt, other spread type anchor with load distribution, or approved equivalent.
 - Concrete / cinder block / solid masonry: Expanding compression type lag, expanding compression type bolt, expanding compression type, all-thread with nuts, or approved equivalent.
 - 3. Tile / Stucco / hollow masonry: Toggle bolts or approved equivalent.
 - 4. Wood: Lag screws, wood screws, or approved equivalent.
 - 5. Metal: Beam clamps, sheet metal screws, self-drilling screws or approved equivalent.

2.03 HANGERS AND SUPPORT

- A. D-RINGS
 - 1. Commercial grade
- B. J-HOOKS
 - 1. Commercial grade
 - 2. Colored coded by system:
 - a. No color = Data
 - b. Orange = Fiber optic cables and service provider feeders
 - c. Blue = CCTV, Electronic Access Control, and Intrusion
 - d. Yellow = Clock, Intercom, and Audio-Visual (non-data)
 - e. Green = EMS and lighting controls
 - f. Red = Fire Alarm

2.04 SURFACE RACEWAY

A. The District has standardized the use of Wiremold 800, 2300, 5400 and 5500 series for non-metallic surface raceway.

2.05 CONDUITS AND ACCESSORIES

A. CONDUITS

- 1. See Division 26 for additional requirements.
- 2. For new construction, exposed Fire Alarm pathways to be in red painted conduit.
- 3. All new conduits shall be sized accordingly to achieve a 40% maximum fill ratio with initial cables installed.
- 4. Underground conduits shall be Schedule 40 PVC.

B. INNERDUCT

- 1. Orange corrugated HDPE (High Density Polyethylene) Innerduct shall be used for fiber optic cable protection in interior locations.
- 2. Fabric multi-cell innerduct is approved for underground conduits 2" and larger.

C. FITTINGS:

- 1. See Division 26 for additional requirements.
- 2. Commercial grade.
- 3. Compression type.
- 2. Conduit bodies and any other sharp bend fittings are <u>strictly prohibited for</u> communication Cat6A and fiber optic cables. Appropriate conduit sweeps are required.

D. PULL LINE

1. Minimum 1/8" diameter or larger braided line of polypropylene or continuous fiber polyolefin. The minimum breaking strength of 1/8 in. line is 200 lbs.

E. SLEEVES

- 1. All conduit sleeves shall be of sufficient quantity and size to achieve a 40% maximum fill ratio with initial cables installed.
- 2. Penetrations through rated assemblies to use EZ-Path or an approved equal.

2.06 BACKBOXES AND JUNCTION BOXES

- A. Galvanized one-piece or welded pressed steel type. Boxes for fixtures shall not be less than 4" square and shall be equipped with fixture stud. Boxes shall be at least 2-1/8" deep, 4" square for 1 or 2 gang devices, with device rings. Boxes mounted in wall or ceiling finished with 5/8" gypsum board shall be furnished with 5/8" deep device rings. Provide blank cover for all boxes without fixture or device. 4 11/16 and/or 5" square back boxes may be required for larger cable requirements.
- B. Junction boxes, larger than 8", located indoors shall be hinged, NEMA-1 rated.
- C. Junction boxes, larger than 8", located outdoors, or in wet or damp locations shall be hinged, NEMA-3R.
- D. Provide and install tamper-proof screws for all exterior box lids.
- E. Junction boxes used for Fire Alarm systems are to be red in color with red colored cover plates.

2.07 GROUND BOXES

- A. See Division 26 and below for additional requirements.
- B. Approved manufactures are Jensen, Christy or approved equivalent.
- C. All ground boxes shall have metal traffic-rated lids with permanent factory markings of COMM/COMMUNICATIONS/DATA/SIGNAL/FIRE ALARM.
- D. Minimum size is 17" x 30"
- E. 24"x36" ground boxes are required for 90-degree turns in underground pathway, or 3-way underground pathway connections.
- E. For dedicated AT&T service feeds, the minimum requirement is a 36"x48" Intercept pull-box at service tie-ins. Refer to current AT&T documents/requirements.
- F. For Comcast service feeds the minimum requirement is a 24" x 36" at service tie in; 17"x30" inline ground boxes are acceptable.

2.08 PENETRATION SEALING

A. Firestopping: Provide UL Listed firestopping materials for all penetrations through rated assemblies (walls / floors). See Division 07 for more information.

- B. Draft stopping: Use foam sealant around conduit penetrations (in non-rated assemblies) to prevent passage of air, smoke, and/or toxic gas. See Division 07 for more information.
- C. Weatherproofing: Use weatherproof sealant around conduit penetrations in exterior walls to prevent the intrusion of water. See Division 07 for more information.

2.09 GROUNDING BUS BAR

A. Copper bus bar 2"x10"x1/4" minimum size with stand-off brackets and insulators, predrilled and threaded mounting holes (hole qty. 12 or greater) for equipment grounding lug attachment.

PART 3 - EXECUTION

3.01 COMMUNICATION SERVICES

A. Install inground boxes, conduits, and terminal cabinets per service provider requirements.

3.02 GROUNDING

- A. Ground fittings shall be UL approved for each application and installed and/or connected to system in accordance with current CEC Code requirements.
- B. See Division 26 for additional requirements.
- C. Install grounding bus bar per manufacturer's instructions in each MDF and IDF.

3.03 HANGERS AND SUPPORTS

- A. Install hangers and supports per manufacturer's written instructions.
- B. Hanger spacing shall be 48" or less and within 12" of sleeves and/or junction/back boxes.

3.04 LOW VOLTAGE PATHWAY/RACEWAYS

- A. EMT conduit may be used at following locations (see Division 26 for additional requirements):
 - 1. In dry locations in furred spaces.
 - 2. In partitions other than concrete or solid masonry.
 - 3. In protected exterior locations not exposed to direct weather.
- B. Rigid steel conduit and fittings shall be used for vertical risers and on top of all roofs, overhangs, walkways, canopies, or any other location exposed to direct weather. See Division 26 for additional requirements.
- C. Furnish and install pull lines in all unused (empty) conduits or raceways. All pull lines shall be permanently tagged with identification at both ends.
- D. Install exposed conduits neatly, parallel to or at right angles to structural members. Maintain a minimum of 12 inches of clearance from steam or hot water pipes. All installed strut channel supports should allow for future conduit attachments. The width of strut channel to match the width of the closest attached junction box. See design document details for attachment requirements.
- E. Install j-hooks pathways perpendicular/parallel to building structure no diagonal runs.

- F. Supports: Support conduit with two-hole straps or strut channel where shown in design documents and/or specified. Coordinate supports with architectural details. Secure to wood structure by means of bolts or lag screws, to metal by means of shallow self-tapping screws, to concrete by means of insert or expansion bolts, to brickwork by means of expansion bolts, and to hollow masonry or stucco by means of toggle bolts.
- G. Spacing for all EMT and rigid steel conduit supports shall be as follows, unless otherwise specified in design documents details:
 - 1. Surface conduit spacing and supports and unless otherwise specified or shown on drawing details:
 - a. EMT Size 3/4" to 2" 4' maximum spacing (3 each supports per 10' conduit length) and 12" from each end of conduit at coupling, connector, or 90-degree bend.
 - b. Rigid steel Size 3/4" to 2" 4' maximum spacing (3 each supports per 10' conduit length) and 12" from each end of conduit at coupling, connector, or 90-degree bend.
- H. If conduit is designated for low voltage use, no more than a total of 360 degrees of conduit bend radius will be allowed between pull/junction boxes.
- I. All junction boxes shall be connected to conduits using appropriate connecting hardware (i.e. box connectors).
- J. Clean, prep and paint with existing matching wall color all exposed conduit, junction boxes, channel strut, fittings, and accessories.
- K. Before pulling any conductors into an underground PVC conduit (new or existing), the conduit shall be first be proofed by pulling through a mandrel of a diameter ¼ in. smaller than the conduit inside dia., followed by a swab of the same diameter as the conduit inside diameter.
- L. Non-metallic raceway to be installed with mechanical fasteners only, do not remove adhesive tape backing.

M. Capping

1. Cap conduits with manufactured seals during construction. Swab out conduits before installing wires.

2. Cap all empty conduits below grade and in pull boxes with manufacturer's caps to prevent entrance of debris; attach pull string to cap.

N. Underground Conduit

- 1. Service provider conduits shall be:
 - a. AT&T one ea. 4" (fiber only) or two ea. 4" (fiber and copper)
 - b. Comcast one ea. 2"
- 2. #10 tracer wire or tracer tape is required for all underground Division 27 PVC conduits.

3.05 J-BOXES

- A. Screws shall be used to attach boxes, and must be accurately placed for finish, independently and securely supported by adequate wood backing or by manufactured adjustable channel type heavy-duty box hangers.
 - 1. Boxes shall be attached to metal studs with metal box hangers.
 - 2. Boxes installed in masonry tile or concrete block construction shall be secured with auxiliary plates, bars, or clips, and be grouted in place.
- B. Locate outlets at the following heights unless otherwise noted on Drawings, Specifications, current CBC, or as required to meet ADA handicap requirements.
 - 1. Data Outlets: Same height as electrical outlets
 - 2. Telephone Wall Outlets: Above counter/backsplash height or at electrical switch height.
- C. Boxes shall be placed within 18" of electrical outlets.
- D. For sound control, separate outlets on opposite sides of walls with a 16" minimum separation. Where outlets are less than 16" or in sound rated walls, seal airtight with fire rated sheet putty pads. Fill gap between junction box and wall with acoustical sealant all around perimeter of junction box. Fill conduits larger than 1 1/4" with fire rated putty.
- E. Installation of conduit and outlet boxes in fire-resistive walls, floors, floor-ceiling or roof-ceiling assemblies shall comply with Title 24, Part 2, Section 713.

3.06 GROUND BOXES

A. To be installed per Division 26 requirements.

- B. Provisions are to be made for supporting cables from the box sides (i.e., j-hooks, d-rings)
- C. Install a 36" x 48" ground box for service provider AT&T at service tie-in location and/or a 24" x 36" ground box for service provider Comcast at service tie-in location. If less than 360-degrees of bend, and less than 200 feet in distance, it is acceptable to stub directly into the MPOE. If greater than 360-degrees of bend, or greater than 200 feet in length, then additional in-line ground boxes are required (17" x 30"). See section Part 2 Products for more information.

3.07 CONDUIT PENETRATIONS AND SLEEVES

A. PENETRATIONS:

- a. Where conduit passes through walls, ceilings, or floors, with connection points to junction boxes or raceways mounted to both sides of the same wall, provide a threaded conduit and secured in place with locking rings on both sides.
- b. Where the conduit passes through walls, ceilings, floors with connection points to junction boxes or raceways not mounted to the same wall as the penetration, provide EMT conduit and secured in place with strut channel.

B. SLEEVES

- a. Conduit sleeves are to extend 6" past wall surface and be securely attached to the building structure, with plastic bushings on both ends.
- b. For rated assemblies use EZ-Path sleeves and install per manufacturer's instructions.

C. FIRE STOPPING

Seal all conduit penetrations through fire-rated walls and floors in a manner that is fire
and smoke tight in conformance with current CBC and current CEC. See Division 07 for
more information.

D. DRAFT STOPPING

1. All non-fire-rated walls must be draft-stopped and sealed. Submit method to be used for approval by inspector and/or project manager. Mineral wool is one product that may be used. See Division 07 for more information.

E. WEATHER SEALING

1. All exterior penetrations shall be sealed watertight. The contractor shall use silicone rubber caulk or other approved methods and materials. Submit methods and materials to inspector and/or project manager. See Division 07 for more information.

3.08 CLEANING

- A. Clean all work prior to concealing, painting, and acceptance. Performed in stages if directed.
- B. Clean and repair soiled or damaged painted exposed work before final acceptance in a manner to match adjoining work.
- C. Remove debris from inside and outside of equipment and enclosures.

3.09 PAINTING

A. Paint exposed conduit and j-boxes occurring in finished areas with existing matching wall color. See 09 91 00 – Painting

3.10 FINAL DOCUMENT SUBMITTALS

A. See 27 00 00 for more information.

END OF SECTION

SECTION 27 10 00

STRUCTURED CABLING

PART 1 - GENERAL

1.01 SUMMARY

- A. This section specifies equipment, accessories, materials, installation, configuration, and testing requirements for a complete and operable Structured Cabling communications system. The system shall provide highly reliable and high-performance data communication from main distribution frame (MDF) through each intermediate distribution frame (IDF) to end points requiring fiber optics and/or copper cabling and associated equipment.
- B. This section condenses sections 27 11 00 Communications Equipment Room Fittings, 27 13 00 Communications Backbone Cabling, 27 15 00 Communications Horizontal Cabling and 27 16 00 Communications Connecting Cords into one comprehensive section.

1.02 SCOPE

- A. The work will include but not be limited to the following objectives:
 - 1. Contractor shall furnish and install all required components and accessories as outlined in the design documents for a complete and operable turn-key system.
 - Quality workmanship is a high priority for the District and the Contractor shall be held to a high-level of professional workmanship. Contractors unfamiliar with the District's standards shall familiarize themselves with the standards and requirements prior to beginning work
 - 3. The Contractor shall furnish and install fire-treated ¾" (three quarter inch) plywood for the MDF room (all walls, from floor level to 8' high) and IDF locations (as required or indicated in the design documents).
 - 4. The Contractor shall furnish and install a ground bus bar at the MDF and IDF rooms.
 - 5. The Contractor shall furnish and install all required racks and cabinets.
 - 6. The Contractor shall furnish and install all newly required conduit/raceway.
 - 7. The Contractor shall furnish and install all wire/cable (copper/fiber optic) as required.
 - 8. The Contractor shall terminate all strands of fiber at each fiber enclosure.
 - 9. The Contractor shall furnish and install termination at all end-point equipment (patch panels, jacks, wallplates, enclosures, etc.).
 - 10. The Contractor shall furnish and install all patch cords (copper/fiber).
 - 11. The Contractor shall test and certify (for warranty) the installed cable plant.

1.03 RELATED REQUIREMENTS

- A. Section 01 General Requirements
- B. Section 27 00 00 Communications
- C. Section 27 05 00 Common Work Results for Communication Systems.

1.04 INDUSTRY GUIDELINES AND STANDARDS

- A. California Electrical Code (CEC) Current adopted version
- B. California Building Code (CBC) Current adopted version.
- C. ANSI/TIA-568.0-D Generic Communications Cabling for Customer Premises.
- D. ANSI/TIA-568.1-D Commercial Building Communications Cabling Standard Part 1: General Requirements.
- E. ANSI/TIA 568-C.2 Balanced Twisted-Pair Telecommunications Cabling and Components Standards
- F. ANSI/TIA 568.3-D Optical Fiber Cabling Components Standard
- G. ANSI/TIA-569-D Commercial Building Standard for Telecommunications Pathways and Spaces.
- J. ANSI/TIA-606-B Administration Standard for the Commercial Telecommunications Infrastructure.
- K. ANSI/JSTD-607-C Commercial Building Bonding and Grounding (Earthing) Requirements for Telecommunications.

1.05 QUALIFICATIONS

- A. The contractor shall possess a California C7 or C10 license.
- B. The Contractor or Subcontractor shall have 5 years' documented experience.
- C. The Contractor and installers shall be certified by the product manufacturer.

1.06 SYSTEM REQUIREMENTS

A. Any new installations or existing system modifications shall seamlessly integrate into the site's existing data cable plan system.

1.07 CONTRACTOR "SHOP DRAWINGS" DESIGN REQUIREMENTS

A. See section 27 00 00 for requirements.

1.08 SUBMITTALS

A. See section 27 00 00 for requirements.

1.09 WARRANTY

- A. Refer to Division 01 Warranty section.
- B. See section 27 00 00 for additional requirements.
- C. 25-year manufacturer's warranty/certification required for all copper and fiber cable plant installations.

1.10 CLOSEOUT DOCUMENTS

A. See section 27 00 00 for requirements.

PART 2 - PRODUCTS

2.01 GENERAL

- A. See Appendix A at the end of this document for pre-approved materials.
- B. All products shall be new, unused and without blemishes and shall be of manufacturer's current and standard production.
- C. The Contractor shall confirm all equipment part numbers with the Project Manager or District prior to ordering equipment and updating submittals as required.
- D. The Drawings and Specifications indicate major system components, and may not show every component, connector, module, or accessory that may be required to support the operation specified. The Contractor shall provide all components needed for complete and satisfactory installation and operation.
- E. The Contractor shall install mounting hardware and anchors as recommended by the Manufacturer of the equipment that requires mounting to the building or structure and adhere to all code requirements. See section 27 05 00 for requirements.

F. Product Availability

1. The Contractor, prior to submitting a proposal, shall determine product availability and delivery time, and shall include such considerations into his proposed Contract Time.

2.02 MANUFACTURERS AND PRODUCTS

- A. See Appendix A at the end of this document for pre-approved materials.
- B. Product Substitutions require proof of equivalence and approval by District and/or its representative. Substitution requests to be submitted in writing.
- C. For maintenance and consistency with the existing installed base, data connectivity components (copper and fiber) shall be Superior Essex cable and Ortronics connectivity.

2.03 COPPER/FIBER OPTIC CABLES AND COMPONENTS

- A. All copper cables and components shall be Cat6A rated.
 - 1. Cable to be reduced diameter. White jacket for default cable, Blue jacket for CCTV and Access Control only.
 - 2. Jacks to be keystone style.
 - 3. All cables shall be terminated on keystones at IDF/MDF end. No modular plug terminations are permitted at IDF/MDF locations.

B. Patch cords system/color:

- 1. Data = White color
- 2. AP = Green color (2 ea. req'd at each AP)
- 3. CCTV = Blue color
- 4. Clock/Intercom = Yellow color
- 5. Access Control = Black color
- 6. Fire Alarm/Intrusion Alarm = Red color

C. Patch cord length

- 1. At patch panel 12" typical or no more than 12" slack.
- 2. Station-side patch cords to be 10' in length.

D. Data jacks system/color:

- 1. Data/default = White color
- 2. AP = Green color
- 3. CCTV = Blue color
- 4. Clock/Intercom = Yellow color
- 5. Access Control = Black color
- 6. Fire Alarm/Intrusion Alarm = Red color

E. Fiber Optic Cable:

- 1. Minimum strand count is 24.
- 2. All fiber optic cables and components shall be single-mode OS2 rated.
- 3. Fiber optic cable terminations shall be LC-Duplex style.

PART 3 – EXECUTION

3.01 ACCEPTABLE INSTALLERS

- A. The components making up the structure cabling system shall only be installed by Contractors who are qualified to install, service and maintain the system.
- B. Cable terminations (copper or fiber) shall be installed by manufacturer-certified technicians.
- C. The Contractor (or subcontractor listed at time of bid) must have at least five (5) years' experience before the Bid Opening Date.

3.02 EXAMINATION

- A. The Contractor shall be required to visit the installation site(s) prior to job bidding. The Contractor acknowledges that the failure to visit the site(s) will not relieve the Contractor of the responsibility for accurate bidding and performance of the Work.
- B. The Contractor shall report any discrepancies between the Specifications, Drawings, and Site Examination prior to the Bid Opening Date.

3.03 PREPARATION

- A. The Contractor shall order all required parts and equipment upon receipt of approved product submittals.
- B. The Contractor shall verify the availability of power where required.

3.04 SHOP DRAWINGS

- A. The Contractor shall create "Shop Drawings" per section 27 00 00 for this section.
- B. Submit drawings for review and approval by the Project Manager and/or Designer.

3.05 INSTALLATION

A. ENTRANCE FACILITIES

- Contact telecommunications service provider and arrange for installation of demarcation point, protected entrance terminals, and housing when so directed by service provider.
- 2. Install underground or aerial pathways complying with recommendations in TIA/EIA-569-A, "Entrance Facilities" Article.

B. UNDERGROUND ENTRANCE PATHWAY

1. Install the underground entrance pathway complying with Division 26.

C. EQUIPMENT RACKS, CABINETS, ENCLOSURES AND ACCESSORIES

1. Backboards:

- a. Shall be installed behind the rack or cabinet if the cabinet is not able to be directly attached to two vertical wall studs.
- b. Backboards shall be made of fire retardant or treated materials, squarely cut, and with sanded edges
- c. Backboards shall be a minimum ¾" thick and large enough to secure it to two vertical wall studs.
- d. The "FIRE RATED" stamp shall be visible.
- e. Backboards shall be fastened with ¼" lag bolt and washer, non-recessed, with maximum spacing of 18" into 2 vertical studs. 1-1/2" embedment.
- f. Visible portions (outside of cabinet) of Backboards shall be painted black.
- 2. All data & voice communications racks and cabinets shall be anchored in accordance with manufacturer's specifications, project specifications and/or drawn details, to walls and floors and grounded to building ground grid (not to water pipes etc.).
- 3. Securely mount equipment cabinet and racks to the building structure. A proper quantity of support fasteners shall be utilized. Typically lag bolts for wood installations, wedge anchors for concrete flooring. Submit data sheets for mounting fasteners for approval before installation. Mount equipment per DSA approved drawings/details.
- 4. Equipment cabinet mounted on or against walls will have 3-foot clearance in front of deepest component and accessible to rear for service.
- 5. MDF and all IDFs shall have at least one dedicated 120VAC 20-amp quad-receptacle each.
- 6. Patch Panels: Mount patch panels into the cabinet/rack. Match manufacturer of existing install or if new construction, see Appendix A.
 - a. Patch panel ports shall be grouped by Room and then by System (General Data, Intercom, AP, Other). Label the patch panel with the first port of each Room.
 - b. Exterior devices shall be grouped with the closest adjacent interior space.
 - c. Do not segregate patch panels by system unless specifically directed on the rack elevation.

- 7. Cable Management: Secure the cable bundle(s) to the rack strain relief and cable management behind the patch panels and cross connect block panels. Install horizontal cable management panels and brackets for routing and management of patch cables. Maintain TIA/EIA and BICSI standards on bundling, supporting and bend radius.
- 8. Surge Protected Outlet Strips: Required in MDF rack. Mount surge protected outlet strips per Manufacturer's directions. Refer to details on the Drawings for mounting location.

D. MDF/IDF GROUNDING

- 1. Refer to Section 27 05 00 Grounding for more requirements.
- 2. Locate the grounding bus bar to minimize the length of bonding conductors. Fasten to the wall allowing at least 2-inch (50-mm) clearance behind the grounding bus bar. Connect grounding bus bar with a minimum No. 6 AWG grounding electrode conductor from grounding bus bar to suitable electrical building ground.
- 3. Bond metallic equipment (including ladder rack) to the grounding bus bar, using not smaller than No. 6 AWG equipment grounding conductor.

3.06 WORKMANSHIP

- A. Quality workmanship is a high priority for the District and the Contractor shall be held to a high-level of professional workmanship.
- B. The District' Project or Construction Manager will have the authority to reject Work which does not conform to the Drawings and Specifications.
- C. Comply with the highest industry standards, except when specified requirements indicate more rigid standards or more precise workmanship.
- D. Perform Work with persons experienced and qualified to produce workmanship specified.
- E. Maintain quality control over suppliers and Subcontractors.

3.07 WIRE/CABLE (COPPER/FIBER OPTIC)

- A. Design, layout, size, and plan new cable runs as required.
- B. All wire and cable passing through metalwork shall be sleeved by an approved grommet or bushing.
- C. Conduit/raceway fill shall not exceed 40 percent of interior cross-sectional area.

- D. Neatly dress and tie (Velcro) all cabling.
- E. UTP cabling shall conform to a 6-foot separation requirement from the main power panel, transformers, switchgear and/or starter motors adjacent to the MDF, IDF and termination locations.
- F. Fiber optic cables shall be installed from the MDF to each IDF.
- G. Orange corrugated HDPE (High Density Polythylene) Innerduct shall be used for fiber optic cable protection in all interior locations.
- H. Spicing of fiber optic cable shall be done with fusion splices.
- I. When required copper feeders (minimum 4-pair) are to be installed from the MDF to each IDF.
- J. Maintain proper bend radius for all cable installations.
- K. Do not exceed cable manufacturer's instructions for installation pull load. Any cable damaged by excessive pull force shall be replaced by the installation contractor.
- L. Modular plug terminated link (MPTL) style wiring is acceptable for CCTV with modified single connector permanent link testing.

3.08 LABELING

- A. MDF/IDF Identification number in large font on front of cabinet.
- B. MDF, Fiber Optic LIU Ports IDF number and room number
- C. MDF/IDF, Copper Patch Panel Panels labeled P1, P2, P3, etc., ports labeled with room number.
- D. LAN Outlet IDF number, patch panel number, patch panel port number.
- E. Cables to be labeled both ends with unique identifiers and from/to location identifiers. For Copper Cat cable IDF number, patch panel number, patch panel port number.
- F. T-bar ceilings shall have device labels attached next to the device for ceiling mounted equipment and at the tile for above ceiling equipment with device type and device ID points/IP address.

3.09 CONDUIT AND RACEWAY INSTALLATION

- A. See Division 26 and section 27 05 00 for additional requirements.
- B. Conduit bodies and any other sharp bend fittings are strictly prohibited for communications cabling (copper/fiber).
- C. Install proper radius conduit sweeps where required.

3.10 COMISSIONING PREPARATION

- A. 4 weeks prior to system turn up:
 - a. All jacks in patch panels are to be completely installed.
 - b. A worksheet is to be prepared by the Contractor indicating which switch port is assigned to what system (i.e. general data, intercom, AP, etc.) and the worksheet to be attached to the data switch.
 - c. Data switches are to be delivered to the District by the Contractor and coordinated with the District's Network Engineer.

3.11 FIELD QUALITY CONTROL AND TESTING

- A. All Fiber and Cat6a copper cable installations to be certified by testing with an certified test system that is approved by the manufacturer for warranty certification (typically a Fluke).
- B. Submit the Record Drawings (as-builts) to District for review prior to inspection.
- C. During the formal Test & Inspection (Commissioning) of the system, the Contractor shall have personnel available with tools and equipment to inspect wiring, devices, and system operation.
- D. If corrections are needed, the Contractor will be provided with a Punch-List of all discrepancies. Perform the needed corrections in a timely fashion.
- E. Notify the District when ready to perform a re-inspection of the installation.
- F. Provide 25-year manufacturer's warranty/certification documentation for all copper and fiber cable plant installations.

3.12 CLOSEOUT DOCUMENTS

A. See section 27 00 00 for requirements.

APPENDIX A – Pre-Approved Materials

APPENDIX A – Pre-Approved Materials		
DESCRIPTION	MFG	PART NUMBER
Wall Mount Cabinet 36" (19 RU) 30" Deep	Chatsworth Products	12419-736
Patch Panel 24-port 1-RU (Black)	Ortronics	OR-SPKSU24
Patch Panel Cable Management Support Bar	Ortronics	OR-CMBFR0RU
Faceplate, 2-port (White)	Ortronics	KSFP2-88
Faceplate, 4-port (White)	Ortronics	KSFP4-88
Surface Mount, 2-port (White)	Ortronics	KSSMB2
Faceplate, 1-port Phone Hanger (Stainless)	Ortronics	403STJ1WP
Cat6A Data Jacks (White)	Ortronics	KT2J6A-88
Cat6A Data Jacks (Green)	Ortronics	KT2J6A-45
Cat6A Data Jacks (Blue)	Ortronics	KT2J6A-36
Cat6A Data Jacks (Yellow)	Ortronics	KT2J6A-44
Cat6A Data Jacks (Black)	Ortronics	KT2J6A-00
Cat6A Data Cable, Plenum (White = default)	Superior Essex	6B-246-4B
Cat6A Data Cable, Plenum (Blue = CCTV/Access Control)	Superior Essex	6B-246-2B
Cat6A Data Cable, Indoor/Outdoor (Black)	Superior Essex	6B-272-ER
Cat6A Data Cable, OSP (Black)	Superior Essex	04-001-A8
Cat6A Patch Cord Slim (White) (12" typ.)	Quiktron	576A-RD25-0xx (xx = length)
Cat6A Patch Cord Slim (Blue) (12" typ.)	Quiktron	576A-RD10-0xx (xx = length)
Cat6A Patch Cord Slim (Green) (12" typ.)	Quiktron	576A-RD20-0xx (xx = length)
Cat6A Patch Cord Slim (Yellow) (12" typ.)	Quiktron	576A-RD15-0xx (xx = length)

STRUCTURED CABLING 27 10 00 - 12

Cat6A Patch Cord Slim (Black) (12" typ.)	Quiktron	576A-RD35-0xx (xx = length)
Fiber Optic LIU 1-RU	Ortronics, Q-Series	EQ01U-CHC
Fiber Optic LIU 2-RU	Ortronics, Q-Series	EQ02U-CHC
Fiber Optic LIU 4-RU	Ortronics, Q-Series	EQ04U-CVC
Splice Tray	Ortronics, Q-Series	FST4-F012 w/ mounting bracket WQS-STB
Fiber Optic Adapter	Ortronics, Q-Series	OFP-LCQ24AC
Fiber Optic LC Field Term Connector	Ortronics	205KNF9SA-09
Fiber Optic Cable 24-strand, Single-Mode OS2, Indoor/Outdoor	Superior Essex	W4024K101

END OF SECTION

SECTION 27 21 00

DATA COMMUNICATIONS NETWORK EQUIPMENT

PART I - GENERAL

1.01 SUMMARY

A. This section specifies equipment, accessories, materials, installation, configuration, and testing requirements for a complete and operable data network system. The system shall provide reliable and high-performance data communication throughout the site.

1.02 SCOPE

- A. The work will include but not be limited to the following objectives:
 - 1. Provide, coordinate, and install all required equipment, licenses, and accessories as outlined in the design documents for a complete and operable system.
 - 2. Labor and Materials: The Contractor shall provide and pay for all labor, supervision, materials, accessories, components, equipment, tools, utilities, construction equipment and machinery, transportation, and other facilities and services necessary for the proper execution, operation, and completion of a turn-key system to the District.
 - 3. Data Communications Network Equipment: Includes, but is not limited to:
 - a. Routers
 - b. Firewalls
 - c. Networking Switches
 - d. Wireless Access Points
 - e. Licenses
 - f. Uninterruptible Power Supplies (UPS)
 - 4. Data Switches to be programmed by the District. The Contractor shall coordinate, deliver and pickup Data Switches from the District.

1.03 RELATED REQUIREMENTS

- A. Division 01 General Requirements
- B. Section 27 00 00 Communications
- C. Section 27 05 00 Common Work Results for Communication Systems.
- D. Section 27 10 00 Structured Cabling

1.04 QUALIFICATIONS

- A. Contractor shall be located within 50 miles or less from the project site to support 2-hour response time.
- B. Five years' experience installing data network equipment and systems.

1.05 SYSTEM REQUIREMENTS

A. Any new installations or existing system modifications shall seamlessly integrate into the site's existing data network infrastructure.

1.06 CONTRACTOR "SHOP DRAWINGS" DESIGN REQUIREMENTS

A. See section 27 00 00 for requirements.

1.07 SUBMITTALS

A. See section 27 00 00 for requirements.

1.08 WARRANTY

- A. Refer to Division 01 Warranty section.
- B. See section 27 00 00 for additional requirements.

1.09 CLOSEOUT DOCUMENTS

A. See section 27 00 00 for requirements.

PART 2 - PRODUCTS

2.01 GENERAL

- A. See Appendix A at the end of this document for pre-approved materials.
- B. All products shall be new, unused and without blemishes and shall be of manufacturer's current and standard production.
- C. Drawings and Specifications indicate major system components, and may not show every component, connector, module, or accessory that may be required to support the operation specified. Contractor shall provide all components needed for complete and satisfactory installation/operation.

D. Product Availability

- 1. Contractor, prior to submitting a proposal, shall determine product availability and delivery time, and shall include such considerations into his proposed Contract Time.
- 2. Subject to compliance with these specifications, products and systems included in this section are to be installed as specified by the manufacturer of the system or engineer approved equal.

2.02 EQUIPMENT

- A. The District's preferred manufacturer for:
 - 1. Routers Cisco
 - 2. Firewalls Cisco
 - 3. Networking Switches Cisco
 - 4. Wireless Access Points Cisco
 - 5. UPS N1C
- B. Substitutions require proof of equivalence and approval by District and/or its representative.
- C. All equipment shall be provided with Licenses as required for seamless integration with the District's network infrastructure.

PART 3 - EXECUTION

3.01 ACCEPTABLE INSTALLERS

- A. The equipment shall only be installed by Contractors who are qualified to install and maintain the system.
- B. The Contractor (or subcontractor listed at time of bid) must have at least five (5) years' experience installing data network equipment before the Bid Opening Date.

3.02 EXAMINATION

- A. The Contractor shall be required to visit the installation site(s) prior to bidding for the job. The Contractor acknowledges that the failure to visit the site(s) will not relieve the Contractor of the responsibility for observing and considering those conditions which a Contractor would have observed and considered during a site visit, estimating properly the difficulty and cost of successfully performing the Work or proceeding to perform the Work without additional cost to District.
- B. The Contractor shall report any discrepancies between the Specifications, Drawings, and Site Examination prior to the Bid Opening Date.

3.03 PREPARATION

- A. The Contractor shall verify materials are readily available prior to submitting product submittals and notify the Project Manager of long lead time items.
- B. The Contractor shall order all required parts and equipment only after receipt of approved product submittals from the Project Manager.
- C. The Contractor shall coordinate with the District's Technology Services department for needed IP addresses at least 4 weeks prior to configuration/installation.

3.04 SHOP DRAWINGS

A. The Contractor shall create "Shop Drawings" per section 27 00 00.

3.05 WORKMANSHIP

- A. Quality workmanship is a high priority for the District and the Contractor shall be held to a high-level of professional workmanship.
- B. The District's Project or Construction Manager will have the authority to reject Work which does not conform to the Drawings and Specifications.

- C. Comply with the highest industry standards, except when specified requirements indicate more rigid standards or more precise workmanship.
- D. Perform Work with persons experienced and qualified to produce workmanship specified.
- E. Maintain quality control over suppliers and Subcontractors.

3.06 PATHWAY AND EQUIPMENT INSTALLATION

- A. Install all conduit and pathway per design documents. Refer to 27 05 00 for additional information/requirements.
- B. Install all Cat6A cable per design documents. Refer to 27 15 00 for additional information/requirements.
- C. Equipment to be installed per manufacturer's instructions.
- D. Devices requiring PoE power shall be connected to a PoE switch in the MDF/IDF data rack verify with Technology Services for available PoE power.

3.07 EQUIPMENT COMISSIONING/CONFIGURATION

- A. See 27 10 00, 3.10 COMISSIONING PREPARATION
 - 1. 4 weeks prior to system turn up:
 - a. All jacks in patch panels are to be completely installed.
 - b. A worksheet is to be prepared by the Contractor indicating which switch port is assigned to what system (i.e. general data, intercom, AP, etc.) and the worksheet to be attached to the data switch.
 - c. Data switches are to be delivered to the District by the Contractor and coordinated with the District's Network Engineer.
- B. The Contractor shall pick up the equipment from the District.
- C. The Contractor shall install the equipment and patch in all connections.
- All equipment to be fully configured and tested for functionality by the Contractor prior to District acceptance testing.

3.08 FIELD QUALITY CONTROL AND TESTING

A. Upon reaching substantial completion, perform a complete test and inspection of the system. If found to be installed and operating properly, notify the District of readiness to perform the formal Test & Inspection of the complete system by the District or its representative. Make all adjustments/changes required from District/representative review.

- B. Submit the Record Drawings (as-builts) to District for review prior to inspection.
- C. During the formal Test & Inspection (Commissioning) of the system and have personnel available with tools and equipment to inspect wiring, devices, and system operation.
- D. If corrections are needed, the Contractor will be provided with a Punch-List of all discrepancies. Perform the needed corrections in a timely fashion.
- E. Notify the District when ready to perform a re-inspection of the installation.

3.10 AS-BUILT DRAWINGS

APPENDIX A – Pre-Approved Materials

DESCRIPTION	MFG	PART NUMBER	
Network Switch (48G/4SFP+) (New Install)	Cisco	OFCI	
SFP transceiver	Cisco	OFCI	
DAC Cable (9300 to previous gen switch)	Cisco	OFCI	
UPS (IDF) with network monitoring (1000 VA)	N1C	N1C.L1000	
120VAC input			
UPS (IDF) with network monitoring (1500 VA)	N1C	N1C.L1500	
120VAC input			
1U Rack Mount Monitor	Tripp Lite	B021-000-19-HD2	

END OF APPENDIX A

END OF SECTION

SECTION 27 51 23.50

EDUCATIONAL INTERCOM SYSTEMS

PART I - GENERAL

1.01 SUMMARY

A. This section specifies equipment, accessories, materials, wire, installation, configuration, and testing requirements for a complete and operable Intercom/Public Address/Bell system. This system shall provide the ability to bi-directionally communicate with an individual room, broadcast to defined speaker zone(s) and ring bell tones on a predefined schedule. For sites that utilize the small message board, this section will supplant the use of section 27 53 13 Clock Systems.

1.02 SCOPE

- A. The work will include but not be limited to the following objectives:
 - Labor and Materials: The Contractor shall provide and pay for all labor, supervision, materials, accessories, components, equipment, tools, transportation, and other facilities and services necessary for the proper installation of a turn-key Assistive Listening system to the District.
 - 2. The contractor will coordinate with the District in writing for any needed information (i.e. IP addresses, etc.) 10 business days prior to the date the information is needed.
- B. The District has standardized on Rauland Telecenter U equipment and the installing Contractor shall be Rauland Telecenter authorized.
- C. For existing construction provide and install all components and accessories to modify the existing system while maintaining code compliance and to seamlessly integrate the new components into the existing campus' system. Prior to beginning any work, the Contractor is responsible for identifying any existing system errors or faults and bring these issues to the attention of the District Project Manager.
- D. The Contractor shall be responsible for programming the Rauland Telecenter Intercom System.
- E. The Contractor shall coordinate with site staff for Bell schedule programming requirements.
- F. The Contractor shall review the proposed final system programming, functionality and expectations with the project manager, Architect/Engineer/Designer and District prior to final programming.

- G. After completion of the installation and pretest of the system a satisfactory final test of the entire system shall be made in the presence of the inspector of record (IOR) and District or the District's representative.
- H. The Contractor shall adjust any speaker levels to the appropriate level as determined in system testing.
- I. Existing systems shall remain operable until the new system is accepted and approved by the District or the District's representative.
- J. The Contractor is responsible for user/operator training (maximum 2 hours).
- K. The Contractor shall complete all required project closeout documentation in a timely fashion.

1.03 RELATED REQUIREMENTS

- A. Division 01 General Requirements
- B. Section 27 00 00 Communications
- C. Section 27 05 00 Common Work Results for Communication Systems.
- E. Section 27 10 00 Structured Cabling

1.04 REFERENCES

A. See section 27 00 00 for requirements.

1.05 DEFINITIONS

A. See section 27 00 00 for requirements.

1.06 SYSTEM REQUIREMENTS

A. Any new installations or existing system modifications shall seamlessly integrate into the site's existing intercom system when applicable.

1.07 SUBMITTALS

1.08 CONTRACTOR "SHOP DRAWINGS" DESIGN REQUIREMENTS

- A. See section 27 00 00 for requirements.
- B. Shop drawings are required for this section.

1.09 QUALIFICATIONS

- B. The Contractor shall be located within 50 miles or less from the project site to support 2-hour response time.
- B. Five (5) years' experience installing Rauland Telecenter equipment.
- C. The contractor shall possess a California a C7 or C10 license.
- D. The Contractor or Subcontractor shall be Rauland Telecenter authorized to provide and install equipment with 5 years documented experience.

1.10 CERTIFICATIONS

A. Installers shall be manufacturer certified...

1.11 WORKMANSHIP

- A. Quality workmanship is a high priority for the District and the Contractor shall be held to a high-level of professional workmanship.
- B. The District's Project or Construction Manager will have the authority to reject Work which does not conform to the Drawings and Specifications.
- C. Comply with highest industry standards, except when specified requirements indicate more rigid standards or more precise workmanship.
- D. Perform Work with persons experienced and qualified to produce workmanship specified.
- E. Maintain quality control over suppliers and Subcontractors.
- F. Contractor shall be responsible for scheduling Subcontractors in a timely fashion.

1.12 WARRANTY

- A. Refer to Division 01 Warranty section.
- B. See section 27 00 00 for additional requirements.

1.13 CLOSEOUT DOCUMENTS

PART 2 - PRODUCTS

2.01 GENERAL

- A. The approved manufacturers for the project are:
 - 1. Control unit and related accessories: Rauland Telecenter U
 - 2. Speakers: See Appendix A for different installation types
 - 3. Wire, cable, and accessories: See Appendix A.
- B. All products shall be new, unused and without blemishes and shall be of manufacturer's current and standard production.
- C. Drawings and Specifications indicate major system components, and may not show every component, connector, module, or accessory that may be required to support the operation specified. The Contractor shall provide all components needed for complete and satisfactory installation and operation.

D. Product Availability

- 1. The Contractor, prior to submitting a proposal, shall determine product availability and delivery time, and shall include such considerations into his proposed Contract Time.
- 2. Subject to compliance with these specifications, products and systems included in this section are to be installed as specified by the manufacturer of the system or engineer approved equal.

2.02 EQUIPMENT

- A. See Appendix A at the end of this document for pre-approved materials.
- B. Substitutions require proof of equivalence and prior approval by District and/or its representative before ordering.
- C. Main system components:
 - 1. Rauland Telecenter U IP Campus Controller and software
 - 2. Rauland Telecenter U Auxilliary Input/Output Module
 - 4. Rauland Telecenter U IP Classroom Module
 - 5. Rauland Telecenter U Administrative Console
 - 6. Rauland Telecenter U Program Line Input Module

PART 3 - EXECUTION

3.01 ACCEPTABLE INSTALLERS

- A. The equipment shall only be installed by Contractors who are qualified and certified by the manufacturer to install and maintain the system.
- B. The Contractor (or subcontractor listed at time of bid) must have at least five (5) years' experience installing educational intercom equipment before the Bid Opening Date.

3.02 EXAMINATION

- A. The Contractor shall be required to visit the installation site(s) prior to bidding the job. The Contractor acknowledges that the failure to visit the site(s) will not relieve the Contractor of the responsibility for observing and considering those conditions which a Contractor would have observed and considered during a site visit, estimating properly the difficulty and cost of successfully performing the Work or proceeding to perform the Work without additional cost to District.
- B. The Contractor shall report any discrepancies between the Specifications, Drawings, and Site Examination prior to the Bid Opening Date.

3.03 PREPARATION

- A. The Contractor shall verify materials are readily available prior to submitting product submittals and notify the District's Project Manager of long lead time items.
- B. The Contractor shall order all required parts and equipment only after receipt of approved product submittals from the District's Project Manager.
- C. Submit and receive approval for shop drawings prior to work commencement.

3.04 PATHWAY INSTALLATION

- A. See Division 26 and Section 27 05 00 for requirements and more information.
- B. Existing Construction:
 - 1. Refer to design documents.
 - 2. Surface raceway and components shall be Wiremold 2300.

3.05 EQUIPMENT INSTALLATION

A. Equipment to be wired and installed per manufacturer's instructions.

- B. The Contractor shall coordinate with the District's IT Department if connecting to their network. The Contractor shall provide a spreadsheet of all device MAC addresses indexed by device location to the District IT department to facilitate programming of reserved IP addresses for each device.
- C. Installation shall be in accordance with applicable codes (i.e. NEC, NFPA 72) local and state codes, as shown on the drawings, and as recommended by the major equipment manufacturer.
- D. Perform all Work as indicated in the Drawings and Specifications.
- E. All low voltage cables shall be kept away from power circuits.
- F. Contractor shall provide programming and configuration of the Educational Intercom system for full functionality.
- G. Contractor shall maintain a complete, up-to-date backup of the system configuration.

 Backup shall be maintained throughout the programming period until final Acceptance by

 District. Submit back-ups to District upon Final Acceptance.

3.06 LABELING/SCHEDULES

- A. All labels are to be machine generated black letters on white adhesive label stock that is appropriate for the installation environment (interior/exterior).
- B. Label all standard speaker cables with port ID.
- C. Label all speakers with speaker ID.
- D. Label all IP speakers with MDF/IDF, patch panel and jack numbers.

3.09 CONFIGURATION

A. All equipment to be fully configured and tested for functionality prior to testing.

3.10 FIELD QUALITY CONTROL AND TESTING

- A. Upon reaching substantial completion, perform a complete test and inspection of the system. If found to be installed and operating properly, notify District of your readiness to perform the formal Test & Inspection of the complete system.
- B. Submit the Record Drawings (as-builts) to District for review prior to inspection.

- C. During the formal Test & Inspection (Commissioning) of the system the Contractor shall have personnel available with tools and equipment to inspect wiring, devices, and system operation.
- D. If corrections are needed, the Contractor will be provided with a Punch-List of all discrepancies. Perform the needed corrections in a timely fashion.
- E. Notify the District when ready to perform a re-inspection of the installation.
- F. District or its representative to provide final sign-off for acceptance.

3.11 AS-BUILT DRAWINGS

- A. See section 27 00 00 for requirements.
- B. As-built riser diagram showing all access control components for site.

3.12 TRAINING

- A. For new systems provide 8-hrs end-user training.
- B. For existing system upgrades provide 2-hrs end-user training.

APPENDIX A – Pre-Approved Materials

DESCRIPTION	MFG	PART NUMBER	
IP Campus Controller and software/licenses	Rauland Telecenter U	TCC2000	
Administrative Console	Rauland Telecenter U	TCC2045	
Auxiliary Input/Output Module	Rauland Telecenter U	TCC2033	
Universal Rack Mounting Kit	Rauland Telecenter U	TCC2099	
Program Line Input Module	Rauland Telecenter U	TCC2055	
IP Classroom Module	Rauland Telecenter U	TCC2011B	
8-Ohm 8" Speaker assembly surface (retrofit)	Rauland	Speaker USO880Add: IP Classroom module	
Clock/Speaker surface combo (standard classroom/office retrofit)	Rauland	 Baffle w/ Speaker ACC3011S Backbox ACC3011SBB Message Board TCC3011S Add: IP Classroom module 	
Exterior Speaker (retrofit)	Rauland Lowell Rauland FSR	Backbox: ACC1113 Baffle: ACC1012 Speaker: 8C10MRB Interior Backbox SMWB-4G-WHT - Add: IP Classroom Module (single speaker up to 2W) Add: Wire breakout 603101 (when IP module used)	
UPS (Telecenter Head End)	N1C	N1C.L1500	

END OF APPENDIX END OF SECTION

SECTION 28 20 00

VIDEO SURVEILLANCE

PART I - GENERAL

1.01 SUMMARY

A. This section specifies software, equipment, accessories, wire, materials, installation, configuration, and testing requirements for a complete and operable Video Surveillance system. The system shall provide electronic recording/playback and monitoring of digital cameras installed at the site.

1.02 SCOPE

- A. The work will include but not be limited to the following objectives:
 - Labor and Materials: The Contractor shall provide and pay for all labor, supervision, materials, accessories, wire, components, equipment, tools, transportation, and other facilities and services necessary for the proper installation of a turn-key Video Surveillance system to District.
- A. The CCTV system shall have the following minimum requirements.
 - 1. Cameras
 - a. Weather resistant IP67 or greater (exterior only)
 - b. Network/IP based
 - c. PoE powered
 - d. 5MP or 4K resolution
 - e. H.265 video compression
 - f. Day/night with IR illumination
 - g. Motion detection
 - h. ONVIF
 - 2. Network Video Recorder
 - a. Network/IP based
 - b. H.265 video compression
 - c. RAID 5 or greater
 - d. Record on motion detection
 - e. 30+ day recording
 - C. Software
 - a. PC and Mobile viewing
 - b. View live and recorded video
 - c. Search
 - d. Save video to MP4 format
 - e. Notifications

1.03 RELATED REQUIREMENTS

- A. Division 01 General Requirements
- B. Section 27 00 00 Communications
- C. Section 27 05 00 Common Work Results for Communication Systems.
- C. Section 27 10 00 Structured Cabling

1.04 QUALIFICATIONS

- A. Contractor shall be located within 50 miles or less from the project site to support 2-hour response time.
- B. Five years' experience installing Video Surveillance equipment systems.

1.05 SYSTEM REQUIREMENTS

A. Any new installations or existing system modifications shall seamlessly integrate into the site's existing Video Surveillance system.

1.06 CONTRACTOR "SHOP DRAWINGS" DESIGN REQUIREMENTS

- A. See section 27 00 00 for requirements.
- B. Shop drawings are required for this section

1.07 SUBMITTALS

A. See section 27 00 00 for requirements.

1.08 WARRANTY

- A. Refer to Division 01 Warranty section.
- B. See section 27 00 00 for additional requirements.

1.09 CLOSEOUT DOCUMENTS

PART 2 - PRODUCTS

2.01 GENERAL

- A. See Appendix A at the end of this document for pre-approved materials.
- B. All products shall be new, unused and without blemishes and shall be of manufacturer's current and standard production.
- C. Drawings and Specifications indicate major system components, and may not show every component, connector, module, or accessory that may be required to support the operation specified. Contractor shall provide all components needed for complete and satisfactory installation/operation.

D. Product Availability

- 1. Contractor, prior to submitting a proposal, shall determine product availability and delivery time, and shall include such considerations into his proposed Contract Time.
- 2. Subject to compliance with these specifications, products and systems included in this section are to be installed as specified by the manufacturer of the system or engineer approved equal.

2.02 EQUIPMENT

- A. The District's preferred manufacturer for CCTV equipment is i-Pro (formally Panasonic) for cameras and network video recorders (NVR).
- B. The District's preferred manufacturer for video intercom is Avigilon.
- C. Substitutions require proof of equivalence and approval by District and/or its representative.
- D. All exterior cameras to be IP67 rated or better.

PART 3 - EXECUTION

3.01 ACCEPTABLE INSTALLERS

- A. The equipment shall only be installed by Contractors who are qualified to install and maintain the system.
- B. The Contractor (or subcontractor listed at time of bid) must have at least five (5) years' experience installing Video Surveillance equipment before the Bid Opening Date.

3.02 EXAMINATION

- A. The Contractor shall be required to visit the installation site(s) prior to job bidding. The Contractor acknowledges that the failure to visit the site(s) will not relieve the Contractor of the responsibility for observing and considering those conditions which a Contractor would have observed and considered during a site visit, estimating properly the difficulty and cost of successfully performing the Work or proceeding to perform the Work without additional cost to District.
- B. The Contractor shall report any discrepancies between the Specifications, Drawings, and Site Examination prior to the Bid Opening Date.

3.03 PREPARATION

- A. The Contractor shall verify materials are readily available prior to submitting product submittals and notify the Project Manager of long lead time items.
- B. The Contractor shall order all required parts and equipment only after receipt of approved product submittals from the Project Manager.
- C. The Contractor shall coordinate with the District's Technology Services department for needed IP addresses at least 2 weeks prior to configuration/installation.

3.04 SHOP DRAWINGS

A. The Contractor shall create "Shop Drawings" per section 27 00 00.

3.05 WORKMANSHIP

- A. Quality workmanship is a high priority for the District and the Contractor shall be held to a high-level of professional workmanship.
- B. The District's Project or Construction Manager will have the authority to reject Work which does not conform to the Drawings and Specifications.

- C. Comply with highest industry standards, except when specified requirements indicate more rigid standards or more precise workmanship.
- D. Perform Work with persons experienced and qualified to produce workmanship specified.
- E. Maintain quality control over suppliers and Subcontractors.

3.06 PATHWAY AND EQUIPMENT INSTALLATION

- A. Install all conduit and pathway per design documents. Refer to 27 05 00 for additional information/requirements.
- B. Install all Cat6A cables per design documents. Refer to Section 27 10 00 for additional information/requirements.
- B. Equipment to be installed per manufacturer's instructions.
- C. Devices requiring PoE power shall be connected to a PoE switch in the MDF/IDF data rack verify for adequate PoE power capacity.

3.07 CONFIGURATION

A. Program cameras and/or NVR with network IP address using the following scheme.

Note: x=site octet, contact District Electronics shop for site information.

- 1. Cameras: 10.x.253.101 = Camera 1, 10.x.253.102 = Camera 2...
- 2. NVR: 10.x.253.5
- 3. POE Switch: $10.x.253.10 = 1^{st}$ switch, 10.x.253.11 = 2nd switch...
- 4. Gateway: 10.x.0.1
- 5. Subnet Mask: 255.255.0.0
- B. All equipment to be fully configured and tested for functionality prior to District acceptance testing.

3.08 CAMERA VIEW

A. Adjust view aim, zoom and focus camera to show intended view from design documents.

3.09 FIELD QUALITY CONTROL AND TESTING

- A. Upon completion of network programming and initial view setting, notify District of your readiness to perform the formal camera view review with District or its representative. Make all adjustments required from District review.
- B. Submit the Record Drawings (as-builts) to District for review prior to inspection.

- C. During the formal Test & Inspection (Commissioning) of the system, Contractor to have personnel available with tools and equipment to inspect wiring, devices, and system operation.
- D. If corrections are needed, the Contractor will be provided with a Punch-List of all discrepancies. Perform the needed corrections in a timely fashion.
- E. Notify the District when ready to perform a re-inspection of the installation.

3.10 AS-BUILT DRAWINGS

APPENDIX A - Pre-Approved Materials

VIDEO SURVEILLANCE:

DESCRIPTION	MFG.	PART NUMBER
NVR License (i-PRO Management Software)	i-PRO	WV-ASM300
Network Dome Camera, Indoor, 5MP	i-PRO	WV-S22500-V3L
Network Dome Camera, Outdoor, Vandal Resistant, 5MP	i-PRO	WV-S25500-V3L
Wall Mount Bracket for Dome Camera (Outdoor)	i-PRO	WV-QJB501-W
Ceiling Mount Bracket for Dome Camera (Outdoor)	i-PRO	WV-QJB504-W
Sunshade for Dome Camera (Outdoor)	i-PRO	WV-QSR505-W
Smoked Dome Cover for Dome Camera (Outdoor)	i-PRO	WV-CW7SN
Network Dual Sensor Camera, Outdoor (2x4MP Sensors)	i-PRO	WV-U85402-V2L
Network Multi-Directional Camera, Outdoor (3x4MP Sensors)	i-PRO	WV-S8543L
Network Multi-Directional Camera, Outdoor (4x4MP Sensors)	i-PRO	WV-S8544L
Wall Mount Bracket for Dual Sensor and Multi-Directional Cameras	i-PRO	WV-QWL501-W
Wall Mount Bracket Adapter for Dual Sensor Camera	i-PRO	WV-QSR507-W
Wall Mount Bracket Adapter for Multi-Directional Cameras	i-PRO	WV-QSR503-W
Ceiling Mount Bracket for Multi-Directional Camera		WV-QJB503-W
Pole Mount Bracket for Cameras		WV-QPL500-W
Corner Mount Bracket for Cameras		WV-QCN500-W

END OF APPENDIX A END OF SECTION