


Sequoia Elementary School

Geotechnical Engineering Report

March 6, 2023 | Terracon Project No. NB225114

Prepared for:

Sacramento City Unified School District
5735 47th Avenue
Sacramento, CA 95824



Nationwide
[Terracon.com](https://www.terracon.com)

- Facilities
- Environmental
- Geotechnical
- Materials



50 Goldenland Court, Suite 100
Sacramento, CA 95834
P (916) 928-4690
Terracon.com

March 6, 2023

Sacramento City Unified School District
5735 47th Avenue
Sacramento, CA 95824

Attn: Meredith Collins
P: 916-333-5701
E: merdith@icscm.com

Re: Geotechnical Engineering Report
Sequoia Elementary School
3333 Rosemont Drive
Sacramento, CA
Terracon Project No. NB225114

Dear Ms. Collins:

We have completed the scope of Geotechnical Engineering services for the referenced project in general accordance with Terracon Proposal No. PNB225114 dated November 1, 2022. This report presents the findings of the subsurface exploration and provides geotechnical recommendations concerning earthwork and the design and construction of foundation and floor slabs for the proposed project.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further service, please contact us.

Sincerely,

Terracon

Eric S. Smith, P.E.
Senior Engineer

Noah T. Smith, P.E., G.E.
Principal

Table of Contents


Report Summary	2
Introduction.....	3
Project Description.....	3
Site Conditions	4
Geotechnical Characterization	5
Groundwater Conditions.....	6
Geologic Hazards.....	6
Faulting and Estimated Ground Motions.....	7
Liquefaction	7
Flooding	7
Seismic Considerations.....	7
Corrosivity	9
Geotechnical Overview	10
Soft/ Subgrade Potential	10
Expansive Soils	10
Earthwork	11
Demolition.....	12
Site Preparation.....	12
Subgrade Preparation.....	12
Soil Stabilization.....	13
Fill Material Types	15
Fill Placement and Compaction Requirements	16
Utility Trench Backfill	17
Grading and Drainage.....	18
Earthwork Construction Considerations	19
Construction Observation and Testing	20
Shallow Foundations	20
Design Parameters – Compressive Loads	21
Foundation Construction Considerations	22
Floor Slabs	22
Floor Slab Design Parameters	23
Floor Slab Construction Considerations.....	24
General Comments	24

Figures

GeoModel

Attachments

Exploration and Testing Procedures
Site Location and Exploration Plans
Exploration and Laboratory Results
Supporting Information

Note: This report was originally delivered in a web-based format. **Blue Bold** text in the report indicates a referenced section heading. The PDF version also includes hyperlinks which direct the reader to that section and clicking on the  logo will bring you back to this page. For more interactive features, please view your project online at client.terracon.com.

Report Summary

Topic ¹	Overview Statement ²
Project Description	The project will consist of demolishing an existing building and the construction of a new restroom building at the same location.
Geotechnical Characterization	<p>The site is surfaced with pavement comprised of approximately 2½ inches to 3 inches of asphalt concrete underlain by about 3½ inches to 7 inches of aggregate base. The subgrade conditions encountered in our borings below the pavement generally consisted of medium stiff to hard silty clay and sandy lean clay to the maximum depth explored of 15 feet below the existing ground surface (bgs) in Boring B1 and to a depth of 9½ feet bgs in Boring B2. In Boring B2, the clays were underlain by medium dense to dense poorly graded sand to the maximum depth explored of 15 feet bgs.</p> <p>Groundwater not observed during our exploration</p>
Earthwork	<p>The existing asphalt and aggregate base should be removed and not be reused as structural fill.</p> <p>Cuts and fills on the order of 1 foot or less are anticipated to develop final grades.</p> <p>Existing clays can be selectively used for engineered fill.</p> <p>Clays are sensitive to moisture variation.</p>
Shallow Foundations	<p>Shallow foundations are recommended for building support.</p> <p>Allowable bearing pressure = 2,500 psf</p> <p>Expected settlements: < 1-inch total, < 1/2-inch differential</p>
Pavements	None anticipated as part of this project.

General Comments

This section contains important information about the limitations of this geotechnical engineering report.

1. If the reader is reviewing this report as a pdf, the topics above can be used to access the appropriate section of the report by simply clicking on the topic itself.
2. This summary is for convenience only. It should be used in conjunction with the entire report for design purposes.

Introduction

This report presents the results of our subsurface exploration and Geotechnical Engineering services performed for the proposed restroom building to be located at 3333 Rosemont Drive in Sacramento, CA. The purpose of these services was to provide information and geotechnical engineering recommendations relative to:

- Subsurface soil conditions
- Groundwater conditions
- Site preparation and earthwork
- Foundation design and construction
- Floor slab design and construction

The geotechnical engineering Scope of Services for this project included the advancement of test borings, laboratory testing, engineering analysis, and preparation of this report.

Drawings showing the site and boring locations are shown on the **Site Location** and **Exploration Plan**, respectively. The results of the laboratory testing performed on soil samples obtained from the site during our field exploration are included on the boring logs and/or as separate graphs in the **Exploration Results** section.

Project Description

Our initial understanding of the project was provided in our proposal and was discussed during project planning. A period of collaboration has transpired since the project was initiated, and our final understanding of the project conditions is as follows:

Item	Description
Information Provided	An email request for proposal from Meredith Collins with SCUSD was sent on October 18, 2022 providing a brief project description and preliminary site plan.

Item	Description
Project Description	The project will consist of demolishing an existing building and the construction of a restroom building at the same location.
Proposed Structure	Single-story restroom building with a footprint of approximately 850 square feet.
Building Construction	We anticipate construction will consist of either masonry or wood frame with a slab-on-grade floor.
Finished Floor Elevation	Not provided; we have assumed the finished floor elevation is not more than 1 foot below/above existing grades.
Maximum Loads	<p>Anticipated structural loads were not provided. In the absence of information provided by the design team, we have used the following loads in estimating settlement based on our experience with similar projects.</p> <ul style="list-style-type: none"> ■ Columns: 20 to 40 kips ■ Walls: 1 to 3 kips per linear foot (klf)
Grading	A preliminary grading plan was not available for review at the time this report was prepared. We have assumed 1 foot or less of cut and fill will be required to develop final grade.
Pavements	None anticipated as part of this project.
Building Code	2022 California Building Code (CBC)

Terracon should be notified if any of the above information is inconsistent with the planned construction, especially the grading limits, as modifications to our recommendations may be necessary.

Site Conditions

The following description of site conditions is derived from our site visit in association with the field exploration and our review of publicly available geologic and topographic maps.

Item	Description
Parcel Information	<p>The project is located at 3333 Rosemont Drive in Sacramento, California</p> <p>Assessor Parcel Number (APN): 060-024-0012-0000</p> <p>Latitude and Longitude (approx.): 38.5516°N, 121.3636°W</p> <p>See Site Location</p>

Item	Description
Existing Improvements	The site is developed with an existing elementary school within a residential neighborhood. The planned area of improvement is located in a paved asphalt area in the southern corner of the campus. The school facility is bordered by residences generally to the north, south and east, and Rosemont Drive toward northwest direction.
Current Ground Cover	Asphalt pavement.
Existing Topography	The site is relatively flat with less than 2 feet of topographic relief across the site based on site observations and a review of GoogleEarth.

Geotechnical Characterization

We have developed a general characterization of the subsurface conditions based upon our review of the subsurface exploration, laboratory data, geologic setting, and our understanding of the project. This characterization, termed GeoModel, forms the basis of our geotechnical calculations and evaluation of the site. Conditions observed at each exploration point are indicated on the individual logs. The individual logs can be found in the [Exploration Results](#) and the GeoModel can be found in the [Figures](#) attachment of this report.

As part of our analyses, we identified the following model layers within the subsurface profile. For a more detailed view of the model layer depths at each boring location, refer to the GeoModel.

Model Layer	Layer Name	General Description
1	Surfacing	Approximately 2½ inches to 3 inches of asphalt overlying 3½ inches to 7 inches of aggregate base course.
2	Silty Clay	Medium stiff to stiff silty clay
3	Sandy Lean Clay	Very stiff to hard sandy lean clay
4	Poorly Graded Sand	Medium dense to dense poorly graded sand

Additional borings, auger probes, test pits, or geophysical testing could be performed to obtain more specific subgrade information.

Groundwater Conditions

The boreholes were observed while drilling and after completion for the presence and level of groundwater. Groundwater was not encountered in our test borings while drilling, or for the short duration the borings could remain open. Groundwater was also not encountered in historical borings carried to a maximum depth of 20 feet bgs performed by Terracon within ½ mile northwest of the site. Groundwater data obtained from the State of California's Department of Water Resources SGMA Data Viewer¹ indicates the shallowest historical depth to groundwater in a well (State Well No. 08N06E17H001M) located approximately 1.4 miles southeast of the site is about 73 feet bgs. The noted well is approximately 28 feet higher in elevation than the project site.

Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff and other factors not evident at the time the borings were performed. Therefore, groundwater levels during construction or at other times in the life of the structure may be higher or lower than anticipated. The possibility of groundwater level fluctuations should be considered when developing the design and construction plans for the project.

Geologic Hazards

We have assumed a Geologic Hazard Evaluation has already been performed for the school campus. As a result, we have not included such an evaluation as part of this report. If a new Geologic Hazard Evaluation will be required by the Division of the State Architect (DSA) and the California Geological Survey (CGS) we can prepare a geologic hazard evaluation report for an additional fee.

Geologic maps of the area indicate native subsurface conditions at the site consist of middle to late Pleistocene age Riverbank formation (Q_{r1})² deposits comprised of interbedded layers of silts, clays and granitic sands. The subsurface conditions encountered in our investigation were generally consistent with the mapped geology.

¹ <https://sgma.water.ca.gov/webgis/?appid=SGMADataViewer#gwlevels>

² Gutierrez, C.I. (2011); *Preliminary Geologic Map of the Sacramento 30' X 60' Quadrangle, California*; California Geological Survey (CGS); Preliminary Geologic Maps PGM-11-06; Scale 1:100,000

Faulting and Estimated Ground Motions

The site is located in the Sacramento Valley area of California, which is a relatively moderate seismicity region. The type and magnitude of seismic hazards affecting the site are dependent on the distance to causative faults, the intensity, and the magnitude of the seismic event. Based on a review of all contributing sources using the USGS Unified Hazard Tool, a Mean Earthquake Magnitude of 6.55 may be considered for this site.

Based on the ASCE 7-16 Standard, the peak ground acceleration (PGA_M) at the subject site is approximately 0.291g. Based on the USGS 2014 interactive deaggregations, the PGA at the subject site for a 2% probability of exceedance in 50 years (return period of 2475 years) is expected to be about 0.306g.

Liquefaction

Liquefaction is a mode of ground failure that results from the generation of high pore water pressures during earthquake ground shaking, causing loss of shear strength. Liquefaction is typically a hazard where loose sandy soils or low plasticity fine grained soils exist below groundwater. The California Geological Survey (CGS) has designated certain areas within California as potential liquefaction hazard zones. These are areas considered at a risk of liquefaction-related ground failure during a seismic event, based upon mapped surficial deposits and the presence of a relatively shallow water table. The project site has not yet been evaluated by CGS for liquefaction hazards.

A liquefaction analysis for the restroom building location was not requested nor performed. However, given the subgrade conditions at the site have a geologic age of middle to late Pleistocene and that available data indicates groundwater in the vicinity of the project is deeper than 50 feet bgs, it is our opinion the potential for liquefaction to occur at the site is very low.

Flooding

Based on a review of the Federal Emergency Management Agency (FEMA) National Flood Layer (NFHL), the project site is not located within a mapped flood zone. The project site is in an area with a FEMA Flood Zone X designation, which is an area of minimal flood hazard.

Seismic Considerations

The 2022 California Building Code (CBC) Seismic Design Parameters have been generated using the SEAOC/OSHPD Seismic Design Maps Tool. This web-based software

application calculates seismic design parameters in accordance with ASCE 7-16, and 2022 CBC. The 2022 CBC requires that a site-specific ground motion study be performed in accordance with Section 11.4.8 of ASCE 7-16 for Site Class D sites with a mapped S_s value greater than or equal 0.2.

However, Section 11.4.8 of ASCE 7-16 includes an exception from such analysis for specific structures on Site Class D sites. The commentary for Section 11 of ASCE 7-16 (Page 534 of Section C11 of ASCE 7-16) states that “In general, this exception effectively limits the requirements for site-specific hazard analysis to very tall and or flexible structures at Site Class D sites.” Based on our understanding of the proposed structure, it is our assumption that the exception in Section 11.4.8 applies to the proposed structure. However, the structural engineer should verify the applicability of this exception.

Based on this exception, the spectral response accelerations presented in the following table were calculated using the site coefficients (F_a and F_v) from Tables 1613.2.3(1) and 1613.2.3(2) presented in Section 16.4.4 of the 2022 CBC.

Description	Value
2022 California Building Code (CBC) Site Classification ¹	D (Default) ²
Risk Category	II
Site Latitude ³	39.5516°
Site Longitude ³	-121.3636°
S_s , Spectral Acceleration for a Short Period ⁴	0.497
S_1 , Spectral Acceleration for a 1-Second Period ⁴	0.234
F_a , Site Coefficient	1.403
F_v , Site Coefficient (1-Second Period)	2.132
S_{DS} , Spectral Acceleration for a Short Period	0.464
S_{D1} , Spectral Acceleration for a 1-Second Period	0.333

1. Seismic site soil classification in general accordance with the *2022 California Building Code*, which refers to ASCE 7-16. Site Classification is required to determine the Seismic Design Category for a structure.

Description	Value
<ol style="list-style-type: none"> 2. The Site Classification is based on the upper 100 feet of the site profile defined by a weighted average value of either shear wave velocity, standard penetration resistance, or undrained shear strength in accordance with Section 20.4 of ASCE 7-16 and the CBC. Subsurface explorations at this site were extended to a maximum depth of approximately 15 feet bgs. The site properties below the maximum exploration depth to 100 feet were estimated based on our experience and knowledge of geologic conditions of the general area. Additional deeper exploration or geophysical testing may be performed to confirm the conditions below the current maximum depth of exploration. 3. Provided coordinates represent a point located at the general center of the site. 4. These values were obtained using online seismic design maps and tools provided by SEAOC and OSHPD (https://seismicmaps.org/). 	

Typically, a site-specific ground motion study may reduce construction costs. We recommend consulting with a structural engineer to evaluate the need for such a study and its potential impact on construction costs. Terracon should be contacted if a site-specific ground motion study is desired.

Corrosivity

The following table lists the results of laboratory soluble sulfate, soluble chloride, electrical resistivity, and pH testing. The values may be used to estimate potential corrosive characteristics of the on-site soils with respect to contact with the various underground materials which will be used for project construction.

Corrosivity Test Results Summary

Boring	Sample Depth (feet)	Soil Description	Soluble Sulfate (%)	Soluble Chloride (%)	Electrical Resistivity (Ω-cm)	pH
B-1	1 to 5	Silty Clay	<0.01	<0.01	7,124	7.0

Results of soluble sulfate testing can be classified in accordance with ACI 318 – Building Code Requirements for Structural Concrete. Numerous sources are available to characterize corrosion potential to buried metals using the parameters presented in the previous table. ANSI/AWWA is commonly used for ductile iron, while threshold values for evaluating the effect on steel can be specific to the buried feature (e.g., piling, culverts, welded wire reinforcement, etc.) or agency for which the work is performed. Imported fill materials may have significantly different properties than the site materials noted above and should be evaluated if expected to be in contact with metals used for

construction. Consultation with a NACE certified corrosion professional is recommended for buried metals on the site.

Mapping by the NRCS includes qualitative severity of corrosion to concrete and steel. Based on this source, the near-surface materials are rated "Low" for corrosion to concrete and "low" for corrosion of steel.

Geotechnical Overview

The subject site has geotechnical considerations that will affect the construction and performance of the proposed restroom building that are discussed in this report. The primary geotechnical considerations that have been identified at the subject site that will affect development are the following:

- Soft/Unstable subgrade potential
- Expansive soils

Soft/ Subgrade Potential

Silty clay was noted near the surface in our soil borings. These soils may become unstable when disturbed. During periods of dry weather, these soils may be stable upon initial exposure, however, these soils could become relatively soft and unstable under construction traffic. Furthermore, depending upon site conditions during construction, over-excavation, or stabilization of the subgrade and/or base of over-excavations may be needed to achieve a suitable working surface. Accordingly, we recommend that the owner budget for the possibility that over-excavation and/or stabilization may be required, and contractors be prepared to handle potentially unstable and/or soft conditions. Stabilization may consist of aerating/drying the soil or a composite section of aggregate base and geogrid.

Expansive Soils

Expansive soils are present on this site. This report provides recommendations to help mitigate the effects of soil shrinkage and expansion. However, even if these procedures are followed, some movement and (at least minor) cracking in the structure should be anticipated. The severity of cracking and other damage such as uneven floor slabs will probably increase if modification of the site results in excessive wetting or drying of the expansive soils. Eliminating the risk of movement and distress may not be feasible, but it may be possible to further reduce the risk of movement if significantly more expensive measures are used during construction, such as complete replacement of expansive soils, using a structural slab, or supporting the building on deep foundations.

The near surface, stiff silty clay could become unstable with typical earthwork and construction traffic, especially after precipitation events. The effective drainage should be completed early in the construction sequence and maintained after construction to avoid potential issues. If possible, the grading should be performed during the warmer and drier times of the year. If grading is performed during the winter months, an increased risk for possible undercutting and replacement of unstable subgrade will persist. Additional site preparation recommendations, including subgrade improvement and fill placement, are provided in the **Earthwork** section.

The soils which form the bearing stratum for shallow foundations are plastic and exhibit potential for shrink-swell movements with changes in moisture. Additional areas of localized moderately to highly plastic soils may be present where borings were not performed. Maintaining above optimum moisture conditions in the bearing soils and a minimum dead load pressure on footings should reduce the anticipated swell movements to tolerable levels. The **Shallow Foundations** section addresses support of the building directly bearing on firm native soils. We do not expect significant dead load on the building floor and recommend over-excavation of near-surface clays to reduce the heave potential. The **Floor Slabs** section addresses slab-on-grade support of the building using over-excavation techniques.

The recommendations contained in this report are based upon the results of field and laboratory testing (presented in the **Exploration Results**), engineering analyses, and our current understanding of the proposed project. The **General Comments** section provides an understanding of the report limitations.

Earthwork

We anticipate general grading may consist of cuts on the order of 1 foot or less and that final design grades will remain at the same elevation as existing. Specific site grading information was unavailable at the time this report was prepared. If elevation and site grading differ from our stated assumptions, Terracon should be contacted to determine if additional earthwork recommendations are warranted.

Earthwork is anticipated to include demolition of the existing structure and surrounding pavement, excavations, and engineered fill placement. The following sections provide recommendations for use in the preparation of specifications for the work. Recommendations include critical quality criteria, as necessary, to render the site in the state considered in our geotechnical engineering evaluation for foundations and floor slabs.

Demolition

The proposed restroom building will be constructed within the footprint of the existing building which will need to be demolished, along with pavements and utilities. We recommend existing foundations, pavements, slabs, and utilities be removed from within proposed building footprint and at least 3 feet beyond the outer edge of foundations. This should include removal of any loose backfill found adjacent to existing foundations. If pipes are abandoned in-place, they should be filled completely with lean cement grout, or other suitable material, to avoid collapse in the future. All materials derived from the demolition of existing structure and pavement should be removed from the site and not be allowed for use as on-site fill.

Site Preparation

Following demolition and prior to fill placement, any existing fill encountered should be removed. Fill removal should extend laterally a minimum of 3 feet beyond the limits of proposed building.

Existing underground utilities and/or storm drain lines may be encountered during construction. Unexpected fills or underground substructures or utilities that are encountered should be removed, and the excavation thoroughly cleaned prior to backfill placement and/or construction.

Although no evidence of fill or underground facilities (such as septic tanks, cesspools, basements, and utilities) was observed during the exploration and site reconnaissance, such features could be encountered during construction. If unexpected fills or underground facilities are encountered, such features should be removed, and the excavation thoroughly cleaned prior to backfill placement and/or construction.

Subgrade Preparation

After clearing, any required cuts and over-excavations should be made.

Subgrade soils beneath proposed floor slab should be removed to a depth of 18 inches beneath finished pad grade.

Once cuts and over-excavation operations are complete, the resulting subgrade should be proofrolled with an adequately loaded vehicle such as a fully-loaded tandem-axle dump truck. The proofrolling should be performed under the observation of the Geotechnical Engineer or their representative. Areas excessively deflecting under the proofroll should be delineated and subsequently addressed by the Geotechnical Engineer. Such areas should either be removed or modified by stabilizing as noted in the

following section **Soil Stabilization**. Excessively wet or dry material should either be removed, or moisture conditioned and recompacted.

Excavated material may be stockpiled for use as fill provided it is cleaned of organic material, debris, and any other deleterious material and meets the criteria for general or structural fill specified in the **Fill Material Types** section of this report.

Once proof rolling has been performed, all exposed areas which will receive fill, once properly cleared, should be scarified, moisture conditioned as necessary, and compacted per the compaction requirements in this report. The depth of scarification of subgrade soils and moisture conditioning of the subgrade is highly dependent upon the time of year of construction and the site conditions that exist immediately prior to construction. If construction occurs during the winter or spring, when the subgrade soils are typically already in a moist condition, scarification and compaction may only be 8 inches. If construction occurs during the summer or fall when the subgrade soils have been allowed to dry out deeper, the depth of scarification and moisture conditioning may be as much as 18 inches or more. A representative from Terracon should be present to observe the exposed subgrade and confirm the depth of scarification and moisture conditioning required.

The exposed subgrade below pavements or the existing building will likely be at an elevated moisture content because it has been covered by pavement or a concrete slab and may require some drying to achieve the required compaction.

Following scarification, moisture conditioning, and compaction of the subgrade soils, compacted structural fill soils should then be placed to the proposed design grade and the moisture content and compaction of subgrade soils should be maintained until proposed construction.

Based upon the subsurface conditions determined from the geotechnical exploration, subgrade soils exposed during construction are anticipated to be relatively workable; however, the workability of the subgrade may be affected by precipitation, repetitive construction traffic or other factors. If unworkable conditions develop, workability may be improved by the methods outlined in the **Subgrade Stabilization** section of this report.

Soil Stabilization

Depending on the time of year, precipitation may create excessively moist soils which may require improving the subgrade prior to constructing the proposed development. Methods of subgrade improvement, as described in this section, could include scarification, moisture conditioning and recompaction, removal of unstable materials and replacement with granular fill (with or without geosynthetics), and chemical stabilization. The appropriate method of improvement, if required, would be dependent on factors

such as schedule, weather, the size of area to be stabilized, and the nature of the instability. More detailed recommendations can be provided during construction as the need for subgrade stabilization occurs. Performing site grading operations during warm seasons and dry periods would help reduce the amount of subgrade stabilization required.

If the exposed subgrade is unstable during proofrolling operations, it could be stabilized using one of the methods outlined below.

- **Scarification and Recompaction** - It may be feasible to scarify, dry, and recompact the exposed soils. The success of this procedure would depend primarily upon favorable weather and sufficient time to dry the soils. Stable subgrades likely would not be achievable if the thickness of the unstable soil is greater than about 1 foot or if construction is performed during a period of wet or cool weather when drying is difficult.
- **Aggregate Base** - The use of Caltrans Class II aggregate base is a common procedure to improve subgrade stability. Typical undercut depths would be expected to range from about 12 to 18 inches below finished subgrade elevation. The use of high modulus geosynthetics (i.e., engineering fabric or geogrid) could also be considered after underground work such as utility construction is completed. Prior to placing the fabric or geogrid, we recommend that all below grade construction, such as utility line installation, be completed to avoid damaging the fabric or geogrid. Equipment should not be operated above the fabric or geogrid until one full lift of aggregate base is placed above it. The maximum particle size of granular material placed over geotextile fabric or geogrid should meet the manufacturer's specifications.
- **Chemical Stabilization** - Improvement of subgrades with Portland cement or quicklime could be considered for improving unstable soils. Chemical stabilization should be performed by a pre-qualified contractor having experience with successfully stabilizing subgrades in the project area on similar sized projects with similar soil conditions. The hazards of chemicals blowing across the site or onto adjacent property should also be considered. Additional testing would be needed to develop specific recommendations to improve subgrade stability by blending chemicals with the site soils. Additional testing could include, but not be limited to, determining the most suitable stabilizing agent, the optimum amounts required, and the presence of sulfates in the soil. If this method is chosen to stabilize subgrade soils the actual amount of high calcium quicklime/Portland cement to be used should be determined by Terracon and by laboratory testing at least three weeks prior to the start of grading operations.

Further evaluation of the need and recommendations for subgrade stabilization can be provided during construction as the geotechnical conditions are exposed.

Fill Material Types

Fill required to achieve design grade should be classified as structural fill and general fill. Structural fill is material used below, or within 3 feet of the building or pavements. General fill is material used to achieve grade outside of these areas.

Reuse of On-Site Soil: Excavated on-site soil may be selectively reused as general fill and structural fill. Portions of the on-site soil have an elevated fines content and will be sensitive to moisture conditions (particularly during seasonally wet periods) and may not be suitable for reuse when above optimum moisture content.

Material property requirements for on-site soil for use as general fill and structural fill are noted in the following table:

Property	General Fill	Structural Fill
Composition	Free of deleterious material	Free of deleterious material
Maximum particle size	6 inches (or 2/3 of the lift thickness)	3 inches
Fines content	Not limited	Less than 75% Passing No. 200 sieve
Plasticity	Not limited	Maximum liquid limit of 30 Maximum plasticity index of 10 Expansion Index less than 20
GeoModel Layer Expected to be Suitable ¹	2,3	2,3,4

1. Based on subsurface exploration. Actual material suitability should be determined in the field at time of construction.

Imported Fill Materials: Imported fill materials should meet the following material property requirements. Regardless of its source, compacted fill should consist of approved materials that are free of organic matter and debris. For all import material, the contractor shall submit current verified reports from a recognized analytical laboratory indicating that the import has a “not applicable” (Class S0) potential for sulfate attack based upon current ACI criteria and is “mildly corrosive” to ferrous metal and copper. The reports shall be accompanied by a written statement from the contractor that the laboratory test results are representative of all import material that will be brought to the project.

Soil Type ¹	USCS Classification	Acceptable Parameters (for Structural Fill)
Low Plasticity Cohesive	CL	Plasticity index less than 10 Liquid Limit less than 30 Expansion index less than 20
Granular ²	GW, GM, SW, SM	Less than 50% passing No. 200 sieve

1. Structural and general fill should consist of approved materials free of organic matter and debris and should contain no material larger than 3 inches in greatest dimension. A sample of each material type should be submitted to the Geotechnical Engineer for evaluation at least two weeks prior to use on this site. Additional geotechnical consultation should be provided prior to use of uniformly graded gravel on the site.
2. Caltrans Class II aggregate base may be used for this material. Recycled aggregate base should not be used.

Fill Placement and Compaction Requirements

Compacted native soil and structural and general fill should meet the following compaction requirements.

Item	Structural Fill	General Fill
Maximum Lift Thickness	8 inches or less in loose thickness when heavy, self-propelled compaction equipment is used 4 to 6 inches in loose thickness when hand-guided equipment (i.e. jumping jack or plate compactor) is used	Same as structural fill
Minimum Compaction Requirements ^{1,2}	95% of max. for structural fill below foundations and slabs, within 1 foot of finished pavement subgrade, for aggregate base, and for fills thicker than 5 feet. 90% of max. for all other locations.	90% of max.
Water Content Range ¹	Low plasticity cohesive: +1% to +3% above optimum Granular: -2% to +2% of optimum	As required to achieve min. compaction requirements

Item	Structural Fill	General Fill
	<ol style="list-style-type: none"> 1. Maximum density and optimum water content as determined by the Modified Proctor test (ASTM D 1557). 2. If the granular material is a coarse sand or gravel, or of a uniform size, or has a low fines content, compaction comparison to relative density may be more appropriate. In this case, granular materials should be compacted to at least 70% relative density (ASTM D 4253 and D 4254). Materials not amenable to density testing should be placed and compacted to a stable condition observed full time by the Geotechnical Engineer or representative. 	

Utility Trench Backfill

Any soft or unsuitable materials encountered at the bottom of utility trench excavations should be removed and replaced with structural fill or bedding material in accordance with public works specifications for the utility to be supported. This recommendation is particularly applicable to utility work requiring grade control and/or in areas where subsequent grade raising could cause settlement in the subgrade supporting the utility. Trench excavation should not be conducted below a downward 1:1 projection from existing foundations without engineering review of shoring requirements and geotechnical observation during construction.

On-site materials are considered suitable for backfill of utility and pipe trenches from 1 foot above the top of the pipe to the final ground surface, provided the material is free of organic matter and deleterious substances. Where trenches are placed beneath slabs or footings, the backfill should satisfy the gradation and Atterberg limit requirements of structural engineered fill discussed in this report.

Trench backfill should be mechanically placed and compacted as discussed earlier in this report. Compaction of initial lifts should be accomplished with hand-operated tampers or other lightweight compactors. Flooding or jetting for placement and compaction of backfill is not recommended.

All trench excavations should be made with sufficient working space to permit construction including backfill placement and compaction. If utility trenches are backfilled with relatively clean granular material, they should be capped with at least 18 inches of cementitious flowable fill or cohesive fill in non-pavement areas to reduce the infiltration and conveyance of surface water through the trench backfill. Attempts should also be made to limit the amount of fines migration into the clean granular material. Fines migration into clean granular fill may result in unanticipated localized settlements over a period of time. To help limit the amount of fines migration, Terracon recommends the use of a geotextile fabric that is designed to prevent fines migration in areas of contact between clean granular material and fine-grained soils. Terracon also recommends that clean granular fill be tracked or tamped in place where possible in

order to limit the amount of future densification which may cause localized settlements over time.

For low permeability subgrades, utility trenches are a common source of water infiltration and migration. Utility trenches penetrating beneath the building should be effectively sealed to restrict water intrusion and flow through the trenches, which could migrate below the building. The trench should provide an effective trench plug that extends at least 5 feet from the face of the building exterior. The plug material should consist of cementitious flowable fill or low permeability clay. The trench plug material should be placed to surround the utility line. If used, the clay trench plug material should be placed and compacted to comply with the water content and compaction recommendations for structural fill stated previously in this report.

Grading and Drainage

All grades must provide effective drainage away from the building during and after construction and should be maintained throughout the life of the structure. Water retained next to the structure can result in soil movements greater than those discussed in this report. Greater movements can result in unacceptable differential slab and/or foundation movements and cracked slabs. The roof should have gutters/drains with downspouts that discharge onto splash blocks a distance of at least 10 feet from the building, onto pavements, or are tied to tight lines that discharge into a storm drain system.

Exposed ground should be sloped and maintained at a minimum 5 percent away from the structure for at least 10 feet beyond the perimeter of the structure. If a minimum 5 percent slope cannot be achieved due to site grades, a minimum 2½ percent slope could be used provided pavement or hardscape surrounds and extends to the structure, or a subdrain could be installed around the perimeter of the foundations that carries water away from the structure. Locally, flatter grades may be necessary to transition ADA access requirements for flatwork. After structure construction have been completed, final grades should be verified to document effective drainage has been achieved. Grades around the structure should also be periodically inspected and adjusted, as necessary, as part of the structure's maintenance program. Where paving or flatwork abuts the structure, a maintenance program should be established to effectively seal and maintain joints and prevent surface water infiltration.

Any planters and bio-swales located within 10 feet of the structure should be self-contained or lined with an impermeable membrane to prevent water from accessing subgrade soils below the structure. Sprinkler mains and spray heads should be located a minimum of 5 feet away from the foundation lines.

Implementation of adequate drainage for this project can affect the surrounding developments. Consequently, in addition to designing and constructing drainage for this

project, the effects of site drainage should be taken into consideration for the planned structures on this property, the undeveloped portions of this property, and surrounding sites. Extra care should be taken to ensure drainage from adjacent areas do not drain onto the project site or saturate the construction area.

Earthwork Construction Considerations

Shallow excavations for the proposed structure are anticipated to be accomplished with conventional construction equipment. Upon completion of filling and grading, care should be taken to maintain the subgrade water content prior to construction of grade-supported improvements such as floor slabs and pavements. Construction traffic over the completed subgrades should be avoided to the extent practical. The site should also be graded to prevent ponding of surface water on the prepared subgrades or in excavations. Water collecting over or adjacent to construction areas should be removed. If the subgrade should become desiccated, saturated, or is disturbed, the affected material should be removed, or the materials should be scarified, moisture conditioned, and recompacted prior to construction.

We recommend that the earthwork portion of this project be completed during extended periods of dry weather if possible. If earthwork is completed during the wet season (typically November through April) it may be necessary to take extra precautionary measures to protect subgrade soils. Wet season earthwork operations may require additional mitigation measures beyond that which would be expected during the drier summer and fall months. This could include ground stabilization utilizing chemical treatment of the subgrade, diversion of surface runoff around exposed soils, and draining of ponded water on the site. Once subgrades are established, it may be necessary to protect the exposed subgrade soils from construction traffic.

As a minimum, excavations should be performed in accordance with OSHA 29 CFR, Part 1926, Subpart P, "Excavations" and its appendices, and in accordance with any applicable local and/or state regulations. Stockpiles of soil, construction materials, and construction equipment should not be placed near trenches or excavations. ***The Contractor is responsible for maintaining the stability of adjacent structures during construction.***

Construction site safety is the sole responsibility of the contractor who controls the means, methods, and sequencing of construction operations. Under no circumstances shall the information provided herein be interpreted to mean Terracon is assuming responsibility for construction site safety or the contractor's activities; such responsibility shall neither be implied nor inferred.

Excavations or other activities resulting in ground disturbance have the potential to affect adjoining properties and structures. Our scope of services does not include review of available final grading information or consider potential temporary grading performed

by the contractor for potential effects such as ground movement beyond the project limits. A preconstruction/ precondition survey should be conducted to document nearby property/infrastructure prior to any site development activity. Excavation or ground disturbance activities adjacent or near property lines should be monitored or instrumented for potential ground movements that could negatively affect adjoining property and/or structures.

Construction Observation and Testing

The earthwork efforts should be observed by the Geotechnical Engineer (or others under their direction). Observation should include documentation of adequate removal of surficial materials (debris, pavements, and pre-existing fill if encountered), evaluation and remediation of existing fill materials, as well as proofrolling and mitigation of unsuitable areas delineated by the proofroll.

Each lift of compacted fill should be tested, evaluated, and reworked, as necessary, as recommended by the Geotechnical Engineer prior to placement of additional lifts. Each lift of fill should be tested for density and water content at a frequency of at least one test for every 500 square feet in the building area. Where not specified by local ordinance, one density and water content test should be performed for every 50 linear feet of compacted utility trench backfill and a minimum of one test performed for every 12 vertical inches of compacted backfill.

In areas of foundation excavations, the bearing subgrade should be evaluated by the Geotechnical Engineer. If unanticipated conditions are observed, the Geotechnical Engineer should prescribe mitigation options.

In addition to the documentation of the essential parameters necessary for construction, the continuation of the Geotechnical Engineer into the construction phase of the project provides the continuity to maintain the Geotechnical Engineer's evaluation of subsurface conditions, including assessing variations and associated design changes.

Shallow Foundations

The proposed building may be supported by spread footings. If the site has been prepared in accordance with the requirements noted in [Earthwork](#), the following design parameters are applicable for shallow foundations.

Design Parameters – Compressive Loads


Item	Description
Maximum Net Allowable Bearing Pressure ^{1, 2}	2,500 psf
Required Bearing Stratum ³	Undisturbed native soil
Minimum Foundation Dimensions	Per CBC 1809.7
Maximum Foundation Dimensions	4 feet
Passive Resistance ^{4, 8} (Equivalent fluid pressures)	300 pcf (native soils)
Sliding Resistance ^{5, 8}	130 pcf allowable cohesion (native clay)
Minimum Embedment below Finished Grade ⁶	18 inches
Estimated Total Settlement from Structural Loads ²	Less than about 1 inch
Estimated Differential Settlement ^{2, 7}	About 1/2 of total settlement

1. The maximum net allowable bearing pressure is the pressure in excess of the minimum surrounding overburden pressure at the footing base elevation. This bearing pressure can be increased by 1/3 for transient loads unless those loads have been factored to account for transient conditions. Values assume that exterior grades are no steeper than 20% within 10 feet of structure.
2. Values provided are for maximum loads noted in **Project Description**. Additional geotechnical consultation will be necessary if higher loads are anticipated.
3. Unsuitable or soft soils should be over-excavated and replaced per the recommendations presented in **Earthwork**.
4. Use of passive earth pressures require the sides of the excavation for the spread footing foundation to be nearly vertical and the concrete placed neat against these vertical faces or that the footing forms be removed, and compacted structural fill be placed against the vertical footing face. Assumes no hydrostatic pressure.
5. Can be used to compute sliding resistance where foundations are placed on suitable soil/materials for fine-grained materials, lateral resistance using cohesion should not exceed 1/2 the dead load.
6. Embedment necessary to minimize the effects of seasonal water content variations.
7. Differential settlements are noted for equivalent-loaded foundations and bearing elevation as measured over a span of 50 feet.
8. Passive Resistance and Sliding Resistance may be combined to resist sliding provided the Passive Resistance is reduced by 50 percent.

Foundation Construction Considerations

As noted in **Earthwork**, the footing excavations should be evaluated under the observation of the Geotechnical Engineer. The base of all foundation excavations should be free of water and loose soil, prior to placing concrete. Concrete should be placed soon after excavating to reduce bearing soil disturbance. Care should be taken to prevent wetting or drying of the bearing materials during construction. Excessively wet or dry material or any loose/disturbed material in the bottom of the footing excavations should be removed/reconditioned before foundation concrete is placed.

If unsuitable bearing soils are observed at the base of the planned footing excavation, the excavation should be extended deeper to suitable soils, and the footings could bear directly on these soils at the lower level or on lean concrete backfill placed in the excavations. The lean concrete replacement zone is illustrated on the following sketch.



To ensure foundations have adequate support, special care should be taken when footings are located adjacent to trenches. The bottom of such footings should be at least 1 foot below an imaginary plane with an inclination of 1.5 horizontal to 1.0 vertical extending upward from the nearest edge of the adjacent trench.

Floor Slabs

Design parameters for floor slabs assume the requirements for **Earthwork** have been followed. Specific attention should be given to positive drainage away from the structure and positive drainage of the floor slab support course beneath the floor slab.

The subgrade soils are comprised of expansive clays exhibiting the potential to shrink/swell with variations in water content. Construction of the floor slab and revising site drainage creates the potential for gradual increased water contents within the clays. Increases in water content will cause the clays to swell and damage the floor slab. To reduce the potential effects of the expansive clays on the building floor slab, at least the upper 18 inches of subgrade soils below the floor slab should consist of an approved granular structural fill material.

Due to the potential for significant moisture fluctuations of subgrade material beneath floor slab supported at-grade, the Geotechnical Engineer should evaluate the material within 12 inches of the bottom of the granular structural fill zone immediately prior to placement of additional fill. Soils below the specified water contents within this zone should be moisture conditioned or replaced with structural fill as stated in our **Earthwork** section.

Floor Slab Design Parameters

Item	Description
Floor Slab Support¹	4 inches of ¾ inch free draining crushed rock ³ overlying 18 inches of granular structural fill. Subgrade compacted to the recommendations in Earthwork
Estimated Modulus of Subgrade Reaction²	75 pounds per square inch per inch (psi/in) for point loads

1. Floor slabs should be structurally independent of building footings or walls to reduce the possibility of floor slab cracking caused by differential movements between the slab and foundation.
2. Modulus of subgrade reaction is an estimated value based upon our experience with the subgrade condition, the requirements noted in **Earthwork**, and the floor slab support as noted in this table. It is provided for point loads. For large area loads the modulus of subgrade reaction would be lower.
3. Free-draining granular material should have less than 5% fines (material passing the No. 200 sieve). Other design considerations such as cold temperatures and condensation development could warrant more extensive design provisions.

The use of a vapor retarder should be considered beneath concrete slabs on grade covered with wood, tile, carpet, or other moisture sensitive or impervious coverings, when the project includes humidity-controlled areas, or when the slab will support equipment sensitive to moisture. When conditions warrant the use of a vapor retarder, the slab designer should refer to ACI 302 and/or ACI 360 for procedures and cautions regarding the use and placement of a vapor retarder.

Saw-cut contraction joints should be placed in the slab to help control the location and extent of cracking. For additional recommendations, refer to the ACI Design Manual. Joints or cracks should be sealed with a waterproof, non-extruding compressible compound specifically recommended for heavy duty concrete pavement and wet environments.

Where floor slabs are tied to perimeter walls or turn-down slabs to meet structural or other construction objectives, our experience indicates differential movement between the walls and slabs will likely be observed in adjacent slab expansion joints or floor slab cracks beyond the length of the structural dowels. The Structural Engineer should account for potential differential settlement through use of sufficient control joints, appropriate reinforcing, or other means.

Floor Slab Construction Considerations

Finished subgrade, within and for at least 10 feet beyond the floor slab, should be protected from traffic, rutting, or other disturbance and maintained in a relatively moist condition until the floor slab is constructed. If the subgrade should become damaged or desiccated prior to construction of the floor slab, the affected material should be removed, and structural fill should be added to replace the resulting excavation. Final conditioning of the finished subgrade should be performed immediately prior to placement of the floor slab support course.

The Geotechnical Engineer should observe the condition of the floor slab subgrades immediately prior to placement of the floor slab support course, reinforcing steel, and concrete. Attention should be paid to high traffic areas that were rutted and disturbed earlier, and to areas where backfilled trenches are located.

General Comments

Our analysis and opinions are based upon our understanding of the project, the geotechnical conditions in the area, and the data obtained from our site exploration. Variations will occur between exploration point locations or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Terracon should be retained as the Geotechnical Engineer, where noted in this report, to provide observation and testing services during pertinent construction phases. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or

identification or prevention of pollutants, hazardous materials, or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

Our services and any correspondence are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in accordance with generally accepted geotechnical engineering practices with no third-party beneficiaries intended. Any third-party access to services or correspondence is solely for information purposes to support the services provided by Terracon to our client. Reliance upon the services and any work product is limited to our client and is not intended for third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly affect excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing. Site safety and cost estimating including excavation support and dewatering requirements/design are the responsibility of others. Construction and site development have the potential to affect adjacent properties. Such impacts can include damages due to vibration, modification of groundwater/surface water flow during construction, foundation movement due to undermining or subsidence from excavation, as well as noise or air quality concerns. Evaluation of these items on nearby properties are commonly associated with contractor means and methods and are not addressed in this report. The owner and contractor should consider a preconstruction/precondition survey of surrounding development. If changes in the nature, design, or location of the project are planned, our conclusions and recommendations shall not be considered valid unless we review the changes and either verify or modify our conclusions in writing. This report should not be used after 3 years without written authorization from Terracon.

Geotechnical Engineering Report

Sequoia Elementary School | Sacramento, CA
March 6, 2023 | Terracon Project No. NB225114




Figures

Contents:

GeoModel

Geomodel



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

Model Layer	Layer Name	General Description
	Surfacing	Approximately 2 1/2 to 3 inches of asphalt overlying 3 1/2 to 7 inches of aggregate base course.
2	Silty Clay	Medium stiff to stiff silty clay.
3	Sandy Lean Clay	Very stiff to hard sandy lean clay.
	Poorly Graded Sand	Medium dense to dense poorly graded sand.

LEGEND

- Asphalt
- Aggregate Base Course
- Sandy Lean Clay
- Silty Clay
- Poorly-graded Sand

NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.

Geotechnical Engineering Report

Sequoia Elementary School | Sacramento, CA
March 6, 2023 | Terracon Project No. NB225114



Attachments

Exploration and Testing Procedures

Field Exploration

Number of Borings	Approximate Boring Depth (feet)	Location
2	15	Proposed Building Area

Boring Layout and Elevations: Terracon personnel provided the boring layout using handheld GPS equipment (estimated horizontal accuracy of about ± 10 feet) and referencing existing site features. Approximate ground surface elevations were obtained by interpolation from Google Earth. If elevations and a more precise boring layout are desired, we recommend the exploration locations be surveyed.

Subsurface Exploration Procedures: We advanced the borings with track-mounted rotary drill rig using continuous flight augers (hollow stem). Four samples were obtained in the upper 10 feet of each boring and at intervals of 5 feet thereafter. In the split-barrel sampling procedure, a standard 2-inch outer diameter split-barrel sampling spoon was driven into the ground by a 140-pound automatic hammer falling a distance of 30 inches. The number of blows required to advance the sampling spoon the last 12 inches of a normal 18-inch penetration is recorded as the Standard Penetration Test (SPT) resistance value. A 3-inch O.D. split-barrel sampling spoon with 2.5-inch I.D. lined sampler was used for sampling. For safety purposes, all borings were backfilled with bentonite and surfaces were capped with cold-patch asphalt after their completion.

We also observed the boreholes while drilling and at the completion of drilling for the presence of groundwater. Groundwater was not observed at these times in the boreholes.

The sampling depths, penetration distances, and other sampling information was recorded on the field boring logs. The samples were placed in appropriate containers and taken to our soil laboratory for testing and classification by a Geotechnical Engineer. Our exploration team prepared field boring logs as part of the drilling operations. These field logs included visual classifications of the materials observed during drilling and our interpretation of the subsurface conditions between samples. Final boring logs were prepared from the field logs. The final boring logs represent the Geotechnical Engineer's interpretation of the field logs and include modifications based on observations and tests of the samples in our laboratory.

Laboratory Testing

The project engineer reviewed the field data and assigned laboratory tests. The laboratory testing program included the following types of tests:

- Moisture Content
- Dry Unit Weight
- Atterberg Limits
- Sieve Analysis
- Unconfined Compression Test

The laboratory testing program often included examination of soil samples by an engineer. Based on the results of our field and laboratory programs, we described and classified the soil samples in accordance with the Unified Soil Classification System.

Site Location and Exploration Plans


Contents:

Site Location Plan

Exploration Plan

Note: All attachments are one page unless noted above.

Site Location



Exploration Plan



Exploration and Laboratory Results

Contents:

Boring Logs (B-1 and B-2)
Atterberg Limits
Unconfined Compression Test
Corrosivity

Note: All attachments are one page unless noted above.

Boring Log No. B-1

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 38.5517° Longitude: -121.3638° Depth (Ft.) Elevation: 46 (Ft.) +/-	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	HP (tsf)	Unconfined Compressive Strength (tsf)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	
											LL-PL-PI	Percent Fines
1	ASPHALT	0.3, approximately 3 inches in thickness 0.6, approximately 3 inches in thickness	45.75 45.42		Hand							
2	AGGREGATE BASE COURSE	approximately 7 inches in thickness SILTY CLAY (CL-ML) , brown, medium stiff				1-5-5		0.92	12.2	105		
						500 psi						
3	SANDY LEAN CLAY (CL)	brown with orange, very stiff to hard	5			3-13-22	4.5 (HP)		18.9	92		73
						5-11-23	4.5 (HP)		21.0	102		
			10			5-10-18	4.5 (HP)		20.2	99		
						7-17-35	4.5 (HP)		17.9	108		
		Boring Terminated at 15 Feet	15									

<p>See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations.</p> <p>Notes Elevation Reference: Elevations estimated from Google Earth Pro</p>	<p>Water Level Observations Groundwater not encountered</p> <p>Drill Rig D-50 track</p> <p>Hammer Type Automatic</p> <p>Driller Terracon Lodi</p> <p>Logged by Brian Turner</p> <p>Boring Started 01-06-2023</p> <p>Boring Completed 01-06-2023</p>
<p>Advancement Method 6" Hollow Stem Auger</p> <p>Abandonment Method Boring backfilled with Auger Cuttings Surface capped with asphalt</p>	


Boring Log No. B-2

Model Layer	Graphic Log	Location: See Exploration Plan Latitude: 38.5517° Longitude: -121.3636°	Depth (Ft.)	Elevation: 46 (Ft.) +/-	Water Level Observations	Sample Type	Field Test Results	HP (tsf)	Unconfined Compressive Strength (tsf)	Water Content (%)	Dry Unit Weight (pcf)	Atterberg Limits	
												LL-PL-PI	Percent Fines
1	ASPHALT	ASPHALT, approximately 2.5 inches in thickness	0.2	45.79									
2	AGGREGATE BASE COURSE	AGGREGATE BASE COURSE, approximately 3.5 inches in thickness	0.5	45.5			7-8-7			12.9	107	22-16-6	
	SILTY CLAY (CL-ML)	SILTY CLAY (CL-ML), brown, stiff					2-3-13	1.0 (HP)		18.3	76		76
3	SANDY LEAN CLAY (CL)	SANDY LEAN CLAY (CL), brown, very stiff, weak cementation	4.5	41.5			6-14-21	4.5 (HP)		21.0	98		
	SANDY LEAN CLAY (CL)	SANDY LEAN CLAY (CL), brown, very stiff, weak cementation					3-9-14	4.5 (HP)		22.5	88		
4	POORLY GRADED SAND (SP)	POORLY GRADED SAND (SP), trace gravel, fine to medium grained, subrounded, brown, medium dense to dense, gravel up to 2 inches in dimension	9.5	36.5			6-12-17			5.5	92		
	POORLY GRADED SAND (SP)	POORLY GRADED SAND (SP), trace gravel, fine to medium grained, subrounded, brown, medium dense to dense, gravel up to 2 inches in dimension					8-14-50			22.8	96		
Boring Terminated at 15 Feet			15.0	31									

<p>See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations.</p> <p>Notes Elevation Reference: Elevations estimated from Google Earth Pro</p>	<p>Water Level Observations Groundwater not encountered</p> <p>Advancement Method 6" Hollow Stem Auger</p> <p>Abandonment Method Boring backfilled with Auger Cuttings Surface capped with asphalt</p>	<p>Drill Rig D-50 track</p> <p>Hammer Type Automatic</p> <p>Driller Terracon Lodi</p> <p>Logged by Brian Turner</p> <p>Boring Started 01-06-2023</p> <p>Boring Completed 01-06-2023</p>
--	---	---


Atterberg Limit Results

ASTM D4318




	Boring ID	Depth (Ft)	LL	PL	PI	Fines	USCS	Description
●	B-2	1 - 2.5	22	16	6		CL-ML	SILTY CLAY

Unconfined Compression Test ASTM D2166



Boring ID	Depth (Ft)	Sample type	LL	PL	PI	Fines (%)	Description
B-1	1 - 2.5	CARS					SILTY CLAY

Specimen Failure Mode	Specimen Test Data
-----------------------	--------------------



Failure Mode: Shear (dashed)

Moisture Content (%)	12.2
Dry Density (pcf)	105
Diameter (in.)	1.95
Height (in.)	4.20
Height / Diameter Ratio	2.15
Calculated Saturation (%)	54.45
Calculated Void Ratio	0.61
Assumed Specific Gravity	2.7
Failure Strain (%)	3.81
Unconfined Compressive Strength (tsf)	0.92
Undrained Shear Strength (tsf)	0.46
Strain Rate (in/min)	
Remarks:	

CHEMICAL LABORATORY TEST REPORT

Project Number: NB225114

Service Date: 01/17/23

Report Date: 01/20/23



10400 State Highway 191

Midland, Texas 79707

432-684-9600

Client	Project
Sacramento City Unified School District 5735 47th Avenue Sacramento, CA 95824	Sequoia Elementary School 3333 Rosemont Drive Sacramento, CA

<i>Sample Location</i>	<u>B-1</u>
<i>Sample Depth (ft.)</i>	<u>1-5</u>
pH Analysis, ASTM - G51-18	<u>7.0</u>
Water Soluble Sulfate (SO4), ASTM C 1580 (%)	<u>< 0.01</u>
Sulfides, ASTM - D4658-15, (mg/kg)	<u>nil</u>
Chlorides, ASTM D 512 , (%)	<u>0.01</u>
RedOx, ASTM D-1498, (mV)	<u>+554</u>
Total Salts, ASTM D1125-14, (mg/kg)	<u>711</u>
Resistivity, ASTM G187, (ohm-cm)	<u>7,124</u>

Analyzed By: *Zach Robertson*
Zach Robertson
Engineering Technician III

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.








Supporting Information

Contents:

General Notes
Unified Soil Classification System

Note: All attachments are one page unless noted above.

General Notes

Sampling	Water Level	Field Tests
 Modified California Ring Sampler  Shelby Tube  Grab Sample	 Water Level Initially Encountered  Water Level After a Specified Period of Time  Water Level After a Specified Period of Time  Cave In Encountered Water levels indicated on the soil boring logs are the levels measured in the borehole at the times indicated. Groundwater level variations will occur over time. In low permeability soils, accurate determination of groundwater levels is not possible with short term water level observations.	N Standard Penetration Test Resistance (Blows/Ft.) (HP) Hand Penetrometer (T) Torvane (DCP) Dynamic Cone Penetrometer UC Unconfined Compressive Strength (PID) Photo-Ionization Detector (OVA) Organic Vapor Analyzer

Descriptive Soil Classification

Soil classification as noted on the soil boring logs is based Unified Soil Classification System. Where sufficient laboratory data exist to classify the soils consistent with ASTM D2487 "Classification of Soils for Engineering Purposes" this procedure is used. ASTM D2488 "Description and Identification of Soils (Visual-Manual Procedure)" is also used to classify the soils, particularly where insufficient laboratory data exist to classify the soils in accordance with ASTM D2487. In addition to USCS classification, coarse grained soils are classified on the basis of their in-place relative density, and fine-grained soils are classified on the basis of their consistency. See "Strength Terms" table below for details. The ASTM standards noted above are for reference to methodology in general. In some cases, variations to methods are applied as a result of local practice or professional judgment.

Location And Elevation Notes

Exploration point locations as shown on the Exploration Plan and as noted on the soil boring logs in the form of Latitude and Longitude are approximate. See Exploration and Testing Procedures in the report for the methods used to locate the exploration points for this project. Surface elevation data annotated with +/- indicates that no actual topographical survey was conducted to confirm the surface elevation. Instead, the surface elevation was approximately determined from topographic maps of the area.

Strength Terms

Relative Density of Coarse-Grained Soils <small>(More than 50% retained on No. 200 sieve.) Density determined by Standard Penetration Resistance</small>			Consistency of Fine-Grained Soils <small>(50% or more passing the No. 200 sieve.) Consistency determined by laboratory shear strength testing, field visual-manual procedures or standard penetration resistance</small>			
Relative Density	Standard Penetration or N-Value (Blows/Ft.)	Ring Sampler (Blows/Ft.)	Consistency	Unconfined Compressive Strength Qu (tsf)	Standard Penetration or N-Value (Blows/Ft.)	Ring Sampler (Blows/Ft.)
Very Loose	0 - 3	0 - 5	Very Soft	less than 0.25	0 - 1	< 3
Loose	4 - 9	6 - 14	Soft	0.25 to 0.50	2 - 4	3 - 5
Medium Dense	10 - 29	15 - 46	Medium Stiff	0.50 to 1.00	4 - 8	6 - 10
Dense	30 - 50	47 - 79	Stiff	1.00 to 2.00	8 - 15	11 - 18
Very Dense	> 50	> 80	Very Stiff	2.00 to 4.00	15 - 30	19 - 36
			Hard	> 4.00	> 30	> 36

Relevance of Exploration and Laboratory Test Results

Exploration/field results and/or laboratory test data contained within this document are intended for application to the project as described in this document. Use of such exploration/field results and/or laboratory test data should not be used independently of this document.

Unified Soil Classification System

Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests ^A				Soil Classification	
				Group Symbol	Group Name ^B
Coarse-Grained Soils: More than 50% retained on No. 200 sieve	Gravels: More than 50% of coarse fraction retained on No. 4 sieve	Clean Gravels: Less than 5% fines ^C	Cu ≥ 4 and 1 ≤ Cc ≤ 3 ^E	GW	Well-graded gravel ^F
		Gravels with Fines: More than 12% fines ^C	Cu < 4 and/or [Cc < 1 or Cc > 3.0] ^E	GP	Poorly graded gravel ^F
			Fines classify as ML or MH	GM	Silty gravel ^{F, G, H}
		Sands: 50% or more of coarse fraction passes No. 4 sieve	Clean Sands: Less than 5% fines ^D	Fines classify as CL or CH	GC
	Cu ≥ 6 and 1 ≤ Cc ≤ 3 ^E			SW	Well-graded sand ^I
	Sands with Fines: More than 12% fines ^D		Cu < 6 and/or [Cc < 1 or Cc > 3.0] ^E	SP	Poorly graded sand ^I
			Fines classify as ML or MH	SM	Silty sand ^{G, H, I}
	Fine-Grained Soils: 50% or more passes the No. 200 sieve	Silts and Clays: Liquid limit less than 50	Inorganic:	PI > 7 and plots above "A" line ^J	CL
PI < 4 or plots below "A" line ^J				ML	Silt ^{K, L, M}
Organic:			$\frac{LL \text{ oven dried}}{LL \text{ not dried}} < 0.75$	OL	Organic clay ^{K, L, M, N} Organic silt ^{K, L, M, O}
			Silts and Clays: Liquid limit 50 or more	Inorganic:	PI plots on or above "A" line
PI plots below "A" line		MH			Elastic silt ^{K, L, M}
Organic:		$\frac{LL \text{ oven dried}}{LL \text{ not dried}} < 0.75$		OH	Organic clay ^{K, L, M, P} Organic silt ^{K, L, M, Q}
		Highly organic soils:		Primarily organic matter, dark in color, and organic odor	

^A Based on the material passing the 3-inch (75-mm) sieve.

^B If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.

^C Gravels with 5 to 12% fines require dual symbols: GW-GM well-graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM poorly graded gravel with silt, GP-GC poorly graded gravel with clay.

^D Sands with 5 to 12% fines require dual symbols: SW-SM well-graded sand with silt, SW-SC well-graded sand with clay, SP-SM poorly graded sand with silt, SP-SC poorly graded sand with clay.

^E $Cu = D_{60}/D_{10}$ $Cc = \frac{(D_{30})^2}{D_{10} \times D_{60}}$

^F If soil contains ≥ 15% sand, add "with sand" to group name.

^G If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.

^H If fines are organic, add "with organic fines" to group name.

^I If soil contains ≥ 15% gravel, add "with gravel" to group name.

^J If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.

^K If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel," whichever is predominant.

^L If soil contains ≥ 30% plus No. 200 predominantly sand, add "sandy" to group name.

^M If soil contains ≥ 30% plus No. 200, predominantly gravel, add "gravelly" to group name.

^N PI ≥ 4 and plots on or above "A" line.

^O PI < 4 or plots below "A" line.

^P PI plots on or above "A" line.

^Q PI plots below "A" line.

