

Business Services Contracts Office 5735 47th Avenue • Sacramento, CA 95824 (916) 643-2464 Rose Ramos, Chief Business Officer Jessica Sulli, Contract Specialist

#### ADDENDUM NO. 0

Date: May 11, 2022

Issued by: Sacramento City Unified School District

Project: SCUSD Project No. 454-1 Shade Structures Group 1A

This Addendum shall supersede the original Information, attachments, and specifications regarding RFQ/P where it adds to, deletes from, clarifies or otherwise modifies them. All other conditions and any previous addenda shall remain unchanged.

#### AD0.01 - Hazmat Reports

A. Reference Hazmat Reports, Sample Maps and SMAQMD forms attached

#### AD0.02 - Project Manual

- A. Table of Contents
  - 1. DELETE Table of Contents in its entirety and REPLACE with Table of Contents included with this addendum.
- B. Division 00, Section 00 52 131. DELETE Section 00 52 13 and replace with revised Section 00 52 13 attached
- C. Division 01, Section 01 32 13, Paragraph 1.03
  - 1. DELETE Section 01 32 13, Paragraph 1.03 and replace with revised Section 01 32 13, Paragraph 1.03 attached
- D. Section 07 9200, Joint Sealants
  - 1. ADD Section 07 9200, Joint Sealants included with this addendum.
- E. Section 09 9100, Painting



1. ADD Section 09 9100, Painting included with this addendum.

#### AD0.03 - For - 02-119973 Shade Structure at Tahoe Elementary School

#### **Drawings**

- A. Sheet 2, Statement of General Conformance
  - 1. ADD Statement of General Conformance sheet per sheet AD0.01 included with this addendum
- B. Sheet LS1.0, General Info
  - 1. DELETE in its entirety and REPLACE with sheet AD0.02 included with this addendum
- C. Sheet LS1.1, DSA 103
  - 1. DELETE in its entirety and REPLACE with sheet AD0.03 included with this addendum
- D. Sheet LS3.0, 30' Wide Rectangular Hip Foundation Plan
  - 1. DELETE in its entirety and REPLACE with sheet AD0.04 included with this addendum
- E. Sheet LS3.1, 30' Wide Rectangular Hip Framing & Connection Details
  - 1. DELETE in its entirety and REPLACE with sheet AD0.05 included with this addendum
- F. Sheet LS3.4, 30' Rectangular Hip Standing Seam Roofing Plan
  - 1. DELETE in its entirety and REPLACE with sheet AD0.06 included with this addendum
- G. Sheet LS5.0, Electrical Access
  - 1. DELETE in its entirety and REPLACE with sheet AD0.07 included with this addendum

#### AD0.04 – For 02-119974 Shade Structure at Sequoia Elementary School

#### **Drawings**

- A. Sheet C0.1, Civil General Notes and Abbreviations
  - 1. ADD Landscape / Irrigation Note per sheet AD0.01 included with this addendum.
- B. Sheet C1.1, Demolition Plan



- 1. REVISE existing water and irrigation line demolition scope and all applicable callouts to now include demolition of the existing water line per sheet AD0.02 included with this addendum.
- 2. REVISE Demolition Note 10 per sheet AD0.02 included with this application
- C. Sheet C2.1, Grading, Drainage and Paving Plan
  - 1. REVISE water and irrigation line scope and all applicable callouts to now show the rerouting of the utilities around the shade structure concrete pad per sheet AD0.03 included with this application.
  - 2. REVISE Construction Notes 15 and 16 per sheet AD0.03 included with this application.
- D. Sheet A1.1.1, Partial Site Plan and Details
  - 1. Detail 2, Site Plan Shade Structure: REVISE site plan to now show a section callout at the shade structure column per sheet AD0.04 included with this addendum.
  - Sheet Note 4: ADD note. Text to read "For footing / concrete pad / column Interaction, see PC shade structure / deferred approval"
- E. Sheet E1.1, Site Plan Electrical
  - 1. REVISE conduit and ground rod callouts per sheet AD0.05 included with this addendum.
  - 2. REVISE Keyed Notes 1 and 4 per sheet AD0.05 included with this addendum.
  - 3. ADD Keyed Notes 8 and 9 per sheet AD0.05 included with this addendum.
- F. Sheet E3.1, Details
  - 1. Detail 2, Typical H/20 Traffic Rated Pull Box: REVISE per sheet AD0.06 included with this addendum.
  - 2. Detail 3, Typical Trench Detail: REVISE per sheet AD0.06 included with this addendum.
  - 3. Detail 4, Conduit Stub in Post Detail: REVISE per sheet AD0.06 included with this addendum.
  - 4. Detail 5, Typical Steel Column & Rebar Grounding Detail: REVISE per sheet AD0.06 included with this addendum.
- G. Sheet 2, Statement of General Conformance
  - 1. ADD Statement of General Conformance sheet per sheet AD0.07 included with this addendum
- H. Sheet LS1.0, General Info
  - 1. DELETE in its entirety and REPLACE with sheet AD0.08 included with this addendum
- I. Sheet LS1.1, DSA 103
  - 1. DELETE in its entirety and REPLACE with sheet AD0.09 included with this addendum



- J. Sheet LS3.0, 30' Wide Rectangular Hip Foundation Plan
  - 1. DELETE in its entirety and REPLACE with sheet AD0.10 included with this addendum
- K. Sheet LS3.1, 30' Wide Rectangular Hip Framing & Connection Details
  - 1. DELETE in its entirety and REPLACE with sheet AD0.11 included with this addendum
- L. Sheet LS3.4, 30' Rectangular Hip Standing Seam Roofing Plan
  - 1. DELETE in its entirety and REPLACE with sheet AD0.12 included with this addendum
- M. Sheet LS5.0, Electrical Access
  - 1. DELETE in its entirety and REPLACE with sheet AD0.13 included with this addendum

#### AD0.05 – For 02-119976 Shade Structure at New Joseph Bonnheim Elementary School

#### **Drawings**

- A. Sheet A0.2, Typical Mounting Heights and Details
  - 1. Detail 10, Hydration Station Guardrail: REVISE per sheet AD0.01 included with this addendum
- B. Sheet C0.1, Civil General Notes and Abbreviations
  - 2. ADD Landscape / Irrigation Note per sheet AD0.02 included with this addendum.
- C. Sheet A1.1.2, Partial Site Plans and Details
  - 1. Detail 1, Enlarged Site Plan SS: REVISE site plan to now show a section callout at the shade structure column per sheet AD0.03 included with this addendum.
  - 2. Sheet Note 7: ADD note. Text to read "For footing / concrete pad / column interaction, see PC shade structure / deferred approval"
- D. Sheet E1.1, Site Plan Electrical
  - 1. REVISE conduit and ground rod callouts per sheet AD0.04 included with this addendum.
  - 2. REVISE Keyed Notes 1 and 4 per sheet AD0.04 included with this addendum.
  - 3. ADD Keyed Note 8 per sheet AD0.04 included with this addendum.
- E. Sheet E3.1, Details



- 1. Detail 2, Typical H/20 Traffic Rated Pull Box: REVISE per sheet AD0.05 included with this addendum.
- 2. Detail 4, Conduit Stub in Post Detail: REVISE per sheet AD0.05 included with this addendum.
- 3. Detail 5, Typical Steel Column & Rebar Grounding Detail: REVISE per sheet AD0.05 included with this addendum.
- F. Sheet 2, Statement of General Conformance
  - 1. ADD Statement of General Conformance sheet per sheet AD0.06 included with this addendum
- G. Sheet LS1.0, General Info
  - 1. DELETE in its entirety and REPLACE with sheet AD0.07 included with this addendum
- H. Sheet LS1.1, DSA 103
  - 1. DELETE in its entirety and REPLACE with sheet AD0.08 included with this addendum
- I. Sheet LS3.0, 30' Wide Rectangular Hip Foundation Plan
  - 1. DELETE in its entirety and REPLACE with sheet AD0.09 included with this addendum
- J. Sheet LS3.1, 30' Wide Rectangular Hip Framing & Connection Details
  - 1. DELETE in its entirety and REPLACE with sheet AD0.10 included with this addendum
- K. Sheet LS3.4, 30' Rectangular Hip Standing Seam Roofing Plan
  - 1. DELETE in its entirety and REPLACE with sheet AD0.11 included with this addendum
- L. Sheet LS5.0, Electrical Access
  - 1. DELETE in its entirety and REPLACE with sheet AD0.12 included with this addendum

#### END OF ADDENDUM NO. 0

#### Vendor to sign as acknowledgment of receipt and return with Bid:

Company Name (please print) \_\_\_\_\_

Asbestos and Lead Building Inspection/Survey

> Sequoia Elementary School Buildings A and D1

3333 Rosemont Drive Sacramento, CA 95826

Presented to:

Mike Taxara Facilities Project Technician

Sacramento City Unified School District 425 1<sup>st</sup> Avenue Sacramento, CA 95818

Inspection Date:

April 19, 2022

Reviewed and Submitted by:

Michael J. Lee Certified Asbestos Consultant Certified Lead Inspector/Assessor Registered Environmental Property Assessor

Conducted by:

Joseph Wilkins Certified Site Surveillance Technician Certified Lead Sampling Technician

National Analytical Laboratories, Inc. 2201 Francisco Dr., Ste.140-261 El Dorado Hills, CA 95742 Office: (916) 361-0555 | Fax: (916) 361-0540 E-Mail: NAL1@NAL1.com | Web Page: www.NAL1.com



April 19, 2022

Mike Taxara Facilities Project Technician Sacramento City Unified School District 425 1<sup>st</sup> Street Sacramento, CA 95818

#### RE: Asbestos and Lead Building Inspection/Survey Sequoia Elementary School Buildings A and D1 3333 Rosemont Drive Sacramento, California 95826

Dear Mr. Taxara,

The following report is regarding the building inspection conducted at the above site. Of the eight (08) suspected asbestos-containing samples collected, none (0) were found to contain asbestos. Eighteen (18) XRF shots were obtained to make a total of the six (06) suspected lead-containing areas tested, none (0) were found to contain lead-based material or lead-based paint. Joseph Wilkins, Certified Site Surveillance Technician, and Lead Sampling Technician, working with National Analytical Laboratories, Inc. (N.A.L.), conducted the inspection on April 19, 2022.

#### SUMMARY OF FINDINGS -

The building inspection and analytical results indicate that no asbestos is present in the areas that are being renovated.

Based on the lead sample results, the specific areas where testing was conducted were found to be below Cal-OSHA's Lead Limit of Detection.

#### SECTION I: ASBESTOS INSPECTION -

The inspection was completed according to the EPA's Asbestos Containing Building Materials (ACBM) In-Schools Rule; 40 CFR 763.85 (Inspection and Re-Inspection). Currently, the EPA regulations classify ACBM as materials containing more than 1-percent (1%) of asbestos. Cal-OSHA currently regulates asbestos to 1/10th of 1% (0.1%) and requires a certified asbestos worker to conduct this work.

Upon completing the visual inspection, the suspect asbestos bulk sample materials were collected under the EPA and Cal-OSHA protocol. They were placed into new plastic bags, sealed, and identified with unique identification numbers. The bulk samples were transported to the laboratory under a chain of custody protocol for analysis. MircoTest Laboratory, located in Rancho Cordova, CA, analyzed the bulk suspect asbestos-containing samples, utilizing the Polarized Light Microscopy (PLM) Method. National Voluntary Laboratory Accreditation Program (NVLAP), certification #200999-0, California Environmental Laboratory Accreditation Program (CAELAP), certification #2974, certifies MicroTest.

Asbestos Building Inspection/Survey Sequoia Elementary School Buildings A and D1 3333 Rosemont Drive, Sacramento, CA April 19, 2022 Page 3 of 5

Minor destructive renovation sampling was conducted during the site visit. If renovation or demolition work reveals any unforeseen suspect materials or if any future renovation work is to be conducted in other areas at the site, the Contractor shall cease all work and contact the building owner for further testing.

Not all the rooms or materials throughout the site were sampled. According to the results, the like materials that were not tested will be treated as homogeneous to the tested materials and will be considered asbestos or non-asbestos.

| Sample ID# | Material        | Location                               | Results       |
|------------|-----------------|--|---------------|
| 3333-1A    | Stucco          | Bldg. A- Exterior, Electrical Room, S. | None Detected |
|            |                 | Wall, Base                             |               |
| 3333-1B    | Stucco          | Bldg. A- Exterior, Electrical Room, E. | None Detected |
|            |                 | Wall, Base                             |               |
| 3333-1C    | Stucco          | Bldg. A- Exterior, Electrical Room, SE | None Detected |
|            |                 | Wall, Base                             |               |
| 3333-2A    | Plaster         | Bldg. A- Electrical Room, Light Switch | None Detected |
| 3333-2B    | Plaster         | Bldg. A - Electrical Room, E. Wall,    | None Detected |
|            |                 | Damage                                 |               |
| 3333-2C    | Plaster         | Bldg. A- Electrical Room, Ceiling,     | None Detected |
|            |                 | Damage                                 |               |
| 3333-3     | Sheetrock-Joint | Bldg. D1- Boy's Restroom, N. Wall,     | None Detected |
|            | Compound        | Damage                                 |               |
| 3333-4     | Sheetrock-Joint | Bldg. D1- Girl's Restroom, S. Wall,    | None Detected |
|            | Compound        | Damage                                 |               |

The following samples were non-asbestos-containing materials:

### ASBESTOS CONCLUSION -

No asbestos was detected in the above-listed samples/materials. Therefore, the contractor, their employees, or the sub-contractors, can complete their work, in the specific areas tested, without any health or safety concerns regarding the exposure to airborne asbestos fibers.

### SECTION II: LEAD INSPECTION -

The lead suspect samples were collected according to the Housing Urban Development (HUD) Guidelines, the Environmental Protection Agency (EPA), and the California Public Health Department (formally DHS), which regulate and require the abatement or in-place management of LBP hazards equal to or greater than 1.0 milligram per square centimeter (1.0 mg/cm<sup>2</sup>) of lead by XRF analysis or more than 0.5% lead by weight by laboratory flame atomic absorption. The following regulation shall be adhered to because Cal-OSHA considers all surfaces to contain Lead: Cal-OSHA's 29 CFR 1926.62, California Occupational Safety and Health Standard, Title 8 (Cal-OSHA 8 CCR 1532.1).

Upon completing the visual inspection, suspect painted finishes or materials were sampled for potential lead content, following the EPA and Cal-OSHA protocol. They were labeled with unique identification numbers and analyzed using the Heuresis Pb200i Portable X-ray Fluorescent (XRF) analyzer. When the material is measured using XRF, each element present in the sample emits its own unique fluorescent x-ray energy spectrum. We can rapidly determine the material's lead content by simultaneously measuring the fluorescent x-ray semitted by the sample's different components.

| The following samples were found to be less than | ו (<) the Cal-OSHA's Limit of Detection |
|--|---|
|--|---|

| Sample ID# | Cample ID# Description Location |  | Concentration %<br>By Weight |
|------------|---------------------------------|--|------------------------------|
| 3333-1L    | Wood                            | Bldg. D1- Boy's/Girl's/Staff Restroom, Ceiling,<br>White Paint | <lod< td=""></lod<>          |
| 3333-2L    | Sheetrock                       | Bldg. D1- Boy's/Girl's/Staff Restroom, Walls,<br>White Paint   | <lod< td=""></lod<>          |
| 3333-3L    | Ceramic                         | Bldg. D1- Boy's/Girl's/Staff Restroom, Walls,<br>Beige Tiles   | <lod< td=""></lod<>          |
| 3333-4L    | Ceramic                         | Bldg. D- Boy's/Girl's/Staff Restroom, Walls,<br>Blue Tiles     | <lod< td=""></lod<>          |
| 3333-5L    | Ceramic                         | Bldg. D1- Boy's/Girl's/Staff Restroom, Floor,<br>Tan Tiles     | <lod< td=""></lod<>          |
| 3333-6L    | Stucco                          | Bldg. A- Exterior, Electrical Room, Walls,<br>White Paint      | <lod< td=""></lod<>          |

#### LEAD CONCLUSION -

The above-listed samples were found to be below Cal-OSHA's limit of detection, therefore, renovation/demolition of the listed materials can proceed without regard to lead dust or lead contamination.

#### ASSUMPTIONS AND LIMITATIONS -

The results, findings, conclusions, and recommendations expressed in this report are based only on conditions that were noted during N.A.L.'s inspection of the specific areas listed herein.

The selection of sample locations and sampling frequency was based on observations and the assumption that like materials in the same area are homogeneous in content. This report is not to be utilized as a bidding document or project specification document since it does not have all the components required to serve as an asbestos and lead abatement project design document or asbestos and lead abatement work plan.

Our professional services have been performed, our findings obtained, and our conclusions and recommendations prepared following established principles and practices in the fields of environmental testing and consulting. This report does not warrant undiscovered hazards and locations not investigated. Asbestos Building Inspection/Survey Sequoia Elementary School Buildings A and D1 3333 Rosemont Drive, Sacramento, CA April 19, 2022 Page 5 of 5

This report includes the laboratory analytical results, chain custody forms, and sample location map. If you have any questions regarding this report or can further assist, please contact our office.

Reviewed and submitted by:


Michael J. Lee Certified Asbestos Consultant DOSH# 06-4047 Certified Lead Inspector/Assessor LRC-00007541 Registered Environmental Property Assessor REPA# 716352750 Conducted by:

andul

Joseph Wilkins Certified Site Surveillance Technician DOSH# 17-5890 Certified Lead Sampling Technician CDPH# 28630









# AIR QUALITY

# **Asbestos Survey Form**

(See Instructions)

| 1.Purpose of  | Survey         |          |              | Renovation      |                        |           |               | Demolition          |              |                      |
|---|----------------|----------|--------------|-----------------|------------------------|-----------|---------------|---------------------|--------------|----------------------|
| 2. Facility Information                                     |                |          |              |                 |                        |           |               |                     |              |                      |
| Project Area(s) D   | escription     |          |              |                 |                        |           |               |                     |              |                      |
| Sequoia Elem  | entary Sc      | hool - E | Building     | s A and D       | 1                      |           |               |                     |              |                      |
| Address   |                |          |              |                 |                        | City      |               |                     |              | # of<br>Structures   |
| 3333 Rosemo   | nt Drive       |          |              |                 |                        | Sacra     | mento         |                     |              |                      |
| 3.Owner Info  | rmation        |          |              |                 |                        |           |               |                     |              |                      |
| Name  |                |          |              |                 |                        |           |               |                     |              |                      |
| Address   |                |          |              |                 | City/State             |           |               |                     |              | Zip                  |
| O a rata at   |                | Dhama    |              |                 | <b>5</b>               |           |               | <b>F</b>            |              |                      |
| Contact   |                | Phone    |              |                 | Fax                    |           |               | Email               |              |                      |
| 4. Consultant   | Informa        | tion     | Surve        | y Date(s):      | 04/19/22               |           |               |                     |              |                      |
| Company Name  |                |          |              |                 |                        |           |               |                     |              |                      |
| Nama  | Natio          | nal An   | alytica      | al Labora       | tories, Inc.           |           |               |                     |              | ц                    |
| <sup>Name</sup> Micha                                       | ael J. Le      | е        |              |                 |                        |           |               |                     | DOSH #       | <sup>*</sup> 06-4047 |
| Address<br>2201 Francisco                                   | Dr Ste 1       | 40-261   | City/S       | tate<br>El Dora | ado Hills, CA          |           |               |                     |              | <sup>Zip</sup> 95762 |
| Phone<br>916-361-0555                                       | Fax            | 61-054   | 1            | Email           | a@nal1.com             |           |               | Signatu             | re           | the last             |
| 5. Client Informa   |                |          |              |                 | eral Contractor        |           | □Insur        | ance Co             | mpany        |                      |
|   | •              | Archit   |              |                 | perty Manager          | •         | <b>⊡Oth</b>   |                     |              |                      |
| Name  |                |          |              |                 |                        |           |               |                     |              |                      |
| Address   |                |          |              |                 | City/State             |           |               |                     |              | Zip                  |
| Contact   |                | Phone    |              |                 | Fax                    |           | Email         |                     |              |                      |
| 6.Have all of   | the susp       | ect mat  | terials      | that will b     | e disturbed b          | een sa    | mpled         | ?                   |              | ⊡Yes                 |
|   | •              |          |              |                 |                        |           | •             |                     |              | □No                  |
| lf no, explain w  | vhy:           |          |              |                 |                        |           |               |                     |              |                      |
|   |                |          |              |                 |                        |           |               |                     |              |                      |
| 7.Summary o   | f Total A      | sbesto   | s Cont       | aining Ma       | terial (ACM) F         | inding    | S             |                     |              |                      |
| Regulated Ask<br>(Includes materials<br>fire damaged materi | subject to kn  |          |              |                 | Categ                  | jory II   |               |                     | Categ        | ory I                |
| Square Ft.  | Linea          | r Ft.    | С            | ubic Ft.        | Square Ft.             | Line      | ar Ft.        | Squ                 | are Ft.      | Linear Ft.           |
| 0   | (              | )        |              | 0               | 0                      |           | 0             | 0                   |              | 0                    |
| To rece   | eive future    | SMAQM    | D Rule       | updates and     | changes affecti        | ing your  | indust        | ry (cheo            | ck one bo    | ox):                 |
| Please send e-m   | ail notices to |          |              |                 | will sign up myself at | www.airqu | uality.org/li | i <u>stserve/</u> t | o receive e- | mailed notices.      |
| I am already su   | bscribed.      | I wan    | t the Distri |                 | s to the address on th |           |               |                     | vner         | Consultant           |

#### **SMAQMD Survey Form Instructions**

- #1. Check the appropriate box as to whether the survey is for a Renovation or Demolition as defined by SMAQMD Rule 902, at the time the survey was conducted. Demolitions require sampling of all suspect materials unless assumed to contain asbestos or only a small area is being impacted by the demolition, ie, the entire building will not be razed. An example of this would be where only a load bearing wall(s) is removed but the building will remain intact. In those cases, explain why all suspect materials in the structure were not sampled in item #6. Renovations (TI's, soft demo's, remodels) require sampling of only the suspect materials that are going to be disturbed.
- #2. Provide the description and function of the building(s) or area(s), ie, "School-Boiler Room", within the building(s) being surveyed. Include the total number of floors surveyed. Provide the address of building(s) surveyed. If multiple buildings are on site, provide the total number of structures surveyed, include portables, outbuildings, garages, sheds, etc.
- #3. Provide owner information.
- #4. Provide consultant information and the date on which each building/area was surveyed in item #2.
- #5. The client refers to whoever requested the survey to be conducted and provided demolition/renovation information to the consultant. If the client is the owner in #3, leave this section blank.
- #6. Unless assumed to contain asbestos, all suspect materials must be sampled prior to a demolition. Prior to a renovation, unless assumed to contain asbestos, suspect materials >160 square feet, 260 linear feet, or 35 cubic feet that will be abated, stripped, or removed must be sampled. You cannot assume suspect materials are negative. Samples taken must be based on the Asbestos Hazard Emergency Response Act (AHERA) guidelines for homogeneous areas but must include both the interior <u>and exterior</u> suspect materials, floor to roof. The list below provides common suspect materials. Surfacing materials requiring 3,5,7 protocol are noted (3,5,7). The SMAQMD considers stucco a surfacing material. All other sampling may be done "sufficient to determine".

#### EPA Category of Common Suspect Asbestos Containing Materials

Note: This list does not include every product that may contain asbestos. It is intended as a general guide to show the proper NESHAP categories of materials typically containing asbestos.

| Regulated Asbestos Containing Material                 | Category II                                  |
|--|--|
| <ul> <li>Fireproofing (3,5,7)</li> </ul>               | • Stucco (3,5,7)                             |
| <ul> <li>Acoustical Ceiling Texture (3,5,7)</li> </ul> | Window Glazing                               |
| • Plaster (3,5,7)                                      | <ul> <li>Cement Board/Transite</li> </ul>    |
| <ul> <li>Wall Texture (3,5,7)</li> </ul>               | Mastics                                      |
| <ul> <li>Ceiling Tiles</li> </ul>                      | <ul> <li>Textured Paints/Coatings</li> </ul> |
| <ul> <li>HVAC Duct Insulation</li> </ul>               | Chalkboards                                  |
| <ul> <li>Thermal System Insulation</li> </ul>          | <ul> <li>Lab Hoods/Table Tops</li> </ul>     |
| <ul> <li>Mudded Pipe Elbow Insulation</li> </ul>       | Cement Pipes                                 |
| <ul> <li>Linoleum Backing</li> </ul>                   | <ul> <li>Cement Roofing Shingles</li> </ul>  |
| <ul> <li>Furnace Insulation</li> </ul>                 | Caulking                                     |
| <ul> <li>Fire Doors</li> </ul>                         | <u>Category I</u>                            |
| <ul> <li>Nicolite Roofing paper</li> </ul>             | <ul> <li>Asphalt Flooring</li> </ul>         |
|  | <ul> <li>Roofing Shingles</li> </ul>         |
|  | <ul> <li>Built-up Roofing</li> </ul>         |
|  | Base Flashing                                |
|  | <ul> <li>Rolled Roofing</li> </ul>           |
|  | <ul> <li>Boiler/Tank Insulation</li> </ul>   |
|  | Vinyl Floor Tile                             |

#7. This is an estimate total of all RACM, Category I & Category II materials found in <u>all</u> structures listed in item #2. If Category I & II materials were subjected to fire or will be subjected to mechanical forces during removal, they must be designated as RACM. An asbestos containing material must only be designated to one category. Category I or II material cannot be listed as RACM.


#### Attachments (Include with Survey)

I. Findings & Recommendations

Explain the significance of the data in item #7. State that Category I material may be left in place during demolition and that RACM and Cementitious Category II material must be removed prior to the renovation or demolition. Explain that the amounts listed are to be used by the owner to obtain accurate bids from abatement contractors. State whether this is a jurisdictional project under the requirements of the federal NESHAP and SMAQMD Rule 902. For unimpacted areas in a renovation, state that untested suspect materials must be tested prior to additional future projects where the materials will be disturbed.

#### II. Floor Plan Map(s)

Create a separate Floor Plan Map (see example below) for each floor or area of every structure surveyed in item #2. If the roof or exterior is impacted by the project, create a separate map for the roof and exterior or include them on one of the floor maps as seen below. Name each room sampled by the commonly used name and state whether the area is undergoing Renovation or Demolition. A demolition is the wrecking, taking out or burning of any load supporting structural member. A renovation is everything else. If the survey is conducted after the demo/reno has occurred, inspect all dumpsters outside of building. Record the location of each sample taken and identify each sample with a unique identifier that will be the same as reported to the laboratory and in the following appendices. Use "+" to describe >1% or "-" to describe = to or <1% asbestos.



Example: Building 1 - Floor Plan Map

• 29+

**Roof** 23+, 24+, 25 thru 28 -

#### III. Sample Results

Create a table (see example below of minimal information needed to comply with SMAQMD Rule 902) for all samples >1% from all structures surveyed in item #2. Category I or Category II materials subject to known mechanical removal or fire damage must be considered RACM. Add more rows and columns as needed.

| Sample(s)<br>ID# | Suspect<br>Material | Asbestos<br>Content<br>(%)<br>(PLM/PC) | EPA<br>Category                 | Total<br>Quantity<br>Sq./Ln/Cu.<br>Ft. |
|------------------|---------------------|--|---------------------------------|--|
| 1                | Ceiling tile        | 2.6-PC                                 | RACM                            | 250 sqft                               |
| 4                | Linoleum            | 40-PLM                                 | RACM                            | 800 sqft                               |
| 5                | Floor<br>mastic     | 1.4-PC                                 | RACM<br>(mechanical<br>removal) | 250 sqft                               |
| 14,16, 18        | TSI                 | 80-PLM                                 | RACM                            | 1,200 li.ft.                           |
| 15,17, 19        | Wall<br>texture     | 3-PC                                   | RACM                            | 2,500 sqft                             |
| 21               | Floor tile          | 8-PLM                                  | CAT II                          | 2,500 sqft                             |
| 20               | Transite<br>panels  | 45-PLM                                 | CAT II                          | 1,100 sqft                             |
| 23               | Nicolite felt       | Assumed                                | RACM                            | 12,000 sqft                            |
| 24               | Roof<br>mastic      | 2-PLM                                  | CATI                            | 12,000 sqft                            |
| 29, 30, 31       | Stucco              | 1.7 PC                                 | RACM                            | 5,40 <del>0</del> sqft                 |

| Example: Building 1 | - Sample Results |
|---------------------|------------------|
|---------------------|------------------|

#### IV. Lab Results

Point count (PC) all samples <10% unless assumed > 1%

V. Current proof of certification of person listed in item #4

# Special Note: The following are common causes for survey rejection and potential citation by SMAQMD:

(1)-Survey form or Appendices incomplete, incorrect or missing attachments.

(2)-All suspect materials are not sampled or assumed to be asbestos containing in the survey (for any reason).

(3)-Affected suspect materials are not sampled utilizing the 3,5,7 protocol.

(4)-Point counts were not conducted, sheetrock was not composite sampled, non-sheetrock materials were composite sampled.

(5)-"Limited Surveys or Inaccessible Areas"- The SMAQMD is aware that renovations impact specific areas within a structure and therefore will not require sampling throughout the entire structure as a demolition survey would require. Stating that a **survey is** "limited" because all areas of the project will not be impacted or areas are inaccessible will result in rejection of the survey unless good cause is provided. There is no requirement to sample inaccessible materials, ie, materials behind a wall or encased in concrete; however, state in the "Findings & Recommendations" that upon discovery of previously untested, inaccessible suspect materials, work must cease until further sampling is conducted. Locked rooms or spaces above drop ceiling tiles are not considered inaccessible and <u>are</u> required to be sampled. The owner/operator must provide access to all impacted areas. Failure to sample suspect materials for "cosmetic" reasons will be rejected.

It is important to state that you cannot be prevented and/or instructed by the owner/operator as to what materials are to be sampled. This is determined by whoever conducts the survey and will give cause for survey rejection and potential citation to the owner/operator for failure to adequately survey all suspect materials.

Survey Instructions (4\_13)



MicroTest Laboratories Inc. NVLAP Code: 200999-0 3110 Gold Canal Dr. Ste. A. Rancho Cordova, CA 95670 PH 916.567.9808 | FX 916.404.0302 www.microtestlabsinc.com | service@microtestlabsinc.com

Project ID

MT012219067

| CLIENT INFORMATION |   |  |  |  |  |  |
|--------------------|---|--|--|--|--|--|
| Company            | <b>Company</b> National Analytical Laboratories, Inc. |  |  |  |  |  |
| Name               | Paula Lee   |  |  |  |  |  |
| Address            | 2201 Francisco Drive, Ste. 140-261                    |  |  |  |  |  |
|                    | El Dorado Hills CA, 95762                             |  |  |  |  |  |
| Phone              | (916) 361 - 0555                                      |  |  |  |  |  |
| Email              | N.A.L. Distribution List                              |  |  |  |  |  |

SAMPLEDateTuesday, April 19, 2022Time8:00 AMMicroTest

Laboratories Analytical Data JOB SITE INFORMATION Sampler Joseph Wilkins

SamplerJoseph withinsProjectSequoia Elementary PropertyAddress3333 Rosemont Drive<br/>Sacramento, CA 95826

#### POLARIZED LIGHT MICROSCOPY (PLM) EPA METHOD 600 / R-93 / 116 & EPA – 40 CFR Appendix E to Subpart E of Part 763

| Sample  | Accession | Client   | Laboratory                                    | Non Fibrous /     | Asbestiform                            |
|---------|-----------|--|---|-------------------|--|
| ID      | Number    | Description  | Description                                   | Fibrous Materials | Minerals %                             |
| 3333-1A | 19067-1   | Bldg. A, Exterior, Electrical<br>Room, S. Wall, Base | Gray Stucco<br>Non-Fibrous<br>Homogenous      | 100% Binder       | None Detected                          |
| 3333-1B | 19067-2   | Bldg. A, Exterior, Electrical<br>Room, E. Wall, Base | Gray Stucco<br>Non-Fibrous<br>Homogenous      | 100% Binder       | None Detected                          |
| 3333-1C | 19067-3   | Bldg. A, Exterior, Electrical<br>Room, SE Wall, Base | Gray Stucco<br>Non-Fibrous<br>Homogenous      | 100% Binder       | None Detected                          |
| 3333-2A | 19067-4   | Bldg. A, Electrical Room, Light<br>Switch            | White Plaster<br>Non-Fibrous<br>Homogenous    | 100% Binder       | None Detected                          |
| 3333-2B | 19067-5   | Bldg. A, Electrical Room, E.<br>Wall, Damage         | White Plaster<br>Non-Fibrous<br>Homogenous    | 100% Binder       | None Detected                          |
| 3333-2C | 19067-6   | Bldg. A, Electrical Room,<br>Ceiling, Damage         | White Plaster<br>Non-Fibrous<br>Homogenous    | 100% Binder       | None Detected                          |
| 3333-3  | 19067-7   | Bldg. D1, Boys Restroom, N.<br>Wall, Damage          | White Sheetrock-Joint Compound<br>Non-Fibrous | 100% Binder       | None Detected                          |
|         | Repo      | ort  |   |                   | nples Received: 8<br>nples Analyzed: 8 |

|      | Report                  |  |
|------|-------------------------|--|
| Date | Tuesday, April 19, 2022 |  |

Analyst: Rosey Nagra

Authorized Signatory:

Kelly Favero - Lab Manager

This analytical data sheet constitutes a final report. Due to the limitation of Polarized Light Microscopy (PLM), some samples classified as containing no asbestos in materials, NoneDetected (ND), such as floor tiles or like materials, warrant a recommendation for further analysis by Transmission Electron Microscopy (TEM). Results apply to the sample as received. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. All Samples will be held for not less than 30 days, upon which they will then be disposed of. This report shall not be reproduced in full without written authorization from MicroTest Laboratories, Inc. Soil and rock matrices are considered problematic matrices and MicroTest recommends sample homogenization prior to PLM analysis. Thermal decomposition of asbestos fibers can yield non-asbestiform mineral properties. The reporting limit for calibrated visual area estimation quantitation procedures is 1%. The reporting limit for 400/1000 point count quantitation procedures is 0.25% or 0.1% respectively. The sample is considered acceptable unless otherwise noted. Sub-samples are analyzed separately accept when manufactured with multiple layers (i.e. Linoluem, Drywall, etc.) or requested contrarily by the client

Documents #MT-PLM-A 1.0 Authorized by Kelly Favero Analytical Page 1 of 2. Proprietary to MicroTest Laboratories, Inc Issue Date: 05/29/18 Rev: 4



MicroTest Laboratories Inc. NVLAP Code: 200999-0 3110 Gold Canal Dr. Ste. A. Rancho Cordova, CA 95670 PH 916.567.9808 | FX 916.404.0302 www.microtestlabsinc.com | service@microtestlabsinc.com

Project ID

MT012219067

#### Heterogenous

| 3333-4 | 19067-8 | Bldg. D1, Girls Restroom, S.<br>Wall, Damage | White Sheetrock-Joint Compound<br>Non-Fibrous | 100% Binder | None Detected |
|--------|---------|--|---|-------------|---------------|
|        |         | wan, Damage                                  | Heterogenous                                  |             |               |

Date

Tuesday, April 19, 2022

Report

Analyst: Rosey Nagra

Authorized Signatory:

Samples Received: 8 Samples Analyzed: 8

Kelly Favero - Lab Manager

This analytical data sheet constitutes a final report. Due to the limitation of Polarized Light Microscopy (PLM), some samples classified as containing no asbestos in materials, NoneDetected (ND), such as floor tiles or like materials, warrant a recommendation for further analysis by Transmission Electron Microscopy (TEM). Results apply to the sample as received. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. All Samples will be held for not less than 30 days, upon which they will then be disposed of. This report shall not be reproduced in full without written authorization from MicroTest Laboratories, Inc. Soil and rock matrices are considered problematic matrices and MicroTest recommends sample homogenization prior to PLM analysis. Thermal decomposition of asbestos fibers can yield non-asbestiform mineral properties. The reporting limit for calibrated visual area estimation quantitation procedures is 1%. The reporting limit for 400/1000 point count quantitation procedures is 0.25% or 0.1% respectively. The sample is considered acceptable unless otherwise noted. Sub-samples are analyzed separately accept when manufactured with multiple layers (i.e. Linoluem, Drywall, etc.) or requested contrarily by the client



Project ID

MT012219067

| CLIENT INFORMATION |  | Sample       |                                     | JOB SITE INFORMATION |                                |
|--------------------|--|--------------|-------------------------------------|----------------------|--------------------------------|
| Company            | <ul> <li>Sac City Unified School<br/>District</li> </ul> | Date<br>Time | Tuesday, April 19, 2022<br>08:00 AM | Site                 | Sequoia Elementary<br>Property |
| Name               | Mike Taxara  |              | Chain-Of-Custody                    | Address              | 3333 Rosemont Drive            |
| Address            | 425 First Avenue<br>Sacramento CA, 95818                 |              |                                     | Unit                 | Sacramento, CA 95826           |
| Phone              | (916) 395 - 3980   |              |                                     | Claim#               |                                |
| Email              | Tina-Alvarez-<br>Bevens@scusd.edu                        |              |                                     | Job #<br>Chain #     | 41021<br>1                     |

# Analysis: PLM | TTFP - 400 PT.CT. Turn Around Time: Same Day

| Sample Number: | Location  | Description              |
|----------------|---|--------------------------|
|                |   |                          |
| 3333-1A        | Bldg. A, Exterior, Electrical Room, S. Wall, Base | Stucco                   |
| 3333-1B        | Bldg. A, Exterior, Electrical Room, E. Wall, Base | Stucco                   |
| 3333-1C        | Bldg. A, Exterior, Electrical Room, SE Wall, Base | Stucco                   |
| 3333-2A        | Bldg. A, Electrical Room, Light Switch            | Plaster                  |
| 3333-2B        | Bldg. A, Electrical Room, E. Wall, Damage         | Plaster                  |
| 3333-2C        | Bldg. A, Electrical Room, Ceiling, Damage         | Plaster                  |
| 3333-3         | Bldg. D1, Boys Restroom, N. Wall, Damage          | Sheetrock-Joint Compound |
| 3333-4         | Bldg. D1, Girls Restroom, S. Wall, Damage         | Sheetrock-Joint Compound |

| Relinquished by (Client) | Date/Time |
|--------------------------|-----------|
|                          |           |
|                          |           |
| Received by (Tech)       | Date/Time |
|                          |           |
|                          |           |

| Relinquished by (Tech) | Date/Time               |
|------------------------|-------------------------|
| mwy                    | 04/19/2022              |
| Convoit                | 08:00 AM                |
|                        |                         |
| Received by (Lab)      | Date/Time               |
| Received by (Lab)      | Date/Time<br>04/19/2022 |

Sampler: Joseph Wilkins

Total Number of Samples 8

COC Page # 1 from 1



**CLIENT INFORMATION** 

Name

Phone

Email

Address

District

Company Sac City Unified School

Mike Taxara

425 First Avenue

(916) 395 - 3980

Bevens@scusd.edu

Tina-Alvarez-

Sacramento CA, 95818

\*\*\*for office use only\*\*\*

Client PO

Project ID

KS#

JOB SITE INFORMATIONSiteSequoia Elementary PropertyAddress3333 Rosemont Drive<br/>Sacramento, CA 95826UnitClaim#Job #26212Chain #1

| TURN AROUND | LEAD PAINT | MEASUREMENT MODE | SAMPLING METHOD | A |
|-------------|------------|------------------|-----------------|---|
| Same Day    | Inspection | Standard         | Heuresis Pb200i |   |

Date

Time

ANALYTICAL DATA

Action Level - 1 Abatement Level - 1 Total Readings - 6

|            |  |                    | 1     |           | Total Readings - 6         |  |
|------------|--|--------------------|-------|-----------|----------------------------|--|
| Sample ID: | Sample Location   Description                            | Structure Material | Color | Condition | Lead (mg/cm <sup>2</sup> ) |  |
| 3333-1L    | Bldg. D1, Boy's/Girl's/Staff Restroom,<br>Ceiling, Paint | Wood               | White | N/A       | <lod< td=""></lod<>        |  |
| 3333-2L    | Bldg. D1, Boy's/Girl's/Staff Restroom,<br>Walls, Paint   | Sheetrock          | White | N/A       | <lod< td=""></lod<>        |  |
| 3333-3L    | Bldg. D1, Boy's/Girl's/Staff Restroom,<br>Walls, Tiles   | Ceramic            | Beige | N/A       | <lod< td=""></lod<>        |  |
| 3333-4L    | Bldg. D1, Boy's/Girl's/Staff Restroom,<br>Walls, Tiles   | Ceramic            | Blue  | N/A       | <lod< td=""></lod<>        |  |
| 3333-5L    | Bldg. D1, Boy's/Girl's/Staff Restroom,<br>Floor, Tiles   | Ceramic            | Tan   | N/A       | <lod< td=""></lod<>        |  |
| 3333-6L    | Bldg. A, Exterior, Electrical Room,<br>Walls, Paint      | Stucco             | White | N/A       | <lod< td=""></lod<>        |  |

SAMPLE

Chain-Of-Custody | Analytical Data

Heuresis Pb200i

Tuesday, April 19, 2022

08:00 AM

<LOD Below Limit of Detection | Reading < 0.0

LCM Lead Containing Material | Readings Ranging from 0 to < 1.0 mg/cm<sup>2</sup>

LBP Lead Based Paint | Readings Greater than 1.0 mg/cm<sup>2</sup>

|      | ANALYSIS       |
|------|----------------|
| Date | April 19, 2022 |
| Time | 08:00 AM       |

| Date/Time |
|-----------|
|           |
|           |
| Date/Time |
|           |
|           |

| Relinquished by (Tech) | Date/Time              |
|------------------------|------------------------|
| mont                   | 04/19/2022<br>08:00 AM |
|                        |                        |
| Received by (Lab)      | Date/Time              |

California Dept. of Public Health www.2.epa.gov/lead



Sampler: Joseph Wilkins

Analyst: Joseph Wilkins

Total Number of Samples 6

COC Page 1 from 2

Asbestos and Lead Building Inspection/Survey

#### Alice Birney K-8 John Bidwell Elementary School John Sloat Elementary School New Joseph Bonnheim Elementary School Tahoe Elementary School *Restrooms*

Presented to:

Mike Taxara Facilities Project Technician

Sacramento City Unified School District 425 1<sup>st</sup> Avenue Sacramento, CA 95818

Inspection Date:

May 06, 2022

Reviewed and submitted by:

Michael J. Lee Certified Asbestos Consultant Certified Lead Inspector/Assessor Registered Environmental Property Assessor

Conducted by:

Robert Mullen Certified Site Surveillance Technician Certified Lead Sampling Technician

National Analytical Laboratories, Inc. 2201 Francisco Dr., Ste.140-261 El Dorado Hills, CA 95742 Office: (916) 361-0555 | Fax: (916) 361-0540 E-Mail: NAL1@NAL1.com | Web Page: www.NAL1.com



May 10, 2022

Mike Taxara Facilities Project Technician Sacramento City Unified School District 425 1<sup>st</sup> Avenue Sacramento, CA 95818

RE: Asbestos and Lead Building Inspection/Survey Group 1 – 5 School Restrooms Alice Birney K-8 John Bidwell Elementary School John Sloat Elementary School New Joseph Bonnheim Elementary School Tahoe Elementary School Sacramento, California

Dear Mr. Taxara,

The following report is regarding the building inspection conducted at the various sites listed above. Of the twenty-two (22) suspect asbestos-containing samples collected, none (0) were found to contain asbestos. Eighty-four (84) XRF shots were obtained to make a total of the twenty-eight (28) suspected lead-containing areas tested, four (04) were found to contain lead-based material (LBM). Robert Mullen, Certified Site Surveillance Technician, and Lead Sampling Technician working with National Analytical Laboratories, Inc. (N.A.L.), conducted the inspection on May 06, 2022.

#### SUMMARY OF FINDINGS -

The building inspection and analytical results indicate that no asbestos is present in the areas that are being renovated.

Based on the lead sample results, the Girl's and Boy's Restroom Tiles were found to contain LBM levels at John Sloat and Tahoe Elementary school above Cal-OSHA's Lead Action Levels.

#### SECTION I: ASBESTOS INSPECTION -

The inspection was completed according to the EPA's Asbestos Containing Building Materials (ACBM) In-Schools Rule; 40 CFR 763.85 (Inspection and Re-Inspection). Currently, the EPA regulations classify ACBM as materials containing more than 1-percent (1%) of asbestos. Cal-OSHA currently regulates asbestos to 1/10th of 1% (0.1%) and requires a certified asbestos worker to conduct this work.

Asbestos and Lead Building Inspection/Survey Group 1 - Restrooms Sacramento, CA May 10, 2022 Page 3 of 7

Upon completing the visual inspection, the suspect asbestos bulk sample materials were collected under the EPA and Cal-OSHA protocol. They were placed into new plastic bags, sealed, and identified with unique identification numbers. The bulk samples were transported to the laboratory under a chain of custody protocol for analysis. MircoTest Laboratory, located in Rancho Cordova, CA, analyzed the bulk suspect asbestos-containing samples, utilizing the Polarized Light Microscopy (PLM) Method. National Voluntary Laboratory Accreditation Program (NVLAP), certification #200999-0, California Environmental Laboratory Accreditation Program (CAELAP), certification #2974, certifies MicroTest.

Minor destructive sampling was conducted during the site visit. In the event that demolition work reveals any unforeseen suspect materials or if any future renovation work is to be conducted in other areas at the site; the contractor shall cease all work and contact the building owner for further testing.

Not all the rooms or materials throughout the site were sampled. According to the results, the like materials that were not tested will be treated as homogeneous to the tested materials and will be considered asbestos or non-asbestos.

#### The following samples were non-asbestos-containing materials:

#### Alice Birney K-8

| Sample ID# | Material              | Location                            | Results       |
|------------|-----------------------|-------------------------------------|---------------|
| 6251-1     | Acoustic Ceiling Tile | Girl's Restroom Ceiling             | None Detected |
| 6251-2A    | Linoleum              | Girl's Restroom, Damage, Multicolor | None Detected |
| 6251-2B    | Mastic                | Girl's Restroom, Damage             | None Detected |
| 6251-3A    | Texture               | Girl's Restroom, Damage             | None Detected |
| 6251-3B    | Texture               | Boy's Restroom, Light Switch        | None Detected |
| 6251-3C    | Texture               | Staff Restroom, Light Switch        | None Detected |
| 6251-4     | Sheetrock-Joint       | Girl's Restroom, Damage             | None Detected |
|            | Compound              | -                                   |               |

#### John Bidwell ES

| Sample ID# | Material                    | Location                | Results       |
|------------|-----------------------------|-------------------------|---------------|
| 1730-1     | Texture                     | Girl's Restroom, Damage | None Detected |
| 1730-1     | Texture                     | Boy's Restroom, Damage  | None Detected |
| 1730-1     | Texture                     | Staff Restroom, Damage  | None Detected |
| 1730-2     | Sheetrock-Joint<br>Compound | Girl's Restroom, Damage | None Detected |

#### John Sloat ES

| Sample ID# | Material | Location                | Results       |
|------------|----------|-------------------------|---------------|
| 7525-1A    | Plaster  | Girl's Restroom, Damage | None Detected |
| 7525-1B    | Plaster  | Boy's Restroom, Damage  | None Detected |
| 7525-1C    | Plaster  | Staff Restroom, Damage  | None Detected |

#### Joseph Bonnheim ES

| Sample ID# | Material              | Location               | Results       |
|------------|-----------------------|------------------------|---------------|
| 7300-1     | Acoustic Ceiling Tile | Boy's Restroom Ceiling | None Detected |

#### Tahoe ES

| Sample ID# | Material         | Location                           | Results       |
|------------|------------------|------------------------------------|---------------|
| 3110-1A    | Texture          | Staff Restroom, Damage             | None Detected |
| 3110-1B    | Texture          | Boy's Restroom, Damage             | None Detected |
| 3110-1C    | Texture          | Girl's Restroom, Damage            | None Detected |
| 3110-2     | Sheetrock-Joint  | Staff Restroom, Damage             | None Detected |
|            | Compound         |                                    |               |
| 3110-3A    | Floor Tile       | Staff Restroom, Damage, Multicolor | None Detected |
| 3110-3B    | Mastic           | Staff Restroom, Damage             | None Detected |
| 3110-4     | Cove Base Mastic | Staff Restroom, Damage             | None Detected |

#### ASBESTOS CONCLUSION -

No asbestos was detected in the above-listed samples/materials. Therefore, the contractor, their employees, or the sub-contractors, can complete their work, in the specific areas tested, without any health or safety concerns regarding the exposure to airborne asbestos fibers.

#### SECTION II: LEAD INSPECTION -

The lead suspect samples were collected according to the Housing Urban Development (HUD) Guidelines, the Environmental Protection Agency (EPA), and the California Public Health Department (formally DHS), which regulate and require the abatement or in-place management of LBP hazards equal to or greater than 1.0 milligram per square centimeter (1.0 mg/cm<sup>2</sup>) of lead by XRF analysis or more than 0.5% lead by weight by laboratory flame atomic absorption. The following regulation shall be adhered to because Cal-OSHA considers all surfaces to contain Lead: Cal-OSHA's 29 CFR 1926.62, California Occupational Safety and Health Standard, Title 8 (Cal-OSHA 8 CCR 1532.1).

Upon completing the visual inspection, suspect painted finishes or materials were sampled for potential lead content, following the EPA and Cal-OSHA protocol. They were labeled with unique identification numbers and analyzed using the Heuresis Pb200i Portable X-ray Fluorescent (XRF) analyzer. When the material is measured using XRF, each element present in the sample emits its own unique fluorescent x-ray energy spectrum. We can rapidly determine the material's lead content by simultaneously measuring the fluorescent x-ray emitted by the sample's different components.

Once the determination is made on where the LBM is located, the In-place Management or the Abatement of the LBM can commence. If the Abatement method of all surfaces is to be completed, then the debris must be bagged, or burrito wrapped before removing the debris from the work area(s) and subsequently the site. Because the samples listed below were found to contain LBM all areas where the LBM will be disturbed will require abatement, encapsulation, or prep work by a certified lead worker.

Therefore, the employer must ensure that the worker is adequately trained under Title 8 (Cal-OSHA 8 CCR 1532 (1) (2) and shall produce evidence that the worker is not being exposed above the Action Level (AL) or the Permissible Exposure Limit (PEL). Suppose no current data is readily available for the worker(s). In that case, the employer shall conclude that the worker is being exposed above the PEL; this SHALL trigger the employer to provide advanced training and certifications for the employees working with LBM.



Although not all the rooms or materials (non-suspect) were sampled, the like materials that were not tested and their results will be treated as homogeneous. The materials will be treated as containing LBM throughout the site.

#### The locations and results of the suspect samples found to be LBM are as follows:

| John Sloat ES |                               |           |        |               |  |  |
|---------------|-------------------------------|-----------|--------|---------------|--|--|
| Sample ID:    | Sample Location   Description | Structure | Color  | Lead (mg/cm²) |  |  |
| 7525-1L       | Girl's Restroom Walls, Tiles  | Ceramic   | Yellow | 9.3           |  |  |
| 7525-2L       | Boy's Restroom Walls, Tiles   | Ceramic   | Blue   | 12.7          |  |  |

#### Tahoe FS

| Sample ID: | Sample Location   Description | Structure | Color | Lead (mg/cm²) |  |  |
|------------|-------------------------------|-----------|-------|---------------|--|--|
| 3110-1L    | Girl's Restroom Walls, Tiles  | Ceramic   | Tan   | 12.3          |  |  |
| 3110-2L    | Boy's Restroom Walls, Tiles   | Ceramic   | Multi | 12.3          |  |  |

Before the renovation/demolition work is completed or the transporting of the debris from the site, Health, and Safety Code 25157.8 (AB 2784 National Resources) requires that all lead debris be sampled for Waste Characterization. This will help the Contractor decide whether the material is to be considered Hazardous or Non-Hazardous Lead waste or general construction debris. The sequence of testing to be completed by the Contractor is as follows:

- Total Threshold Limit Concentration (TTLC) resulting from 50 mg/kg or more, but less than 1,000 mg/kg of lead must be retested using the Soluble Threshold Limit concentration (STLC) method.
- An STLC result of 5.0 mg/L or greater is considered California Hazardous Waste.
- Total Characteristic Leaching Procedure (TCLP) testing shall only be accomplished when approved by the Owners Representative; This procedure shall be generally reserved for out-of-state shipments, and A TCLP result of 5.0 mg/L or more deems the waste Federal RCRA materials; and
- The California hazardous waste threshold for total lead using STLC is 5 mg/L.

#### The following were found to be less than (<) Cal-OSHA's Limit of Detection:

| Alice | <b>Birney</b> | K-8 |
|-------|---------------|-----|
|-------|---------------|-----|

| Sample ID: | Sample Location   Description                | Structure | Lead (mg/cm <sup>2</sup> ) |
|------------|--|-----------|----------------------------|
| 6251-1L    | Interior Walls, White Paint                  | Sheetrock | <lod< td=""></lod<>        |
| 6251-2L    | Interior Doors, Frames, & Trim, Orange Paint | Metal     | <lod< td=""></lod<>        |

#### John Bidwell ES

| Sample ID: | Sample Location   Description       | Structure | Lead (mg/cm <sup>2</sup> ) |
|------------|-------------------------------------|-----------|----------------------------|
| 1730-1L    | Interior Walls, Multi-Colored Tiles | Ceramic   | <lod< td=""></lod<>        |
| 1730-2L    | Interior Walls, White Paint         | Sheetrock | <lod< td=""></lod<>        |
| 1730-3L    | Interior Ceiling, White Paint       | Wood      | <lod< td=""></lod<>        |

| Sample ID: | Sample Location   Description              | Structure | Lead (mg/cm <sup>2</sup> ) |
|------------|--|-----------|----------------------------|
| 1730-4L    | Interior Floors, Tan Tiles                 | Ceramic   | <lod< td=""></lod<>        |
| 1730-5L    | Interior Doors, Frames, & Trim, Blue Paint | Metal     | <lod< td=""></lod<>        |

#### John Sloat ES

| Sample ID: | Sample Location   Description             | Structure | Lead (mg/cm <sup>2</sup> ) |
|------------|---|-----------|----------------------------|
| 7525-3L    | Girl's Restroom Floor, Yellow Tiles       | Ceramic   | <lod< td=""></lod<>        |
| 7525-4L    | Boy's Restroom Floor, Blue Tiles          | Ceramic   | <lod< td=""></lod<>        |
| 7525-5L    | Staff Restroom Walls, Multi-Colored Tiles | Ceramic   | <lod< td=""></lod<>        |
| 7525-6L    | Staff Restroom Floor, Tan Tiles           | Ceramic   | <lod< td=""></lod<>        |
| 7525-7L    | Interior Walls, White Paint               | Sheetrock | <lod< td=""></lod<>        |
| 7525-8L    | Interior Ceiling, White Paint             | Wood      | <lod< td=""></lod<>        |
| 7525-9L    | Interior Doors, Blue Paint                | Metal     | <lod< td=""></lod<>        |
| 7525-10L   | Interior Frames/Trim, Blue Paint          | Wood      | <lod< td=""></lod<>        |

#### **Joseph Bonnheim ES**

| Sample ID: | Sample Location   Description              | Structure | Lead (mg/cm <sup>2</sup> ) |
|------------|--|-----------|----------------------------|
| 7300-1L    | Interior Doors, Frames, & Trim, Blue Paint | Metal     | <lod< td=""></lod<>        |

#### Tahoe ES

| Sample ID: | Sample Location   Description                        | Structure | Lead (mg/cm <sup>2</sup> ) |
|------------|--|-----------|----------------------------|
| 3110-3L    | Staff Restroom Walls/Ceiling, Tan Paint              | Sheetrock | <lod< td=""></lod<>        |
| 3110-4L    | Staff Restroom, Doors, Frames, & Trim, Tan<br>Paint  | Metal     | <lod< td=""></lod<>        |
| 3110-5L    | Boy's Restroom Walls/Ceiling, Tan Paint              | Sheetrock | <lod< td=""></lod<>        |
| 3110-6L    | Girl's Restroom Walls/Ceiling, Tan Paint             | Sheetrock | <lod< td=""></lod<>        |
| 3110-7L    | Boy's Restroom, Doors, Frames, & Trim, Blue<br>Paint | Metal     | <lod< td=""></lod<>        |
| 3110-8L    | Boy's Restroom Floor, Blue Tiles                     | Ceramic   | <lod< td=""></lod<>        |
| 3110-9L    | Girl's Restroom, Doors, Frames, & Trim, Blue Metal   |           | <lod< td=""></lod<>        |
| 3110-10L   | Girl's Restroom Floor, Green Tiles                   | Ceramic   | <lod< td=""></lod<>        |

#### LEAD RECOMMENDATION -

To stabilize the current lead conditions, N.A.L recommends Lead Certified CDPH Workers conduct in-place management work of the LBM surfaces/sample scheduled for renovation/demolition. Once the abatement, in-place management, or prep work is completed and the areas are stabilized, the existing surfaces/samples will be in good condition and not create a health or safety concern to the workers conducting the general



Asbestos and Lead Building Inspection/Survey Group 1 - Restrooms Sacramento, CA May 10, 2022 Page 7 of 7

construction work at the site. A Scope of Work or specifications should be utilized to conduct the lead work at the site.

#### ASSUMPTIONS AND LIMITATIONS -

The results, findings, conclusions, and recommendations expressed in this report are based only on conditions noted during N.A.L.'s inspection of the specific areas listed herein.


The selection of sample locations and sampling frequency was based on observations and the assumption that like materials in the same area are homogeneous in content. This report is not to be utilized as a bidding document or a project specification document since it does not have all the components required to serve as an Asbestos & Lead Abatement Project Design document or an Asbestos and Lead Abatement Work plan.

Our professional services have been performed, our findings obtained, and our conclusions and recommendations prepared following established principles and practices in environmental testing and consulting. This report does not warrant undiscovered hazards and locations not investigated.

This report includes the laboratory analytical results, chain custody forms, and sample location map. If you have any questions regarding this report or can be of further assistance, please get in touch with our office.

Reviewed and submitted by:

Michael J. Lee Certified Asbestos Consultant DOSH# 06-4047 Certified Lead Inspector/Assessor LRC-00007541 Registered Environmental Property Assessor REPA# 716352750



Certified Site Surveillance Technician DOSH# 17-5889 Certified Lead Sampling Technician CDPH# 28631







MicroTest Laboratories Inc. NVLAP Code: 200999-0 3110 Gold Canal Dr. Ste. A. Rancho Cordova, CA 95670 PH 916.567.9808 | FX 916.404.0302 www.microtestlabsinc.com | service@microtestlabsinc.com

Project ID

MT012219533

| CLIENT         | INFORMATION   |      | SAMPLE               | JOB SITE | <b>EINFORMATION</b>        |
|----------------|---|------|----------------------|----------|----------------------------|
| Company        | y National Analytical<br>Laboratories, Inc.                               | Date | Friday, May 06, 2022 | Sampler  | Robert Mullen              |
| Name           | Paula Lee   | Time | 8:00 AM              | Project  | Alice Birney Public School |
| Address        | 2201 Francisco Drive, Ste. 140-<br>261                                    |      | <b>MicroTest</b>     | Address  |                            |
| Phone<br>Email | El Dorado Hills CA, 95762<br>(916) 361 - 0555<br>N.A.L. Distribution List |      | Laboratories         |          | Sacramento, CA 95831       |
|                |   |      | Analytical Data      |          |                            |

#### POLARIZED LIGHT MICROSCOPY (PLM) EPA METHOD 600 / R-93 / 116 & EPA – 40 CFR Appendix E to Subpart E of Part 763

|         |           | $10007 K^{-} / 37110 K^{-}$           | In to Critic Appendix                              | L to Subpart L 0             | 1 1 alt 705   |
|---------|-----------|---------------------------------------|--|------------------------------|---------------|
| Sample  | Accession | Client                                | Laboratory   | Non Fibrous /                | Asbestiform   |
| ID      | Number    | Description                           | Description  | Fibrous Materials            | Minerals %    |
| 6251-1  | 19533-1   | Girls Restroom Ceiling                | White/Yellow Ceiling Tile<br>Fibrous<br>Homogenous | 90% Fiberglass<br>10% Binder | None Detected |
| 6251-2A | 19533-2   | Girls Restroom, Damage,<br>Multicolor | Tan Linoleum<br>Non-Fibrous<br>Homogenous          | 100% Binder                  | None Detected |
| 6251-2B | 19533-3   | Girls Restroom, Damage                | Yellow Mastic<br>Non-Fibrous<br>Homogenous         | 100% Binder                  | None Detected |
| 6251-3A | 19533-4   | Girls Restroom, Damage                | White Texture<br>Non-Fibrous<br>Homogenous         | 100% Binder                  | None Detected |
| 6251-3B | 19533-5   | Boys Restroom, Light Switch           | White Texture<br>Non-Fibrous<br>Homogenous         | 100% Binder                  | None Detected |
| 6251-3C | 19533-6   | Staff Restroom, Light Switch          | White Texture<br>Non-Fibrous<br>Homogenous         | 100% Binder                  | None Detected |

|      | Report               |
|------|----------------------|
| Date | Friday, May 06, 2022 |

Analyst: Nolan Starbuck

Authorized Signatory:

Samples Received: 7 Samples Analyzed: 7

Kelly Favero - Lab Manager

This analytical data sheet constitutes a final report. Due to the limitation of Polarized Light Microscopy (PLM), some samples classified as containing no asbestos in materials, NoneDetected (ND), such as floor tiles or like materials, warrant a recommendation for further analysis by Transmission Electron Microscopy (TEM). Results apply to the sample as received. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. All Samples will be held for not less than 30 days, upon which they will then be disposed of. This report shall not be reproduced in full without written authorization from MicroTest Laboratories, Inc. Soil and rock matrices are considered problematic matrices and MicroTest recommends sample homogenization prior to PLM analysis. Thermal decomposition of asbestos fibers can yield non-asbestiform mineral properties. The reporting limit for calibrated visual area estimation quantitation procedures is 1%. The reporting limit for 400/1000 point count quantitation procedures is 0.25% or 0.1% respectively. The sample is considered acceptable unless otherwise noted. Sub-samples are analyzed separately accept when manufactured with multiple layers (i.e. Linoluem, Drywall, etc.) or requested contrarily by the client



MicroTest Laboratories Inc. NVLAP Code: 200999-0 3110 Gold Canal Dr. Ste. A. Rancho Cordova, CA 95670 PH 916.567.9808 | FX 916.404.0302 www.microtestlabsinc.com | service@microtestlabsinc.com Project ID

MT012219533

| 6251-4 | 19533-7 | Girls Restroom, Damage | White Sheetrock-Joint Compound | 5% Cellulose | None Detected |
|--------|---------|------------------------|--------------------------------|--------------|---------------|
|        |         |                        | Fibrous                        | 95% Binder   |               |

Heterogenous

Samples Received: 7 Samples Analyzed: 7

Kelly Favero - Lab Manager

This analytical data sheet constitutes a final report. Due to the limitation of Polarized Light Microscopy (PLM), some samples classified as containing no asbestos in materials, NoneDetected (ND), such as floor tiles or like materials, warrant a recommendation for further analysis by Transmission Electron Microscopy (TEM). Results apply to the sample as received. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. All Samples will be held for not less than 30 days, upon which they will then be disposed of. This report shall not be reproduced in full without written authorization from MicroTest Laboratories, Inc. Soil and rock matrices are considered problematic matrices and MicroTest recommends sample homogenization prior to PLM analysis. Thermal decomposition of asbestos fibers can yield non-asbestiform mineral properties. The reporting limit for calibrated visual area estimation quantitation procedures is 1%. The reporting limit for 400/1000 point count quantitation procedures is 0.25% or 0.1% respectively. The sample is considered acceptable unless otherwise noted. Sub-samples are analyzed separately accept when manufactured with multiple layers (i.e. Linoluem, Drywall, etc.) or requested contrarily by the client

Documents #MT-PLM-A 1.0 Authorized by Kelly Favero Analytical Page 2 of 2. Proprietary to MicroTest Laboratories, Inc Issue Date: 05/29/18 Rev: 4

Analyst: Nolan Starbuck

Date

Friday, May 06, 2022

Report

Authorized Signatory:

and the



**Project ID** MT012219533

| CLIENT IN | NFORMATION                        |      | Sample               | JOB SI | TE INFORMATION             |
|-----------|-----------------------------------|------|----------------------|--------|----------------------------|
| Company   | Sac City Unified School           | Date | Friday, May 06, 2022 | Site   | Alice Birney Public School |
|           | District                          | Time | 08:00 AM             | Addres | ss 6251 13th Street        |
| Name      | Mike Taxara                       |      | Chain-Of-Custody     |        | Sacramento, CA 95831       |
| Address   | 425 First Avenue                  |      | Chain-Of-Custody     | Unit   |                            |
|           | Sacramento CA, 95818              |      |                      | Claim# | £                          |
| Phone     | (916) 395 - 3980                  |      |                      | Job #  | 41702                      |
| Email     | Tina-Alvarez-<br>Bevens@scusd.edu |      |                      | Chain  | # 1                        |

# Analysis: PLM | TTFP - 400 PT.CT. Turn Around Time: Same Day

| Sample Number: | Location                           | Description              |
|----------------|------------------------------------|--------------------------|
| 6251-1         | Girls Restroom Ceiling             | Acoustic Ceiling Tile    |
| 6251-2A        | Girls Restroom, Damage, Multicolor | Linoleum                 |
| 6251-2B        | Girls Restroom, Damage             | Mastic                   |
| 6251-3A        | Girls Restroom, Damage             | Texture                  |
| 6251-3B        | Boys Restroom, Light Switch        | Texture                  |
| 6251-3C        | Staff Restroom, Light Switch       | Texture                  |
| 6251-4         | Girls Restroom, Damage             | Sheetrock-Joint Compound |

| Relinquished by (Client) | Date/Time  |
|--------------------------|------------|
|                          |            |
|                          |            |
| Received by (lech)       | Date/Time  |
| Received by (Tech)       | Dater Time |

| Relinquished by (Tech) | Date/Time               |
|------------------------|-------------------------|
| ~ 20                   | 05/06/2022              |
| S-t-nt                 | 08:00 AM                |
|                        |                         |
| Received by (Lab)      | Date/Time               |
| Received by (Lab)      | Date/Time<br>05/06/2022 |

Sampler: Robert Mullen

Total Number of Samples 7

COC Page # 1 from 1

| The formation of the fo |   |                     |   |        | ***for office use only***<br>KS#<br>Client PO<br>Project ID |  |  |
|--|---|---------------------|---|--------|---|--|--|
| CLIENT INFORM  | IATION  |                     | SAMPLE                                    | -      | JOB SIT   | <b>TE INFORMATION</b>  |  |
| Company Sac City Unified School<br>District  |   | Date<br>Time        | Friday, May 06, 2022<br>08:00 AM          | 2      | Site<br>Address   | Alice Birney Public School<br>6251 13th Street                                   |  |
| Sacram   | axara<br>st Avenue<br>ento CA, 95818<br>95 - 3980 |                     | Custody   Analytical I<br>Ieuresis Pb200i | Data   | Unit<br>Claim#<br>Job #<br>Chain #                          | Sacramento, CA 95831<br>26269<br>1   |  |
| TURN AROUN<br>Same Day   | D LEAD PAINT<br>Inspection                        | MEASUREME<br>Standa |   |        | <b>NG METHOD</b><br>sis Pb200i                              | ANALYTICAL DATA<br>Action Level - 1<br>Abatement Level - 1<br>Total Readings - 2 |  |
| Sample ID:   | Sample Location   Desc                            | cription            | Structure Material                        | Color  | Conditio  | n Lead (mg/cm <sup>2</sup> )   |  |
| 6251-1L  | Interior Walls, Paint                             |                     | Sheetrock                                 | White  | N/A   | <lod< th=""></lod<>  |  |
| 6251-2L  | Interior Doors, Frames,                           | & Trim, Paint       | Metal                                     | Orange | N/A   | <lod< td=""></lod<>  |  |



MicroTest Laboratories Inc. NVLAP Code: 200999-0 3110 Gold Canal Dr. Ste. A. Rancho Cordova, CA 95670 PH 916.567.9808 | FX 916.404.0302 www.microtestlabsinc.com | service@microtestlabsinc.com

Project ID

MT012219534

|                 | <b>INFORMATION</b><br>y National Analytical<br>Laboratories, Inc. | Date | SAMPLE<br>Friday, May 06, 2022  |                    | E INFORMATION<br>Robert Mullen  |
|-----------------|---|------|---------------------------------|--------------------|---|
| Name<br>Address | Paula Lee   | Time | 9:00 AM<br>MicroTest            | Project<br>Address | John Bidwell Elementary School Property<br>1730 65th Avenue<br>Sacramento, CA 95822 |
| Phone<br>Email  | (916) 361 - 0555<br>N.A.L. Distribution List                      |      | Laboratories<br>Analytical Data |                    |   |

#### POLARIZED LIGHT MICROSCOPY (PLM) EPA METHOD 600 / R-93 / 116 & EPA – 40 CFR Appendix E to Subpart E of Part 763

|         |           |                        | FF  |                   |               |
|---------|-----------|------------------------|---|-------------------|---------------|
| Sample  | Accession | Client                 | Laboratory  | Non Fibrous /     | Asbestiform   |
| ID      | Number    | Description            | Description   | Fibrous Materials | Minerals %    |
| 1730-1A | 19534-1   | Girls Restroom, Damage | White Texture<br>Non-Fibrous<br>Homogenous                  | 100% Binder       | None Detected |
| 1730-1B | 19534-2   | Boys Restroom, Damage  | White Texture<br>Non-Fibrous<br>Homogenous                  | 100% Binder       | None Detected |
| 1730-1C | 19534-3   | Staff Restroom, Damage | White Texture<br>Non-Fibrous<br>Homogenous                  | 100% Binder       | None Detected |
| 1730-2  | 19534-4   | Girls Restroom, Damage | White Sheetrock-Joint Compound<br>Non-Fibrous<br>Homogenous | 100% Binder       | None Detected |

**Report** Friday, May 06, 2022 Samples Received: 4 Samples Analyzed: 4

Analyst: Nolan Starbuck

Date

Authorized Signatory:

Kelly Favero - Lab Manager

This analytical data sheet constitutes a final report. Due to the limitation of Polarized Light Microscopy (PLM), some samples classified as containing no asbestos in materials, NoneDetected (ND), such as floor tiles or like materials, warrant a recommendation for further analysis by Transmission Electron Microscopy (TEM). Results apply to the sample as received. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. All Samples will be held for not less than 30 days, upon which they will then be disposed of. This report shall not be reproduced in full without written authorization from MicroTest Laboratories, Inc. Soil and rock matrices are considered problematic matrices and MicroTest recommends sample homogenization prior to PLM analysis. Thermal decomposition of asbestos fibers can yield non-asbestiform mineral properties. The reporting limit for calibrated visual area estimation quantitation procedures is 1%. The reporting limit for 400/1000 point count quantitation procedures is 0.25% or 0.1% respectively. The sample is considered acceptable unless otherwise noted. Sub-samples are analyzed separately accept when manufactured with multiple layers (i.e. Linoluem, Drywall, etc.) or requested contrarily by the client



Project ID

MT012219534

| CLIENT IN | FORMATION  |              | Sample                           | JOB SITE | <b>INFORMATION</b>                         |
|-----------|--|--------------|----------------------------------|----------|--|
| Company   | <ul> <li>Sac City Unified School<br/>District</li> </ul> | Date<br>Time | Friday, May 06, 2022<br>09:00 AM | Site     | John Bidwell Elementary<br>School Property |
| Name      | Mike Taxara  |              |                                  | Address  | 1730 65th Avenue                           |
| Address   | 425 First Avenue   |              | Chain-Of-Custody                 |          | Sacramento, CA 95822                       |
|           | Sacramento CA, 95818                                     |              |                                  | Unit     |  |
| Phone     | (916) 395 - 3980   |              |                                  | Claim#   |  |
| Email     | Tina-Alvarez-  |              |                                  | Job #    | 41703                                      |
|           | Bevens@scusd.edu   |              |                                  | Chain #  | 1  |

# Analysis: PLM | TTFP - 400 PT.CT. Turn Around Time: Same Day

| Sample Number: | Location               | Description              |
|----------------|------------------------|--------------------------|
|                |                        |                          |
| 1730-1A        | Girls Restroom, Damage | Texture                  |
|                |                        |                          |
| 1730-1B        | Boys Restroom, Damage  | Texture                  |
|                |                        |                          |
| 1730-1C        | Staff Restroom, Damage | Texture                  |
|                |                        |                          |
| 1730-2         | Girls Restroom, Damage | Sheetrock-Joint Compound |

| Relinquished by (Client) | Date/Time |
|--------------------------|-----------|
|                          |           |
|                          |           |
| Received by (Tech)       | Date/Time |
|                          |           |

| Relinquished by (Tech) | Date/Time               |
|------------------------|-------------------------|
| ~ 20                   | 05/06/2022              |
| S-t-nt                 | 09:00 AM                |
|                        |                         |
| Received by (Lab)      | Date/Time               |
| Received by (Lab)      | Date/Time<br>05/06/2022 |

Sampler: Robert Mullen

Total Number of Samples 4

COC Page # 1 from 1

|                             | PH 916.361.0555   FX 9<br>service@nall.com        | 16.361.0540         |   |        | KS#<br>Client PO<br>Project ID     | ***for office use only***  |
|-----------------------------|---|---------------------|---|--------|------------------------------------|--|
| CLIENT INFORM               | IATION  |                     | SAMPLE                                    |        | JOB SIT                            | TE INFORMATION   |
| Company Sac Cit<br>District |   | Date<br>Time        | Friday, May 06, 2022<br>08:00 AM          | 2      | Site<br>Address                    | Alice Birney Public School<br>6 6251 13th Street                                 |
| Sacram                      | axara<br>st Avenue<br>ento CA, 95818<br>95 - 3980 |                     | Custody   Analytical I<br>Ieuresis Pb200i | Data   | Unit<br>Claim#<br>Job #<br>Chain # | Sacramento, CA 95831<br>26269<br>1   |
| TURN AROUN<br>Same Day      | D LEAD PAINT<br>Inspection                        | MEASUREME<br>Standa |   |        | <b>NG METHOD</b><br>siss Pb200i    | ANALYTICAL DATA<br>Action Level - 1<br>Abatement Level - 1<br>Total Readings - 2 |
| Sample ID:                  | Sample Location   Desc                            | cription            | Structure Material                        | Color  | Conditio                           | on Lead (mg/cm <sup>2</sup> )  |
| 6251-1L                     | Interior Walls, Paint                             |                     | Sheetrock                                 | White  | N/A                                | <lod< th=""></lod<>  |
| 6251-2L                     | Interior Doors, Frames,                           | & Trim, Paint       | Metal                                     | Orange | N/A                                | <lod< td=""></lod<>  |



MicroTest Laboratories Inc. NVLAP Code: 200999-0 3110 Gold Canal Dr. Ste. A. Rancho Cordova, CA 95670 PH 916.567.9808 | FX 916.404.0302 www.microtestlabsinc.com | service@microtestlabsinc.com

Project ID

MT012219535

| CLIENT  | INFORMATION                    |      | SAMPLE               | JOB SITE | E INFORMATION                |
|---------|--------------------------------|------|----------------------|----------|------------------------------|
| Company | National Analytical            | Date | Friday, May 06, 2022 | Sampler  | Robert Mullen                |
|         | Laboratories, Inc.             |      |                      |          |                              |
| Name    | Paula Lee                      | Time | 10:00 AM             | Project  | John Sloat Elementary School |
| Address | 2201 Francisco Drive, Ste. 140 | -    |                      | Address  | 7525 Candlewood Way          |
|         | 261                            |      | MicroTest            |          |                              |
|         | El Dorado Hills CA, 95762      |      |                      |          | Sacramento, CA 95822         |
| Phone   | (916) 361 - 0555               |      | T - L                |          |                              |
| Email   | N.A.L. Distribution List       |      | Laboratories         |          |                              |
|         |                                |      | Analytical Data      |          |                              |

#### POLARIZED LIGHT MICROSCOPY (PLM) EPA METHOD 600 / R-93 / 116 & EPA – 40 CFR Appendix E to Subpart E of Part 763

| Sample  | Accession | Client                 | Laboratory                             | Non Fibrous /              | Asbestiform   |
|---------|-----------|------------------------|--|----------------------------|---------------|
| ID      | Number    | Description            | Description                            | Fibrous Materials          | Minerals %    |
| 7525-1A | 19535-1   | Girls Restroom, Damage | White Plaster<br>Fibrous<br>Homogenous | 5% Cellulose<br>95% Binder | None Detected |
| 7525-1B | 19535-2   | Boys Restroom, Damage  | White Plaster<br>Fibrous<br>Homogenous | 5% Cellulose<br>95% Binder | None Detected |
| 7525-1C | 19535-3   | Staff Restroom, Damage | White Plaster<br>Fibrous<br>Homogenous | 5% Cellulose<br>95% Binder | None Detected |

Date Friday, May 06, 2022

Report

Analyst: Nolan Starbuck


Authorized Signatory:

Samples Received: 3 Samples Analyzed: 3

Kelly Favero - Lab Manager

This analytical data sheet constitutes a final report. Due to the limitation of Polarized Light Microscopy (PLM), some samples classified as containing no asbestos in materials, NoneDetected (ND), such as floor tiles or like materials, warrant a recommendation for further analysis by Transmission Electron Microscopy (TEM). Results apply to the sample as received. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. All Samples will be held for not less than 30 days, upon which they will then be disposed of. This report shall not be reproduced in full without written authorization from MicroTest Laboratories, Inc. Soil and rock matrices are considered problematic matrices and MicroTest recommends sample homogenization prior to PLM analysis. Thermal decomposition of asbestos fibers can yield non-asbestiform mineral properties. The reporting limit for calibrated visual area estimation quantitation procedures is 1%. The reporting limit for 400/1000 point count quantitation procedures is 0.25% or 0.1% respectively. The sample is considered acceptable unless otherwise noted. Sub-samples are analyzed separately accept when manufactured with multiple layers (i.e. Linoluem, Drywall, etc.) or requested contrarily by the client

Documents #MT-PLM-A 1.0 Authorized by Kelly Favero Analytical Page 1 of 1. Proprietary to MicroTest Laboratories, Inc Issue Date: 05/29/18 Rev: 4



Project ID

MT012219535

| CLIENT IN | FORMATION                             |              | Sample                           | JOB SIT | E INFORMATION                   |
|-----------|---------------------------------------|--------------|----------------------------------|---------|---------------------------------|
| Company   | / Sac City Unified School<br>District | Date<br>Time | Friday, May 06, 2022<br>10:00 AM | Site    | John Sloat Elementary<br>School |
| Name      | Mike Taxara                           |              |                                  | Address | s 7525 Candlewood Way           |
| Address   | 425 First Avenue                      |              | Chain-Of-Custody                 |         | Sacramento, CA 95822            |
|           | Sacramento CA, 95818                  |              |                                  | Unit    |                                 |
| Phone     | (916) 395 - 3980                      |              |                                  | Claim#  |                                 |
| Email     | Tina-Alvarez-                         |              |                                  | Job #   | 41704                           |
|           | Bevens@scusd.edu                      |              |                                  | Chain # | 1                               |
|           |                                       |              |                                  | enan "  |                                 |

# **Analysis:** PLM | TTFP - 400 PT.CT. **Turn Around Time:** Same Day

| Sample Number: | Location               | Description |
|----------------|------------------------|-------------|
|                |                        |             |
| 7525-1A        | Girls Restroom, Damage | Plaster     |
|                |                        |             |
| 7525-1B        | Boys Restroom, Damage  | Plaster     |
|                |                        |             |
| 7525-1C        | Staff Restroom, Damage | Plaster     |

| Relinquished by (Client) | Date/Time |
|--------------------------|-----------|
|                          |           |
|                          |           |
| Received by (Tech)       | Date/Time |
|                          |           |
|                          |           |

| Relinquished by (Tech) | Date/Time               |
|------------------------|-------------------------|
| ~ 0                    | 05/06/2022              |
| S-t-nt                 | 10:00 AM                |
|                        |                         |
| Received by (Lab)      | Date/Time               |
| Received by (Lab)      | Date/Time<br>05/06/2022 |

Sampler: Robert Mullen

Total Number of Samples 3

COC Page # 1 from 1

| ENVIRONS  | I.A.I     | PH 916.361.0555   FX 9 | 916.361.0540 |                      |        | KS#<br>Client P(<br>Project I | C         | **for office use only***     |
|-----------|-----------|------------------------|--------------|----------------------|--------|-------------------------------|-----------|------------------------------|
| CLIENT I  | NFORMA    | ATION                  |              | SAMPLE               |        | J                             | OB SITE   | E INFORMATION                |
| Company   | •         | Unified School         | Date         | Friday, May 06, 202  | 2      | 5                             | Site .    | John Sloat Elementary School |
|           | District  |                        | Time         | 10:00 AM             |        | 1                             | Address ' | 7525 Candlewood Way          |
| Name      | Mike Tax  | ara                    |              | ~                    | _      |                               | :         | Sacramento, CA 95822         |
| Address   | 425 First | Avenue                 |              | Custody   Analytical | Data   | I                             | Unit      |                              |
|           | Sacramen  | to CA, 95818           |              | Heuresis Pb200i      |        |                               | Claim#    |                              |
| Phone     | (916) 395 | - 3980                 |              |                      |        | J                             | Job #     | 26271                        |
| Email     |           |                        |              |                      |        | (                             | Chain #   | 1                            |
| TURN A    | ROUND     | LEAD PAINT             | MEASUREME    | ENT MODE SA          | AMPLI  | NG MET                        | ГНОД      | ANALYTICAL DATA              |
| Same      | e Day     | Inspection             | Standa       | ırd                  | Heure  | esis Pb20                     | 00i       | Action Level - 1             |
|           |           |                        |              |                      |        |                               |           | Abatement Level - 1          |
|           |           |                        |              |                      |        |                               |           | Total Readings - 10          |
| Sample ID | ):        | Sample Location   Des  | scription    | Structure Material   | Color  | C                             | Condition | Lead (mg/cm <sup>2</sup> )   |
| 7525-1L   |           | Girl's Restroom Walls. | Tiles        | Ceramic              | Yellow | , Iı                          | ntact     | 93                           |

| Sample Location   Description | Structure Material | Color  | Condition |
|-------------------------------|--------------------|--------|-----------|
| Girl's Restroom Walls, Tiles  | Ceramic            | Yellow | Intact    |
| Boy's Restroom Walls, Tiles   | Ceramic            | Blue   | Intact    |

| 7525-1L | Oni s Resubbili wans, Thes   | Ceranne   | TCHOW  | intact | ).5                 |
|---------|------------------------------|-----------|--------|--------|---------------------|
| 7525-2L | Boy's Restroom Walls, Tiles  | Ceramic   | Blue   | Intact | 12.7                |
|         |                              |           |        |        |                     |
| 7525-3L | Girl's Restroom Floor, Tiles | Ceramic   | Yellow | N/A    | <lod< td=""></lod<> |
| 7525-4L | Boy's Restroom Floor, Tiles  | Ceramic   | Blue   | N/A    | <lod< td=""></lod<> |
| 7525-5L | Staff Restroom Walls, Tiles  | Ceramic   | Multi  | N/A    | <lod< td=""></lod<> |
| 7525-6L | Staff Restroom Floor, Tiles  | Ceramic   | Tan    | N/A    | <lod< td=""></lod<> |
| 7525-7L | Interior Walls, Paint        | Sheetrock | White  | N/A    | <lod< td=""></lod<> |
| 7525-8L | Interior Ceiling, Paint      | Wood      | White  | N/A    | <lod< td=""></lod<> |
| 7525-9L | Interior Doors, Paint        | Metal     | Blue   | N/A    | <lod< td=""></lod<> |

<LOD Below Limit of Detection | Reading < 0.0

LCM Lead Containing Material | Readings Ranging from 0 to < 1.0 mg/cm<sup>2</sup>

LBP Lead Based Paint | Readings Greater than 1.0 mg/cm<sup>2</sup>

| ANALYSIS |
|----------|
|          |

Date May 06, 2022 Time 10:00 AM

| Relinquished by (Client) | Date/Time |
|--------------------------|-----------|
|                          |           |
| Received by (Tech)       | Date/Time |
| Received by (Teen)       | Dute/Time |
|                          |           |

| Relinquished by (Tech) | Date/Time              |
|------------------------|------------------------|
| 5 - nl                 | 05/06/2022<br>10:00 AM |
|                        |                        |
| Received by (Lab)      | Date/Time              |

California Dept. of Public Health www.2.epa.gov/lead



Sampler: Robert Mullen

Analyst: Robert Mullen

Total Number of Samples 10

COC Page 1 from 1



MicroTest Laboratories Inc. NVLAP Code: 200999-0 3110 Gold Canal Dr. Ste. A. Rancho Cordova, CA 95670 PH 916.567.9808 | FX 916.404.0302 www.microtestlabsinc.com | service@microtestlabsinc.com

Project ID

MT012219536

|                | <b>INFORMATION</b>  | <b>D</b> ( | SAMPLE               | 00-0    | E INFORMATION                                     |
|----------------|---|------------|----------------------|---------|---|
| Compan         | y National Analytical<br>Laboratories, Inc.                               | Date       | Friday, May 06, 2022 | Sampler | Robert Mullen                                     |
| Name           | Paula Lee   | Time       | 11:00 AM             | Project | New Joseph Bonnheim Elementary<br>School Property |
| Address        | 261   |            | MicroTest            | Address | 7300 Marin Avenue                                 |
| Phone<br>Email | El Dorado Hills CA, 95762<br>(916) 361 - 0555<br>N.A.L. Distribution List |            | Laboratories         |         | Sacramento, CA 95820                              |
|                |   |            | Analytical Data      |         |   |
|                |   |            |                      |         |   |

## POLARIZED LIGHT MICROSCOPY (PLM) EPA METHOD 600 / R-93 / 116 & EPA – 40 CFR Appendix E to Subpart E of Part 763

| Sample | Accession | Client                | Laboratory   | Non Fibrous /                | Asbestiform   |
|--------|-----------|-----------------------|--|------------------------------|---------------|
| ID     | Number    | Description           | Description  | Fibrous Materials            | Minerals %    |
| 7300-1 | 19536-1   | Boys Restroom Ceiling | White/Yellow Ceiling Tile<br>Fibrous<br>Homogenous | 90% Fiberglass<br>10% Binder | None Detected |

Report

Date

Friday, May 06, 2022


Analyst: Nolan Starbuck

Authorized Signatory:

Samples Received: 1 Samples Analyzed: 1

Kelly Favero - Lab Manager

This analytical data sheet constitutes a final report. Due to the limitation of Polarized Light Microscopy (PLM), some samples classified as containing no asbestos in materials, NoneDetected (ND), such as floor tiles or like materials, warrant a recommendation for further analysis by Transmission Electron Microscopy (TEM). Results apply to the sample as received. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. All Samples will be held for not less than 30 days, upon which they will then be disposed of. This report shall not be reproduced in full without written authorization from MicroTest Laboratories, Inc. Soil and rock matrices are considered problematic matrices and MicroTest recommends sample homogenization prior to PLM analysis. Thermal decomposition of asbestos fibers can yield non-asbestiform mineral properties. The reporting limit for calibrated visual area estimation quantitation procedures is 1%. The reporting limit for 400/1000 point count quantitation procedures is 0.25% or 0.1% respectively. The sample is considered acceptable unless otherwise noted. Sub-samples are analyzed separately accept when manufactured with multiple layers (i.e. Linoluem, Drywall, etc.) or requested contrarily by the client



Project ID

MT012219536

| CLIENT IN | FORMATION  |              | Sample                           | JOB SITE | E INFORMATION                            |
|-----------|--|--------------|----------------------------------|----------|--|
| Company   | <ul> <li>Sac City Unified School<br/>District</li> </ul> | Date<br>Time | Friday, May 06, 2022<br>11:00 AM | Site     | New Joseph Bonnheim<br>Elementary School |
| Name      | Mike Taxara  |              | Chain Of Custody                 |          | Property                                 |
| Address   | 425 First Avenue   |              | Chain-Of-Custody                 | Address  | 7300 Marin Avenue                        |
|           | Sacramento CA, 95818                                     |              |                                  |          | Sacramento, CA 95820                     |
| Phone     | (916) 395 - 3980   |              |                                  | Unit     |  |
| Email     | Tina-Alvarez-  |              |                                  | Claim#   |  |
|           | Bevens@scusd.edu   |              |                                  | Job #    | 41705                                    |
|           |  |              |                                  | Chain #  | 1  |
|           |  |              |                                  |          |  |

# Analysis: PLM | TTFP - 400 PT.CT. Turn Around Time: Same Day

| Sample Number: | Location              | Description           |
|----------------|-----------------------|-----------------------|
| 7300-1         | Boys Restroom Ceiling | Acoustic Ceiling Tile |

| Date/Time |
|-----------|
|           |
| Date/Time |
|           |
|           |

| Relinquished by (Tech) |                         |
|------------------------|-------------------------|
| ~ 20                   | 05/06/2022              |
| S-t-nt                 | 11:00 AM                |
|                        |                         |
| Received by (Lab)      | Date/Time               |
| Received by (Lab)      | Date/Time<br>05/06/2022 |

Sampler: Robert Mullen

Total Number of Samples 1

COC Page # 1 from 1

| INVIRON                                     | J-A-I     | PH 916.361.0555   FX 9  | 016.361.0540                       |                    |                           | KS#<br>Client PO<br>Project ID                | ***fo           | or office use only***      |
|---|-----------|---|------------------------------------|--------------------|---------------------------|---|-----------------|----------------------------|
| CLIENT I                                    | NFORMA    | ATION   |                                    | SAMPLE             |                           | JOB S   | ITE I           | NFORMATION                 |
| Company Sac City Unified School<br>District |           | Date         Friday, May 06, 2022           Time         11:00 AM |                                    | Site               |                           | w Joseph Bonnheim<br>ementary School Property |                 |                            |
| Name  | Mike Tax  | ara   |                                    |                    | Address 7300 Marin Avenue |   | 00 Marin Avenue |                            |
| Address                                     | 425 First | Avenue  | Chain-Of-Custody   Analytical Data |                    |                           | Sacramento, CA 95820                          |                 | cramento, CA 95820         |
|   | Sacramen  | to CA, 95818  |                                    | Heuresis Pb200i    |                           | Unit  |                 |                            |
| Phone                                       | (916) 395 | - 3980  |                                    |                    |                           | Claim   | <b>i</b> #      |                            |
| Email                                       |           |   |                                    |                    |                           | Job #   | 26              | 272                        |
|   |           |   |                                    |                    |                           | Chair   | n#1             |                            |
| TURN A                                      | AROUND    | LEAD PAINT  | MEASUREME                          | NT MODE S          | AMPLI                     | NG METHOI                                     | )               | ANALYTICAL DATA            |
| Sam   | e Day     | Inspection  | Standa                             | urd                | Heure                     | euresis Pb200i                                |                 | Action Level - 1           |
|   |           |   |                                    |                    |                           |   |                 | Abatement Level - 1        |
|   |           |   |                                    |                    |                           |   |                 | Total Readings - 1         |
| Sample ID                                   | ):        | Sample Location   Des   | cription                           | Structure Material | l Color                   | Condi   | tion            | Lead (mg/cm <sup>2</sup> ) |
| 7300-1L                                     |           | Interior Doors, Frames,   | & Trim, Paint                      | Metal              | Blue                      | N/A   |                 | <lod< td=""></lod<>        |

<LOD Below Limit of Detection | Reading < 0.0

LCM Lead Containing Material | Readings Ranging from 0 to < 1.0 mg/cm<sup>2</sup>

LBP Lead Based Paint | Readings Greater than 1.0 mg/cm<sup>2</sup>

| ANALYSIS |  |
|----------|--|
| 06.0000  |  |

 Date
 May 06, 2022

 Time
 11:00 AM

| Relinquished by (Client) | Date/Time |
|--------------------------|-----------|
|                          |           |
|                          |           |
| Received by (Tech)       | Date/Time |
|                          |           |
|                          |           |

| Relinquished by (Tech) | Date/Time              |
|------------------------|------------------------|
| 5 nl                   | 05/06/2022<br>11:00 AM |
|                        |                        |
| Received by (Lab)      | Date/Time              |

California Dept. of Public Health www.2.epa.gov/lead



Sampler: Robert Mullen

Analyst: Robert Mullen

Total Number of Samples 1

COC Page 1 from 1



MicroTest Laboratories Inc. NVLAP Code: 200999-0 3110 Gold Canal Dr. Ste. A. Rancho Cordova, CA 95670 PH 916.567.9808 | FX 916.404.0302 www.microtestlabsinc.com | service@microtestlabsinc.com

Project ID

MT012219537

| Commonwi |                                 | SAMPLE    |                      | JOB SITE INFORMATION |                         |  |
|----------|---------------------------------|-----------|----------------------|----------------------|-------------------------|--|
| Company  | National Analytical             | Date      | Friday, May 06, 2022 | Sampler              | Robert Mullen           |  |
| ]        | Laboratories, Inc.              |           |                      |                      |                         |  |
| Name 1   | Paula Lee                       | Time      | 11:30 AM             | Project              | Tahoe Elementary School |  |
| Address  | 2201 Francisco Drive, Ste. 140- |           |                      | Address              | 3110 60th Street        |  |
|          | 261                             | MicroTest |                      |                      |                         |  |
| ]        | El Dorado Hills CA, 95762       |           |                      |                      | Sacramento, CA 95820    |  |
| Phone    | (916) 361 - 0555                |           | I ab anatomias       |                      |                         |  |
| Email    | N.A.L. Distribution List        |           | Laboratories         |                      |                         |  |
|          |                                 |           | Analytical Data      |                      |                         |  |

## POLARIZED LIGHT MICROSCOPY (PLM) EPA METHOD 600 / R-93 / 116 & EPA – 40 CFR Appendix E to Subpart E of Part 763

| Sample  | Accession | Client                                | Laboratory  | Non Fibrous /               | Asbestiform   |
|---------|-----------|---------------------------------------|---|-----------------------------|---------------|
| ID      | Number    | Description                           | Description   | Fibrous Materials           | Minerals %    |
| 3110-1A | 19537-1   | Staff Restroom, Damage                | White Texture<br>Non-Fibrous<br>Homogenous                | 100% Binder                 | None Detected |
| 3110-1B | 19537-2   | Boys Restroom, Damage                 | White Texture<br>Non-Fibrous<br>Homogenous                | 100% Binder                 | None Detected |
| 3110-1C | 19537-3   | Girls Restroom, Damage                | White Texture<br>Non-Fibrous<br>Homogenous                | 100% Binder                 | None Detected |
| 3110-2  | 19537-4   | Staff Restroom, Damage                | White Sheetrock-Joint Compound<br>Fibrous<br>Heterogenous | 10% Cellulose<br>90% Binder | None Detected |
| 3110-3A | 19537-5   | Staff Restroom, Damage,<br>Multicolor | Gray Tile<br>Non-Fibrous<br>Homogenous                    | 100% Binder                 | None Detected |
| 3110-3B | 19537-6   | Staff Restroom, Damage                | Black Mastic<br>Non-Fibrous<br>Homogenous                 | 100% Binder                 | None Detected |

| Report |                      |  |  |  |  |  |
|--------|----------------------|--|--|--|--|--|
| Date   | Friday, May 06, 2022 |  |  |  |  |  |

Analyst: Nolan Starbuck

Authorized Signatory:

Samples Received: 7 Samples Analyzed: 7

Kelly Favero - Lab Manager

This analytical data sheet constitutes a final report. Due to the limitation of Polarized Light Microscopy (PLM), some samples classified as containing no asbestos in materials, NoneDetected (ND), such as floor tiles or like materials, warrant a recommendation for further analysis by Transmission Electron Microscopy (TEM). Results apply to the sample as received. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. All Samples will be held for not less than 30 days, upon which they will then be disposed of. This report shall not be reproduced in full without written authorization from MicroTest Laboratories, Inc. Soil and rock matrices are considered problematic matrices and MicroTest recommends sample homogenization prior to PLM analysis. Thermal decomposition of asbestos fibers can yield non-asbestiform mineral properties. The reporting limit for calibrated visual area estimation quantitation procedures is 1%. The reporting limit for 400/1000 point count quantitation procedures is 0.25% or 0.1% respectively. The sample is considered acceptable unless otherwise noted. Sub-samples are analyzed separately accept when manufactured with multiple layers (i.e. Linoluem, Drywall, etc.) or requested contrarily by the client

Documents #MT-PLM-A 1.0 Authorized by Kelly Favero Analytical Page 1 of 2. Proprietary to MicroTest Laboratories, Inc Issue Date: 05/29/18 Rev: 4



MicroTest Laboratories Inc. NVLAP Code: 200999-0 3110 Gold Canal Dr. Ste. A. Rancho Cordova, CA 95670 PH 916.567.9808 | FX 916.404.0302 www.microtestlabsinc.com | service@microtestlabsinc.com

3110-4 19537-7 Staff Restroom, Damage

Cream Mastic Non-Fibrous Homogenous **Project ID** 

MT012219537

100% Binder

None Detected

Date

Friday, May 06, 2022

Report

Analyst: Nolan Starbuck

Authorized Signatory:

Samples Received: 7 Samples Analyzed: 7

Kelly Favero - Lab Manager

This analytical data sheet constitutes a final report. Due to the limitation of Polarized Light Microscopy (PLM), some samples classified as containing no asbestos in materials, NoneDetected (ND), such as floor tiles or like materials, warrant a recommendation for further analysis by Transmission Electron Microscopy (TEM). Results apply to the sample as received. This report must not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. All Samples will be held for not less than 30 days, upon which they will then be disposed of. This report shall not be reproduced in full without written authorization from MicroTest Laboratories, Inc. Soil and rock matrices are considered problematic matrices and MicroTest recommends sample homogenization prior to PLM analysis. Thermal decomposition of asbestos fibers can yield non-asbestiform mineral properties. The reporting limit for calibrated visual area estimation quantitation procedures is 1%. The reporting limit for 400/1000 point count quantitation procedures is 0.25% or 0.1% respectively. The sample is considered acceptable unless otherwise noted. Sub-samples are analyzed separately accept when manufactured with multiple layers (i.e. Linoluem, Drywall, etc.) or requested contrarily by the client

Documents #MT-PLM-A 1.0 Authorized by Kelly Favero Analytical Page 2 of 2. Proprietary to MicroTest Laboratories, Inc Issue Date: 05/29/18 Rev: 4



**Project ID** MT012219537

| CLIENT INFORMATION                      | Sample                    | JOB SITE INFORMATION         |  |
|---|---------------------------|------------------------------|--|
| Company Sac City Unified School         | Date Friday, May 06, 2022 | Site Tahoe Elementary School |  |
| District                                | Time 11:30 AM             | Address 3110 60th Street     |  |
| Name Mike Taxara                        | Chain-Of-Custody          | Sacramento, CA 95820         |  |
| Address 425 First Avenue                | Chain-Or-Custody          | Unit                         |  |
| Sacramento CA, 95818                    |                           | Claim#                       |  |
| Phone (916) 395 - 3980                  |                           | <b>Job #</b> 41706           |  |
| Email Tina-Alvarez-<br>Bevens@scusd.edu |                           | Chain # 1                    |  |

# Analysis: PLM | TTFP - 400 PT.CT. Turn Around Time: Same Day

| Sample Number: | Location                           | Description              |
|----------------|------------------------------------|--------------------------|
| 3110-1A        | Staff Restroom, Damage             | Texture                  |
| 3110-1B        | Boys Restroom, Damage              | Texture                  |
| 3110-1C        | Girls Restroom, Damage             | Texture                  |
| 3110-2         | Staff Restroom, Damage             | Sheetrock-Joint Compound |
| 3110-3A        | Staff Restroom, Damage, Multicolor | Floor Tile               |
| 3110-3B        | Staff Restroom, Damage             | Mastic                   |
| 3110-4         | Staff Restroom, Damage             | Cove Base Mastic         |

| Relinquished by (Client) | Date/Time |
|--------------------------|-----------|
|                          |           |
|                          |           |
| Received by (Tech)       | Date/Time |
|                          |           |
|                          |           |

| Relinquished by (Tech) | Date/Time               |  |
|------------------------|-------------------------|--|
| ~ 20                   | 05/06/2022              |  |
| S-t-nt                 | 11:30 AM                |  |
|                        |                         |  |
| Received by (Lab)      | Date/Time               |  |
| Received by (Lab)      | Date/Time<br>05/06/2022 |  |

Sampler: Robert Mullen

Total Number of Samples 7

COC Page # 1 from 1

| PH 916.361.0555   FX 916.361.0540<br>service@nall.com |                                 |                                 |                 |   |                      | ***for office use only***<br>KS#<br>Client PO<br>Project ID |                              |  |
|---|---------------------------------|---------------------------------|-----------------|---|----------------------|---|------------------------------|--|
| CLIENT I  | INFORM                          | ATION                           |                 | SAMPLE  |                      | JOB SIT   | E INFORMATION                |  |
| Company   | Company Sac City Unified School |                                 | Date            | Friday, May 06, 202                                   | 2                    | Site  | Tahoe Elementary School      |  |
|   | District                        |                                 | Time            | <b>Time</b> 11:30 AM                                  |                      | Address 3110 60th Street                                    |                              |  |
| Name Mike Taxara                                      |                                 |                                 |                 | Dete  | Sacramento, CA 95820 |   |                              |  |
| Address   | 425 First                       |                                 |                 | Chain-Of-Custody   Analytical Data<br>Heuresis Pb200i |                      | Unit  |                              |  |
|   |                                 | to CA, 95818                    |                 | 11curesis F 02001                                     | leuresis Pb2001      |   |                              |  |
| Phone   | (916) 395                       | - 3980                          |                 |   |                      | Job # 26273<br>Chain # 1                                    |                              |  |
| Email   |                                 |                                 |                 |   |                      |   |                              |  |
| TURN A  | AROUND                          | LEAD PAINT                      | MEASUREMI       | ENT MODE SA   | AMPLI                | NG METHOD   | ANALYTICAL DATA              |  |
| Sam   | e Day                           | Inspection                      | Standa          | Standard Heu  |                      | esis Pb200i   | Action Level - 1             |  |
|   |                                 |                                 |                 |   |                      |   | Abatement Level - 1          |  |
|   |                                 |                                 |                 |   |                      |   | Total Readings - 10          |  |
| Sample ID   | ):                              | Sample Location   De            | scription       | Structure Material                                    | Color                | Condition   | n Lead (mg/cm <sup>2</sup> ) |  |
| 3110-1L   |                                 | Girl's Restroom Walls,          | Tiles           | Ceramic   | Tan                  | Intact  | 12.3                         |  |
| 3110-2L   |                                 | Boy's Restroom Walls,           | Tiles           | Ceramic   | Multi                | Intact  | 12.3                         |  |
| 3110-3L   |                                 | Staff Restroom Walls/0          | Ceiling, Paint  | Sheetrock   | Tan                  | N/A   | <lod< td=""></lod<>          |  |
| 3110-4L   |                                 | Staff Restroom, Doors,<br>Paint | Frames, & Trim, | Metal   | Tan                  | N/A   | <lod< td=""></lod<>          |  |
| 3110-5L   |                                 | Boy's Restroom Walls/           | Ceiling, Paint  | Sheetrock   | Tan                  | N/A   | <lod< td=""></lod<>          |  |
| 3110-6L   |                                 | Girl's Restroom Walls/          | Ceiling, Paint  | Sheetrock   | Tan                  | N/A   | <lod< td=""></lod<>          |  |

<LOD Below Limit of Detection | Reading < 0.0

Paint

LCM Lead Containing Material | Readings Ranging from 0 to < 1.0 mg/cm<sup>2</sup>

Boy's Restroom, Doors, Frames, & Trim,

LBP Lead Based Paint | Readings Greater than 1.0 mg/cm<sup>2</sup>

Boy's Restroom Floor, Tiles

| ANALYSIS |  |
|----------|--|
|          |  |

 Date
 May 06, 2022

 Time
 11:30 AM

3110-7L

3110-8L

| Relinquished by (Client) | Date/Time |
|--------------------------|-----------|
|                          |           |
| Received by (Tech)       | Date/Time |
| Received by (Teen)       | Date/Time |
|                          |           |

| Relinquished by (Tech) | Date/Time              |
|------------------------|------------------------|
| 5 Pnl                  | 05/06/2022<br>11:30 AM |
|                        |                        |
| Received by (Lab)      | Date/Time              |

Metal

Ceramic

Blue

Blue

N/A

N/A

California Dept. of Public Health www.2.epa.gov/lead



Sampler: Robert Mullen

<LOD

<LOD

Analyst: Robert Mullen

Total Number of Samples 10

| Sample ID: | Sample Location   Description                    | Structure Material | Color | Condition | Lead (mg/cm <sup>2</sup> ) |
|------------|--|--------------------|-------|-----------|----------------------------|
| 3110-9L    | Girl's Restroom, Doors, Frames, & Trim,<br>Paint | Metal              | Blue  | N/A       | <lod< td=""></lod<>        |
| 3110-10L   | Girl's Restroom Floor, Tiles                     | Ceramic            | Green | N/A       | <lod< td=""></lod<>        |

<LOD Below Limit of Detection | Reading < 0.0

LCM Lead Containing Material | Readings Ranging from 0 to < 1.0 mg/cm<sup>2</sup>

LBP Lead Based Paint | Readings Greater than 1.0 mg/cm<sup>2</sup>

| ANALYSIS |   |
|----------|---|
|          | 1 |

 Date
 May 06, 2022

 Time
 11:30 AM

| Relinquished by (Client) | Date/Time |
|--------------------------|-----------|
|                          |           |
|                          |           |
| Received by (Tech)       | Date/Time |
|                          |           |

| Relinquished by (Tech) | Date/Time              |
|------------------------|------------------------|
| 5 - nl                 | 05/06/2022<br>11:30 AM |
|                        |                        |
| Received by (Lab)      | Date/Time              |


California Dept. of Public Health www.2.epa.gov/lead





Sampler: Robert Mullen

Analyst: Robert Mullen

Total Number of Samples 10







AIR QUALITY MANAGEMENT DISTRICT

# **Asbestos Survey Form**

(See Instructions)

| 1.Purpose of   | Survey            |              | x            | Renov                 | vation                 |             |             |                      | Demoli       | tion                 |
|--|-------------------|--------------|--------------|-----------------------|------------------------|-------------|-------------|----------------------|--------------|----------------------|
| 2.Facility Info  | rmation           |              |              |                       |                        |             |             |                      |              |                      |
| Project Area(s)  | escription        |              |              |                       |                        |             |             |                      |              |                      |
| New Joseph Bonnheim Elementary School - Restrooms          |                   |              |              |                       |                        |             |             |                      |              |                      |
| Address  | Address City # of |              |              |                       |                        |             |             |                      |              | # of<br>Structures   |
| 7300 Marin Avenue Sacramento Sacramento                    |                   |              |              |                       |                        |             |             |                      |              |                      |
| 3.Owner Info   | rmation           |              |              |                       |                        |             |             |                      |              |                      |
| Name   |                   |              |              |                       |                        |             |             |                      |              |                      |
| Address  |                   |              |              |                       | City/State             |             |             |                      |              | Zip                  |
| Contact  |                   | Phone        |              |                       | Fax                    |             |             | Email                |              |                      |
|  |                   | •            |              |                       |                        |             |             |                      |              |                      |
| 4.Consultant   | Informat          | ion s        | Survey       | Date(s):              | 05/06/22               |             |             |                      |              |                      |
| Company Name   | Natio             |              | - h - C I    | Labara                |                        |             |             |                      |              |                      |
| Name Misha   |                   |              | alytical     | Labora                | toires, Inc.           |             |             |                      | DOSH ;       | 4                    |
| Micha  | ael J. Le         | е            |              |                       |                        |             |             |                      | DUSIT        | 06-4047              |
| Address<br>2201 Francisco                                  | Dr. Ste. 1        | 40-261       | City/Sta     | te<br>El Dora         | ado Hills, CA          |             |             |                      |              | <sup>Zip</sup> 95762 |
| Phone<br>916-361-0555                                      | Fax<br>916-3      | 61-0540      | E            | <sup>mail</sup> Paula | @nal1.com              |             |             | Signatu              | re           | 10                   |
| 5. Client Informa  |                   |              |              |                       | eral Contractor        |             |             | rance Co             | ompany       |                      |
| Name   |                   | ☐Archite     | ect          |                       | operty Manage          | ſ           | □Oth        | er                   |              |                      |
| Name   |                   |              |              |                       |                        |             |             |                      |              |                      |
| Address  |                   |              |              |                       | City/State             |             |             |                      |              | Zip                  |
| Contact  |                   | Phone        |              |                       | Fax                    |             | Email       |                      |              |                      |
| 6.Have all of  | the susp          | ect mate     | erials tl    | nat will b            | e disturbed b          | een sa      | mpled       | 1?                   |              | ⊡Yes                 |
|  |                   |              |              |                       |                        |             |             |                      |              | □No                  |
| If no, explain v   | vhy:              |              |              |                       |                        |             |             |                      |              |                      |
| 7.Summary o  | f Total A         | chastas      | Conta        | ining Ma              | torial (ACM) F         | indina      | 6           |                      |              |                      |
|  |                   |              |              |                       | . ,                    |             | 3           | 1                    |              |                      |
| Regulated Ask<br>(Includes materials<br>fire damaged mater | subject to kn     |              |              |                       | Categ                  | jory II     |             |                      | Categ        | ory I                |
| _  | -                 | ж <b>Г</b> + | -            | bio Et                | Squara Et              | Line        | or Et       | Sau                  | -<br>ara Et  | Lincor Et            |
| Square Ft.   | Linea             | п Г.         |              | bic Ft.               | Square Ft.             |             | ar Ft.      | Squ                  | are Ft.      | Linear Ft.           |
|  |                   |              |              |                       |                        |             |             |                      |              |                      |
| To rece  | eive future       | SMAQME       | Rule up      | dates and             | changes affect         | ing your    | indust      | try (cheo            | ck one bo    | ox):                 |
| Please send e-m  | ail notices to    |              |              |                       | will sign up myself at | www.airqu   | uality.org/ | <u>/listserve/</u> t | o receive e- | mailed notices.      |
| □I am already su   | bscribed.         | I want       | the District | to mail notice        | s to the address on th | is applicat | ion:        |                      | wner         | Consultant           |

## **SMAQMD Survey Form Instructions**

- #1. Check the appropriate box as to whether the survey is for a Renovation or Demolition as defined by SMAQMD Rule 902, at the time the survey was conducted. Demolitions require sampling of all suspect materials unless assumed to contain asbestos or only a small area is being impacted by the demolition, ie, the entire building will not be razed. An example of this would be where only a load bearing wall(s) is removed but the building will remain intact. In those cases, explain why all suspect materials in the structure were not sampled in item #6. Renovations (TI's, soft demo's, remodels) require sampling of only the suspect materials that are going to be disturbed.
- #2. Provide the description and function of the building(s) or area(s), ie, "School-Boiler Room", within the building(s) being surveyed. Include the total number of floors surveyed. Provide the address of building(s) surveyed. If multiple buildings are on site, provide the total number of structures surveyed, include portables, outbuildings, garages, sheds, etc.
- #3. Provide owner information.
- #4. Provide consultant information and the date on which each building/area was surveyed in item #2.
- #5. The client refers to whoever requested the survey to be conducted and provided demolition/renovation information to the consultant. If the client is the owner in #3, leave this section blank.
- #6. Unless assumed to contain asbestos, all suspect materials must be sampled prior to a demolition. Prior to a renovation, unless assumed to contain asbestos, suspect materials >160 square feet, 260 linear feet, or 35 cubic feet that will be abated, stripped, or removed must be sampled. You cannot assume suspect materials are negative. Samples taken must be based on the Asbestos Hazard Emergency Response Act (AHERA) guidelines for homogeneous areas but must include both the interior <u>and exterior</u> suspect materials, floor to roof. The list below provides common suspect materials. Surfacing materials requiring 3,5,7 protocol are noted (3,5,7). The SMAQMD considers stucco a surfacing material. All other sampling may be done "sufficient to determine".

### EPA Category of Common Suspect Asbestos Containing Materials

Note: This list does not include every product that may contain asbestos. It is intended as a general guide to show the proper NESHAP categories of materials typically containing asbestos.

| Regulated Asbestos Containing Material                 | Category II                                  |
|--|--|
| <ul> <li>Fireproofing (3,5,7)</li> </ul>               | • Stucco (3,5,7)                             |
| <ul> <li>Acoustical Ceiling Texture (3,5,7)</li> </ul> | Window Glazing                               |
| • Plaster (3,5,7)                                      | <ul> <li>Cement Board/Transite</li> </ul>    |
| <ul> <li>Wall Texture (3,5,7)</li> </ul>               | Mastics                                      |
| <ul> <li>Ceiling Tiles</li> </ul>                      | <ul> <li>Textured Paints/Coatings</li> </ul> |
| <ul> <li>HVAC Duct Insulation</li> </ul>               | Chalkboards                                  |
| <ul> <li>Thermal System Insulation</li> </ul>          | <ul> <li>Lab Hoods/Table Tops</li> </ul>     |
| <ul> <li>Mudded Pipe Elbow Insulation</li> </ul>       | Cement Pipes                                 |
| <ul> <li>Linoleum Backing</li> </ul>                   | <ul> <li>Cement Roofing Shingles</li> </ul>  |
| <ul> <li>Furnace Insulation</li> </ul>                 | Caulking                                     |
| <ul> <li>Fire Doors</li> </ul>                         | <u>Category I</u>                            |
| <ul> <li>Nicolite Roofing paper</li> </ul>             | <ul> <li>Asphalt Flooring</li> </ul>         |
|  | <ul> <li>Roofing Shingles</li> </ul>         |
|  | <ul> <li>Built-up Roofing</li> </ul>         |
|  | Base Flashing                                |
|  | <ul> <li>Rolled Roofing</li> </ul>           |
|  | <ul> <li>Boiler/Tank Insulation</li> </ul>   |
|  | Vinyl Floor Tile                             |

#7. This is an estimate total of all RACM, Category I & Category II materials found in <u>all</u> structures listed in item #2. If Category I & II materials were subjected to fire or will be subjected to mechanical forces during removal, they must be designated as RACM. An asbestos containing material must only be designated to one category. Category I or II material cannot be listed as RACM.


## Attachments (Include with Survey)

I. Findings & Recommendations

Explain the significance of the data in item #7. State that Category I material may be left in place during demolition and that RACM and Cementitious Category II material must be removed prior to the renovation or demolition. Explain that the amounts listed are to be used by the owner to obtain accurate bids from abatement contractors. State whether this is a jurisdictional project under the requirements of the federal NESHAP and SMAQMD Rule 902. For unimpacted areas in a renovation, state that untested suspect materials must be tested prior to additional future projects where the materials will be disturbed.

### II. Floor Plan Map(s)

Create a separate Floor Plan Map (see example below) for each floor or area of every structure surveyed in item #2. If the roof or exterior is impacted by the project, create a separate map for the roof and exterior or include them on one of the floor maps as seen below. Name each room sampled by the commonly used name and state whether the area is undergoing Renovation or Demolition. A demolition is the wrecking, taking out or burning of any load supporting structural member. A renovation is everything else. If the survey is conducted after the demo/reno has occurred, inspect all dumpsters outside of building. Record the location of each sample taken and identify each sample with a unique identifier that will be the same as reported to the laboratory and in the following appendices. Use "+" to describe >1% or "-" to describe = to or <1% asbestos.



Example: Building 1 - Floor Plan Map

• 29+

**Roof** 23+, 24+, 25 thru 28 -

## III. Sample Results

Create a table (see example below of minimal information needed to comply with SMAQMD Rule 902) for all samples >1% from all structures surveyed in item #2. Category I or Category II materials subject to known mechanical removal or fire damage must be considered RACM. Add more rows and columns as needed.

| Sample(s)<br>ID# | Suspect<br>Material | Asbestos<br>Content<br>(%)<br>(PLM/PC) | EPA<br>Category                 | Total<br>Quantity<br>Sq./Ln/Cu.<br>Ft. |
|------------------|---------------------|--|---------------------------------|--|
| 1                | Ceiling tile        | 2.6-PC                                 | RACM                            | 250 sqft                               |
| 4                | Linoleum            | 40-PLM                                 | RACM                            | 800 sqft                               |
| 5                | Floor<br>mastic     | 1.4-PC                                 | RACM<br>(mechanical<br>removal) | 250 sqft                               |
| 14,16, 18        | TSI                 | 80-PLM                                 | RACM                            | 1,200 li.ft.                           |
| 15,17, 19        | Wall<br>texture     | 3-PC                                   | RACM                            | 2,500 sqft                             |
| 21               | Floor tile          | 8-PLM                                  | CAT II                          | 2,500 sqft                             |
| 20               | Transite<br>panels  | 45-PLM                                 | CAT II                          | 1,100 sqft                             |
| 23               | Nicolite felt       | Assumed                                | RACM                            | 12,000 sqft                            |
| 24               | Roof<br>mastic      | 2-PLM                                  | CATI                            | 12,000 sqft                            |
| 29, 30, 31       | Stucco              | 1.7 PC                                 | RACM                            | 5,40 <del>0</del> sqft                 |

| Example: Building 1 | - Sample Results |
|---------------------|------------------|
|---------------------|------------------|

### IV. Lab Results

Point count (PC) all samples <10% unless assumed > 1%

V. Current proof of certification of person listed in item #4

# Special Note: The following are common causes for survey rejection and potential citation by SMAQMD:

(1)-Survey form or Appendices incomplete, incorrect or missing attachments.

(2)-All suspect materials are not sampled or assumed to be asbestos containing in the survey (for any reason).


(3)-Affected suspect materials are not sampled utilizing the 3,5,7 protocol.

(4)-Point counts were not conducted, sheetrock was not composite sampled, non-sheetrock materials were composite sampled.

(5)-"Limited Surveys or Inaccessible Areas"- The SMAQMD is aware that renovations impact specific areas within a structure and therefore will not require sampling throughout the entire structure as a demolition survey would require. Stating that a **survey is** "limited" because all areas of the project will not be impacted or areas are inaccessible will result in rejection of the survey unless good cause is provided. There is no requirement to sample inaccessible materials, ie, materials behind a wall or encased in concrete; however, state in the "Findings & Recommendations" that upon discovery of previously untested, inaccessible suspect materials, work must cease until further sampling is conducted. Locked rooms or spaces above drop ceiling tiles are not considered inaccessible and <u>are</u> required to be sampled. The owner/operator must provide access to all impacted areas. Failure to sample suspect materials for "cosmetic" reasons will be rejected.

It is important to state that you cannot be prevented and/or instructed by the owner/operator as to what materials are to be sampled. This is determined by whoever conducts the survey and will give cause for survey rejection and potential citation to the owner/operator for failure to adequately survey all suspect materials.

Survey Instructions (4\_13)



AIR QUALITY MANAGEMENT DISTRICT

# **Asbestos Survey Form**

(See Instructions)

| 1.Purpose of   | Survey        |                         | x              | Renov                 | vation                           |          |               |                 | Demoli   | tion                 |
|--|---------------|-------------------------|----------------|-----------------------|----------------------------------|----------|---------------|-----------------|----------|----------------------|
| 2.Facility Info  | rmation       |                         |                |                       |                                  |          |               |                 |          |                      |
| Project Area(s)  | escription    |                         |                |                       |                                  |          |               |                 |          |                      |
| Tahoe Elemer   | ntary Scho    | ol - Res                | strooms        |                       |                                  |          |               |                 |          |                      |
| Address  |               |                         |                |                       |                                  | City     |               |                 |          | # of<br>Structures   |
| 3110 60th Stre   | et            |                         |                |                       |                                  | Sacrai   | mento         |                 |          |                      |
| 3.Owner Info   | rmation       |                         |                |                       |                                  |          |               |                 |          |                      |
| Name   |               |                         |                |                       |                                  |          |               |                 |          |                      |
| Address  |               |                         |                |                       | City/State                       |          |               |                 |          | Zip                  |
| Contact  |               | Phone                   |                |                       | Fax                              |          |               | Email           |          | 1                    |
| 4.Consultant   | Informat      | ion (                   | Survey         | Date(s):              | 05/06/22                         |          |               |                 |          |                      |
| Company Name   | Natio         |                         | alvtical       | Labora                | toiros Inc                       |          |               |                 |          |                      |
| Name Michael   |               |                         | aiyuCal        |                       | toires, Inc.                     |          |               |                 | DOSH #   | ŧ                    |
| Micha  | ael J. Le     | e                       |                |                       |                                  |          |               |                 |          | 06-4047              |
| Address<br>2201 Francisco                                  | Dr. Ste. 1    | 40-261                  | City/Stat      |                       | ado Hills, CA                    |          |               |                 |          | <sup>Zip</sup> 95762 |
| Phone<br>916-361-0555                                      | Fax<br>916-3  | 61-0540                 |                | <sup>nail</sup> Paula | @nal1.com                        |          |               | Signature       | Ŕ        | to                   |
| 5. Client Informa  | •             | rent than ∉<br>∃Archite |                |                       | eral Contractor<br>operty Manage | r        | □lnsu<br>□Oth | rance Cor<br>er | npany    |                      |
| Name   |               |                         |                |                       |                                  |          |               |                 |          |                      |
| Address  |               |                         |                |                       | City/State                       |          |               |                 |          | Zip                  |
| Contact  |               | Phone                   |                |                       | Fax                              |          | Email         |                 |          |                      |
| 6.Have all of  | the susp      | ect mat                 | erials th      | at will b             | e disturbed b                    | een sa   | mpled         | ?               |          | ⊠Yes                 |
| lf no, explain v   | vbv:          |                         |                |                       |                                  |          |               |                 |          | □No                  |
|  | viry.         |                         |                |                       |                                  |          |               |                 |          |                      |
| 7.Summary o  | f Total A     | sbestos                 | Contai         | ning Ma               | terial (ACM) F                   | inding   | S             |                 |          |                      |
| Regulated Ask<br>(Includes materials<br>fire damaged mater | subject to kn |                         |                |                       | Categ                            | jory II  |               |                 | Categ    | ory I                |
| Square Ft.   | Linea         | r Ft.                   | Cub            | oic Ft.               | Square Ft.                       | Line     | ar Ft.        | Squa            | re Ft.   | Linear Ft.           |
|  |               |                         |                |                       |                                  |          |               |                 |          |                      |
| To rece  | eive future   | SMAQM                   | l<br>D Rule up | dates and             | changes affect                   | ing your | r indust      | ry (checl       | k one bo | x):                  |
| Please send e-m  |               | •                       | •              |                       | will sign up myself at           | •••      |               |                 |          | ,                    |
| I am already su  |               | □l want                 | the District t |                       | s to the address on th           |          |               |                 |          |                      |

## **SMAQMD Survey Form Instructions**

- #1. Check the appropriate box as to whether the survey is for a Renovation or Demolition as defined by SMAQMD Rule 902, at the time the survey was conducted. Demolitions require sampling of all suspect materials unless assumed to contain asbestos or only a small area is being impacted by the demolition, ie, the entire building will not be razed. An example of this would be where only a load bearing wall(s) is removed but the building will remain intact. In those cases, explain why all suspect materials in the structure were not sampled in item #6. Renovations (TI's, soft demo's, remodels) require sampling of only the suspect materials that are going to be disturbed.
- #2. Provide the description and function of the building(s) or area(s), ie, "School-Boiler Room", within the building(s) being surveyed. Include the total number of floors surveyed. Provide the address of building(s) surveyed. If multiple buildings are on site, provide the total number of structures surveyed, include portables, outbuildings, garages, sheds, etc.
- #3. Provide owner information.
- #4. Provide consultant information and the date on which each building/area was surveyed in item #2.
- #5. The client refers to whoever requested the survey to be conducted and provided demolition/renovation information to the consultant. If the client is the owner in #3, leave this section blank.
- #6. Unless assumed to contain asbestos, all suspect materials must be sampled prior to a demolition. Prior to a renovation, unless assumed to contain asbestos, suspect materials >160 square feet, 260 linear feet, or 35 cubic feet that will be abated, stripped, or removed must be sampled. You cannot assume suspect materials are negative. Samples taken must be based on the Asbestos Hazard Emergency Response Act (AHERA) guidelines for homogeneous areas but must include both the interior <u>and exterior</u> suspect materials, floor to roof. The list below provides common suspect materials. Surfacing materials requiring 3,5,7 protocol are noted (3,5,7). The SMAQMD considers stucco a surfacing material. All other sampling may be done "sufficient to determine".

### EPA Category of Common Suspect Asbestos Containing Materials

Note: This list does not include every product that may contain asbestos. It is intended as a general guide to show the proper NESHAP categories of materials typically containing asbestos.

| Regulated Asbestos Containing Material                 | Category II                                  |
|--|--|
| <ul> <li>Fireproofing (3,5,7)</li> </ul>               | • Stucco (3,5,7)                             |
| <ul> <li>Acoustical Ceiling Texture (3,5,7)</li> </ul> | Window Glazing                               |
| • Plaster (3,5,7)                                      | <ul> <li>Cement Board/Transite</li> </ul>    |
| <ul> <li>Wall Texture (3,5,7)</li> </ul>               | Mastics                                      |
| <ul> <li>Ceiling Tiles</li> </ul>                      | <ul> <li>Textured Paints/Coatings</li> </ul> |
| <ul> <li>HVAC Duct Insulation</li> </ul>               | Chalkboards                                  |
| <ul> <li>Thermal System Insulation</li> </ul>          | <ul> <li>Lab Hoods/Table Tops</li> </ul>     |
| <ul> <li>Mudded Pipe Elbow Insulation</li> </ul>       | Cement Pipes                                 |
| <ul> <li>Linoleum Backing</li> </ul>                   | <ul> <li>Cement Roofing Shingles</li> </ul>  |
| <ul> <li>Furnace Insulation</li> </ul>                 | Caulking                                     |
| <ul> <li>Fire Doors</li> </ul>                         | <u>Category I</u>                            |
| <ul> <li>Nicolite Roofing paper</li> </ul>             | <ul> <li>Asphalt Flooring</li> </ul>         |
|  | <ul> <li>Roofing Shingles</li> </ul>         |
|  | <ul> <li>Built-up Roofing</li> </ul>         |
|  | Base Flashing                                |
|  | <ul> <li>Rolled Roofing</li> </ul>           |
|  | <ul> <li>Boiler/Tank Insulation</li> </ul>   |
|  | Vinyl Floor Tile                             |

#7. This is an estimate total of all RACM, Category I & Category II materials found in <u>all</u> structures listed in item #2. If Category I & II materials were subjected to fire or will be subjected to mechanical forces during removal, they must be designated as RACM. An asbestos containing material must only be designated to one category. Category I or II material cannot be listed as RACM.


## Attachments (Include with Survey)

I. Findings & Recommendations

Explain the significance of the data in item #7. State that Category I material may be left in place during demolition and that RACM and Cementitious Category II material must be removed prior to the renovation or demolition. Explain that the amounts listed are to be used by the owner to obtain accurate bids from abatement contractors. State whether this is a jurisdictional project under the requirements of the federal NESHAP and SMAQMD Rule 902. For unimpacted areas in a renovation, state that untested suspect materials must be tested prior to additional future projects where the materials will be disturbed.

### II. Floor Plan Map(s)

Create a separate Floor Plan Map (see example below) for each floor or area of every structure surveyed in item #2. If the roof or exterior is impacted by the project, create a separate map for the roof and exterior or include them on one of the floor maps as seen below. Name each room sampled by the commonly used name and state whether the area is undergoing Renovation or Demolition. A demolition is the wrecking, taking out or burning of any load supporting structural member. A renovation is everything else. If the survey is conducted after the demo/reno has occurred, inspect all dumpsters outside of building. Record the location of each sample taken and identify each sample with a unique identifier that will be the same as reported to the laboratory and in the following appendices. Use "+" to describe >1% or "-" to describe = to or <1% asbestos.



Example: Building 1 - Floor Plan Map

• 29+

**Roof** 23+, 24+, 25 thru 28 -

## III. Sample Results

Create a table (see example below of minimal information needed to comply with SMAQMD Rule 902) for all samples >1% from all structures surveyed in item #2. Category I or Category II materials subject to known mechanical removal or fire damage must be considered RACM. Add more rows and columns as needed.

| Sample(s)<br>ID# | Suspect<br>Material | Asbestos<br>Content<br>(%)<br>(PLM/PC) | EPA<br>Category                 | Total<br>Quantity<br>Sq./Ln/Cu.<br>Ft. |
|------------------|---------------------|--|---------------------------------|--|
| 1                | Ceiling tile        | 2.6-PC                                 | RACM                            | 250 sqft                               |
| 4                | Linoleum            | 40-PLM                                 | RACM                            | 800 sqft                               |
| 5                | Floor<br>mastic     | 1.4-PC                                 | RACM<br>(mechanical<br>removal) | 250 sqft                               |
| 14,16, 18        | TSI                 | 80-PLM                                 | RACM                            | 1,200 li.ft.                           |
| 15,17, 19        | Wall<br>texture     | 3-PC                                   | RACM                            | 2,500 sqft                             |
| 21               | Floor tile          | 8-PLM                                  | CAT II                          | 2,500 sqft                             |
| 20               | Transite<br>panels  | 45-PLM                                 | CAT II                          | 1,100 sqft                             |
| 23               | Nicolite felt       | Assumed                                | RACM                            | 12,000 sqft                            |
| 24               | Roof<br>mastic      | 2-PLM                                  | CATI                            | 12,000 sqft                            |
| 29, 30, 31       | Stucco              | 1.7 PC                                 | RACM                            | 5,40 <del>0</del> sqft                 |

| Example: Building 1 | - Sample Results |
|---------------------|------------------|
|---------------------|------------------|

### IV. Lab Results

Point count (PC) all samples <10% unless assumed > 1%

V. Current proof of certification of person listed in item #4

# Special Note: The following are common causes for survey rejection and potential citation by SMAQMD:

(1)-Survey form or Appendices incomplete, incorrect or missing attachments.

(2)-All suspect materials are not sampled or assumed to be asbestos containing in the survey (for any reason).

(3)-Affected suspect materials are not sampled utilizing the 3,5,7 protocol.

(4)-Point counts were not conducted, sheetrock was not composite sampled, non-sheetrock materials were composite sampled.

(5)-"Limited Surveys or Inaccessible Areas"- The SMAQMD is aware that renovations impact specific areas within a structure and therefore will not require sampling throughout the entire structure as a demolition survey would require. Stating that a **survey is** "limited" because all areas of the project will not be impacted or areas are inaccessible will result in rejection of the survey unless good cause is provided. There is no requirement to sample inaccessible materials, ie, materials behind a wall or encased in concrete; however, state in the "Findings & Recommendations" that upon discovery of previously untested, inaccessible suspect materials, work must cease until further sampling is conducted. Locked rooms or spaces above drop ceiling tiles are not considered inaccessible and <u>are</u> required to be sampled. The owner/operator must provide access to all impacted areas. Failure to sample suspect materials for "cosmetic" reasons will be rejected.

It is important to state that you cannot be prevented and/or instructed by the owner/operator as to what materials are to be sampled. This is determined by whoever conducts the survey and will give cause for survey rejection and potential citation to the owner/operator for failure to adequately survey all suspect materials.

Survey Instructions (4\_13)

# DOCUMENT 00 01 10

# TABLE OF CONTENTS

# Procurement and Contracting Requirements

| <u>Division 0</u><br>Division 0 | <u>Section</u><br>00 01 01<br>00 01 03<br>00 01 10<br>00 01 15<br><u>Section</u>  | <u>Title</u><br>Project Title Page<br>Seals Pages<br>Table of Contents<br>List of Drawings and Tables<br><u>Solicitation</u><br>Title   |
|---------------------------------|---|---|
|                                 | 00 11 16  | Notice to Bidders   |
| Division 0                      | <u>Section</u><br>00 21 13  | <u>Title</u><br>Instructions to Bidders   |
|                                 | <u> </u>  | Available Information   |
| <u>Division 0</u>               | <u>Section</u><br>00 31 19<br>00 31 32  | <u>Title</u><br>Existing Conditions<br>Geotechnical Data  |
|                                 | Procuren  | nent Forms and Supplements  |
| <u>Division 0</u>               | Section<br>00 41 13<br>00 43 13<br>00 43 36<br>00 45 01<br>00 45 19<br>00 45 19.01<br>00 45 26<br>00 45 46.01<br>00 45 46.02<br>00 45 46.03<br>00 45 46.04<br>00 45 46.05<br>00 45 46.07<br>00 45 46.08 | TitleBid Form and ProposalBid BondDesignated Subcontractors ListSite Visit CertificationNon-Collusion DeclarationIran Contracting Act CertificationWorkers' Compensation CertificationPrevailing Wage and Related Labor RequirementsCertificationDisabled Veteran Business Enterprise ParticipationCertificationDrug-Free Workplace CertificationHazardous Materials CertificationLead-Based Materials CertificationImported Materials CertificationCriminal Background Investigation/FingerprintingCertification |

| 00 45 46.09 | Buy American Certification               |
|-------------|--|
| 00 45 46.10 | Roofing Project Certification            |
| 00 45 46.11 | Federal Debarment Certification          |
| 00 45 46.12 | Federal Byrd Anti-Lobbying Certification |
| 00 45 49    | Registered Subcontractors List           |
| 00 45 90    | Post Bid Interview                       |

# Contracting Forms and Supplements

| <u>Division 0</u> | <u>Section</u>  | <u>Title</u>   |
|-------------------|---|--|
|                   | 00 52 13  | Agreement Form – Stipulated Sum (Single-Prime<br>Contract)   |
|                   | 00 56 00  | Escrow Bid Documentation   |
|                   | 00 57 00  | Escrow Agreement in Lieu of Retention  |
|                   |   | Project Forms  |
| <u>Division 0</u> | <u>Section</u><br>00 61 13.13<br>00 61 13.16<br>00 63 40<br>00 63 47<br>00 63 57<br>00 63 63<br>00 65 19.26<br>00 65 36 | <u>Title</u><br>Performance Bond<br>Payment Bond<br>Allowance Expenditure Directive Form<br>Daily Force Account Report<br>Proposed Change Order Form<br>Change Order Form<br>Agreement and Release of Any and All Claims<br>Guarantee Form |
|                   |   | Conditions of the Contract   |
| <u>Division 0</u> | <u>Section</u><br>00 72 13<br>00 73 13<br>00 73 56  | <u>Title</u><br>General Conditions – Stipulated Sum (Single-Prime<br>Contract)<br>Special Conditions<br>Hazardous Materials Procedures and<br>Requirements   |
|                   |   | <u>General Requirements</u>  |
| <u>Division 1</u> | <u>Section</u><br>01 11 00  | <u>Title</u><br>Summary of Work  |
|                   | I   | Price and Payment Procedures   |
| <u>Division 1</u> | <u>Section</u><br>01 21 00<br>01 22 00  | <u>Title</u><br>Allowance<br>Alternatives and Unit Prices  |

|                   | 01 25 13<br>01 26 00<br>01 29 00<br><u>Adm</u>   | Product Options and Substitutions<br>Changes in the Work<br>Application for Payment and Conditional and<br>Unconditional Waiver and Release Forms<br><u>inistrative Requirements</u>                   |
|-------------------|--|--|
| <u>Division 1</u> | <u>Section</u><br>01 31 19<br>01 32 13<br>01 33 00<br>01 35 13.23                                  | <u>Title</u><br>Project Meetings<br>Scheduling of Work<br>Submittals<br>Site Standards<br>Quality Requirements   |
| <u>Division 1</u> | <u>Section</u><br>01 41 00<br>01 42 13<br>01 42 16<br>01 42 19<br>01 43 00<br>01 45 00             | <u>Title</u><br>Regulatory Requirements<br>Abbreviations and Acronyms<br>Definitions<br>References<br>Materials and Equipment<br>Quality Control   |
| <u>Division 1</u> | <u>Section</u><br>01 50 00<br>01 50 13<br>01 52 13   | <u>Title</u><br>Temporary Facilities and Controls<br>Construction Waste Management and Disposal<br>Field Offices   |
| <u>Division 1</u> | <u>Section</u><br>01 64 00<br>01 66 00   | Product Requirements<br><u>Title</u><br>Owner-Furnished Products<br>Product Delivery, Storage and Handling<br>n and Closeout Requirements  |
| <u>Division 1</u> | <u>Section</u><br>01 71 23<br>01 73 29<br>01 76 00<br>01 77 00<br>01 78 23<br>01 78 36<br>01 78 39 | <u>Title</u><br>Field Engineering<br>Cutting and Patching<br>Alteration Project Procedures<br>Contract Closeout and Final Cleaning<br>Operation and Maintenance Data<br>Warranties<br>Record Documents |

## **Technical Specifications**

- **DIVISION 02 EXISTING CONDITIONS NOT USED**
- **DIVISION 03 CONCRETE NOT USED**
- **DIVISION 04 MASONRY NOT USED**

#### **DIVISION 05 - METALS**

- SECTION 05 5000 Metal Fabrications
- **DIVISION 06 WOOD, PLASTICS, AND COMPOSITES NOT USED**
- **DIVISION 07 THERMAL AND MOISTURE PROTECTION**
- SECTION 07 9200 Joint Sealants
- **DIVISION 08 OPENINGS NOT USED**

#### **DIVISION 09 - FINISHES**

SECTION 09 9100 – Painting

#### **DIVISION 10 - SPECIALTIES**

- SECTION 10 1400 Signage 10 2113 - Plastic Toilet Compartments 10 2813 - Toilet Accessories
- **DIVISION 11 EQUIPMENT NOT USED**
- **DIVISION 12 FURNISHINGS NOT USED**
- **DIVISION 13 SPECIAL CONSTRUCTION NOT USED**
- **DIVISION 14 CONVEYING EQUIPMENT NOT USED**
- **DIVISION 21 FIRE SUPPRESSION NOT USED**
- **DIVISION 22 PLUMBING NOT USED**
- DIVISION 23 HEATING, VENTILATING AND AIR CONDITIONING (HVAC) NOT USED
- **DIVISION 26 ELECTRICAL**
- SECTION 26 0150 Electrical Basic Materials and Methods
- **DIVISION 27 COMMUNICATIONS NOT USED**
- **DIVISION 28 ELECTRONIC SAFETY AND SECURITY NOT USED**
- **DIVISION 31 EARTHWORK**

| SECTION | 31 0000 - Earthwork                 |
|---------|-------------------------------------|
|         | 31 2333 - Trenching and Backfilling |

## **DIVISION 32 - EXTERIOR IMPROVEMENTS**

SECTION 32 1200 - Asphalt Concrete Paving 32 1600 - Site Concrete 32 3119 - Decorative Metal Fences and Gates (All-Welded)

### **DIVISION 33 - UTILITIES - NOT USED**

SECTION 33 4000 - Storm Drainage Utilities

"All rights reserved. This Project Manual or any part hereof may not be duplicated without the written consent of Rainforth Grau Architects except in the form of excerpts or quotations for the purpose of review."

## DOCUMENT 00 52 13

# **AGREEMENT**

THIS AGREEMENT IS MADE AND ENTERED INTO THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, 20\_\_\_, by and between the Sacramento City Unified School District ("District") and \_\_\_\_\_ ("Contractor")

("Agreement").

**WITNESSETH:** That the parties hereto have mutually covenanted and agreed, and by these presents do covenant and agree with each other, as follows:

1. **The Work**: Contractor agrees to furnish all tools, equipment, apparatus, facilities, labor, and material necessary to perform and complete in a good and workmanlike manner, the work of the following project:

Shade Structures Group 1A

("Project" or "Contract" or "Work")

It is understood and agreed that the Work shall be performed and completed as required in the Contract Documents including, without limitation, the Drawings and Specifications and submission of all documents required to secure funding or by the Division of the State Architect for close-out of the Project, under the direction and supervision of, and subject to the approval of, the District or its authorized representative.

- 2. **The Contract Documents**: The complete Contract consists of all Contract Documents as defined in the General Conditions and incorporated herein by this reference. Any and all obligations of the District and Contractor are fully set forth and described in the Contract Documents. All Contract Documents are intended to cooperate so that any Work called for in one and not mentioned in the other or vice versa is to be executed the same as if mentioned in all Contract Documents.
- 3. **Interpretation of Contract Documents**: Should any question arise concerning the intent or meaning of Contract Documents, including the Drawings or Specifications, the question shall be submitted to the District for interpretation. If a conflict exists in the Contract Documents, valid, written modifications, beginning with the most recent, shall control over this Agreement (if any), which shall control over the Special Conditions, which shall control over any Supplemental Conditions, which shall control over the General Conditions, which shall control over the remaining Division 0 documents, which shall control over Division 1 Documents which shall control over Division 2 through Division 49 documents, which shall control over figured dimensions, which shall control over large-scale drawings, which shall control over small-scale drawings. In the case of a discrepancy or ambiguity solely between and among the Drawings and Specifications, the discrepancy or ambiguity shall be resolved in favor of the interpretation that will provide District with the functionally complete and operable Project described in the Drawings and Specifications. In no case shall a document calling for lower quality and/or quantity material or workmanship control. The decision of the District in the matter shall be final.

- 4. **Time for Completion**: It is hereby understood and agreed that the Work under this Contract shall be completed by December 31, 2022.
- 5. **Completion Extension of Time**: Should the Contractor fail to complete this Contract, and the Work provided herein, within the time fixed for completion, due allowance being made for the contingencies provided for herein, the Contractor shall become liable to the District for all loss and damage that the District may suffer on account thereof. The Contractor shall coordinate its Work with the Work of all other contractors. The District shall not be liable for delays resulting from Contractor's failure to coordinate its Work with other contractors in a manner that will allow timely completion of Contractor's Work. Contractor shall be liable for delays to other contractors caused by Contractor's failure to coordinate its Work with the Work of other contractors.
- 6. **Liquidated Damages**: Time is of the essence for all work under this Agreement. It is hereby understood and agreed that it is and will be difficult and/or impossible to ascertain and determine the actual damage that the District will sustain in the event of and by reason of Contractor's delay; therefore, Contractor agrees that it shall pay to the District the sum of <u>five-hundred</u> dollars (\$500.00) per day as liquidated damages for each and every day's delay beyond the time herein prescribed in completion of the Work.

It is hereby understood and agreed that this amount is not a penalty.

In the event that any portion of the liquidated damages is not paid to the District, the District may deduct that amount from any money due or that may become due the Contractor under this Agreement, and such deduction does not constitute a withholding or penalty. The District's right to assess liquidated damages is as indicated herein and in the General Conditions.

The time during which the Contract is delayed for cause, as hereinafter specified, may extend the time of completion for a reasonable time as the District may grant, provided that Contractor has complied with the claims procedure of the Contract Documents. This provision does not exclude the recovery of damages by either party under other provisions in the Contract Documents.

- 7. **Loss Or Damage**: The District and its agents and authorized representatives shall not in any way or manner be answerable or suffer loss, damage, expense, or liability for any loss or damage that may happen to the Work, or any part thereof, or in or about the same during its construction and before acceptance, and the Contractor shall assume all liabilities of every kind or nature arising from the Work, either by accident, negligence, theft, vandalism, or any cause whatsoever; and shall hold the District and its agents and authorized representatives harmless from all liability of every kind and nature arising from accident, negligence, or any cause whatsoever.
- 8. **Limitation Of District Liability:** District's financial obligations under this Contract shall be limited to the payment of the compensation provided in this Contract. Notwithstanding any other provision of this Contract, in no event shall District be liable, regardless of whether any claim is based on contract or tort, for any special, consequential, indirect or incidental damages, including, but not limited to, lost profits or revenue, lost bonding capacity, arising out of or in connection with this Contract for the services performed in connection with this Contract.

- 9. **Insurance and Bonds**: Prior to issuance of the Notice to Proceed by the District, Contractor shall provide all required certificates of insurance, insurance endorsements, and payment and performance bonds as evidence thereof.
- 10. **Prosecution of Work**: If the Contractor should neglect to prosecute the Work properly or fail to perform any provisions of this Contract, the District, may, pursuant to the General Conditions and without prejudice to any other remedy it may have, make good such deficiencies and may deduct the cost thereof from the payment then or thereafter due the Contractor.
- 11. **Authority of Architect, Project Inspector, and DSA**: Contractor hereby acknowledges that the Architect(s), the Project Inspector(s), and the Division of the State Architect ("DSA") have authority to approve and/or suspend Work if the Contractor's Work does not comply with the requirements of the Contract Documents, Title 24 of the California Code of Regulations, and all applicable laws and regulations. The Contractor shall be liable for any delay caused by its non-compliant Work.
- 12. **Assignment of Contract**: Neither the Contract, nor any part thereof, nor any moneys due or to become due thereunder, may be assigned by the Contractor without the prior written approval of the District, nor without the written consent of the Surety on the Contractor's Performance Bond (the "Surety"), unless the Surety has waived in writing its right to notice of assignment.
- 13. **Classification of Contractor's License**: Contractor hereby acknowledges that it currently holds valid Class A or B Contractor's license(s) issued by the State of California, Contractors' State License Board, in accordance with division 3, chapter 9, of the Business and Professions Code and in the classification called for in the Contract Documents.
- 14. **Registration as Public Works Contractor**: The Contractor and all Subcontractors currently are registered as public works contractors with the Department of Industrial Relations, State of California, in accordance with Labor Code section 1771.1.
- 15. **Payment of Prevailing Wages**: The Contractor and all Subcontractors shall pay all workers on all Work performed pursuant to this Contract not less than the general prevailing rate of per diem wages and the general prevailing rate for holiday and overtime work as determined by the Director of the Department of Industrial Relations, State of California, for the type of work performed and the locality in which the work is to be performed within the boundaries of the District, pursuant to sections 1770 et seq. of the California Labor Code. The Contractor and all Subcontractors shall comply with the Davis Bacon Act, applicable reporting requirements, and any other applicable requirements for federal funding. If a conflict exists, the more stringent provision shall control over this Agreement.
- 16. **Labor Compliance Monitoring and Enforcement**: This Project is subject to labor compliance monitoring and enforcement by the Department of Industrial Relations pursuant to Labor Code section 1771.4 and Title 8 of the California Code of Regulations. Contractor specifically acknowledges and understands that it shall perform the Work of this Agreement while complying with all the applicable provisions of Division 2, Part 7, Chapter 1, of the Labor Code, including, without limitation, the requirement that the Contractor and all of its Subcontractors shall

timely submit complete and accurate electronic certified payroll records as required by the Contract Documents, or the District may not issue payment.

17. **Contract Price**: In consideration of the foregoing covenants, promises, and agreements on the part of the Contractor, and the strict and literal fulfillment of each and every covenant, promise, and agreement, and as compensation agreed upon for the Work and construction, erection, and completion as aforesaid, the District covenants, promises, and agrees that it will well and truly pay and cause to be paid to the Contractor in full, and as the full Contract Price and compensation for construction, erection, and completion of the Work hereinabove agreed to be performed by the Contractor, the following price:

in lawful money of the United States, which sum is to be paid according to the schedule provided by the Contractor and accepted by the District and subject to additions and deductions as provided in the Contract. This amount supersedes any previously stated and/or agreed to amount(s).

- 18. **No Representations:** No representations have been made other than as set forth in writing in the Contract Documents, including this Agreement. Each of the Parties to this Agreement warrants that it has carefully read and understood the terms and conditions of this Agreement and all Contract Documents, and that it has not relied upon the representations or advice of any other Party or any attorney not its own.
- 19. **Entire Agreement:** The Contract Documents, including this Agreement, set forth the entire agreement between the parties hereto and fully supersede any and all prior agreements, understandings, written or oral, between the parties hereto pertaining to the subject matter thereof.
- 20. **Severability**: If any term, covenant, condition, or provision in any of the Contract Documents is held by a court of competent jurisdiction to be invalid, void or unenforceable, the remainder of the provisions in the Contract Documents shall remain in full force and effect and shall in no way be affected, impaired, or invalidated thereby.
- 21. **Authority of Signatories**: Each party has the full power and authority to enter into and perform this Contract, and the person signing this Contract on behalf of each party has been properly authorized and empowered to enter into this Contract. This Contract may be executed in one or more counterparts, each of which shall be deemed an original. For this Agreement, and for all Contract Documents requiring a signature, a facsimile or electronic signature shall be deemed to be the equivalent of the actual original signature. All counterparts so executed shall constitute one Contract binding all the Parties hereto.

# [SIGNATURES ON FOLLOWING PAGE]

IN WITNESS WHEREOF, accepted and agreed on the date indicated above:

## [CONTRACTOR NAME]

# SACRAMENTO CITY UNIFIED SCHOOL DISTRICT

| Ву:    | Ву:    |
|--------|--------|
| Title: | Title: |

NOTE: If the party executing this Contract is a corporation, a certified copy of the by-laws, or of the resolution of the Board of Directors, authorizing the officers of said corporation to execute the Contract and the bonds required thereby must be attached hereto.

END OF DOCUMENT

## **1.03 CONSTRUCTION SCHEDULE**

- A. Within ten (10) days of issuance of the Notice to Proceed and before request for first progress payment, the Contractor shall prepare and submit to the Project Manager a construction progress schedule conforming to the Milestone Schedule below.
- B. The Construction Schedule shall be continuously updated, and an updated schedule shall be submitted with each application for progress payment.
   Each revised schedule shall indicate the work actually accomplished during the previous period and the schedule for completion of the remaining work.
- C. Milestone Schedule:

## **Preliminary Construction Schedule**

| Anticipated Notice of Intent to Award (NOITA)       | 05/20/22            |
|---|---------------------|
| Anticipated Board Approval of Construction Contract | 06/02/22            |
| Anticipated Notice to Proceed (NTP)                 | 06/03/22            |
| Shop Drawings, Submittals, Materials Procurement    | 06/03/22 - 06/16/22 |

## **Site Construction Schedule**

| Last Day of 2021-2022 School           | 06/16/22 |
|--|----------|
| First Day of 2022-23 School            | 8/25/22  |
| Mobilization and Start of Construction | 06/17/22 |

#### Site-Adaption Construction Phase – Completion 8/20/22

Work prior to install of Shade Structures to include, but not limited to HAZMAT, Utilities, Electrical Rough-in, ADA improvements, concrete footings & pads. Contractor to include the pick-up of anchor bolts from District storage – location TBD

| Site Adaptation Phase Punch & Corrective work         | 8/20/22 - 8/24/22 |
|---|-------------------|
| Milestone Completion Date of All Site Adaptation work | 8/24/2022         |
| Anticipated Shipments of OFCI Shade Structures        | 8/19/22 - 9/9/22  |

### Start of OFCI Shade Structure Install Phase

Delivery Dates - TBD

Install timeframe of Each Structure: No more than 5 days unless given authorization by District. Complete work on swing shift, after school hours. Provide temporary fencing around work area at all times through completion.

| Punch List, Corrective Work & Final Cleaning | 10/15/22 - 10/30/22 |
|--|---------------------|
|--|---------------------|

## FINAL PROJECT COMPLETION

December 31, 2022

# PART 1 - GENERAL

## 1.1 SUMMARY

- A. Section Includes:
  - 1. Sealants and backing for interior and exterior joints.

# 1.2 RELATED REQUIREMENTS

- A. Section 01 6116, Volatile Organic Compound (VOC) Restrictions, for VOC limits pertaining to adhesives, sealants, fillers, primers, and coatings.
- B. Pertinent Sections specifying sealants or referencing this Section for sealant products and installation requirements.

# 1.3 **REFERENCES AND STANDARDS**

- A. California Building Code (CBC), edition as noted on Drawings.
- B. California Green Building Standards Code (CAL Green), edition as noted on Drawings.
- C. American Concrete Institute (ACI) Publications and Standards:
  - 1. ACI 302.1R: Guide to Concrete Floor and Slab Construction.
  - 2. ACI 360R-10: Guide to Design of Slabs-on-Ground.
- D. ASTM International (ASTM):
  - 1. C834: Standard Specification for Latex Sealants.
  - 2. C919: Standard Practice for Use of Sealants in Acoustical Applications.
  - 3. C920: Standard Specification for Elastomeric Joint Sealants.
  - 4. C1193: Standard Guide for Use of Joint Sealants.
  - 5. C1247: Standard Test Method for Durability of Sealants Exposed to Continuous Immersion in Liquids.
  - 6. C1248: Standard Test Method for Staining of Porous Substrate by Joint Sealants.
  - 7. C1311: Standard Specification for Solvent Release Sealants.
  - 8. C1330: Standard Specification for Cylindrical Sealant Backing for Use with Cold Liquid-Applied Sealants.
  - 9. C1521: Standard Practice for Evaluating Adhesion of Installed Weatherproofing Sealant Joints.
  - 10. D1667: Standard Specification for Flexible Cellular Materials Poly (Vinyl Chloride) Foam (Closed-Cell).
  - 11. E90: Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements.
- E. Federal Specifications (FS):

## JOINT SEALANTS SECTION 07 9200 21-1504

- 1. FS TT-S-001657: Sealing Compound--Single Component, Butyl Rubber Based, Solvent Release Type.
- F. South Coast Air Quality Management District (SCAQMD):
  - 1. Rule 1168: Adhesive and Sealant Applications.
- G. U.S. Food & Drug Administration (FDA):
  - 1. Code of Federal Regulations: Title 21, 21 CFR 177.2600, Rubber Articles Intended for Repeated Use.

## 1.4 **DEFINITIONS**

- A. Sealant Terminology in accordance with ASTM C834 and ASTM C920:
  - 1. Type C: Clear / translucent sealant.
  - 2. Type OP: Opaque pigmented sealant.
  - 3. Type S: Single component sealant.
  - 4. Type M: Sealant with two or more components.
  - 5. Grade NS: Nonsag sealant.
  - 6. Grade P: Pourable sealant.
  - 7. Grade -18°C: Sealant with low temperature flexibility tested to -18°C (0°F).
  - 8. Grade 0°C: Sealant with low temperature flexibility tested to 0°C (32°F).
  - 9. Grade NF: Sealant does not meet low temperature flexibility requirements.
  - 10. Class12-1/2: Sealant capable of handling movement, either contraction or expansion, of 12.5 percent of the original joint width.
  - 11. Class 25: Sealant capable of handling movement, either contraction or expansion, of 25 percent of the original joint width.
  - 12. Class 35: Sealant capable of handling movement, either contraction or expansion, of 35 percent of the original joint width.
  - 13. Class 50: Sealant capable of handling movement, either contraction or expansion, of 50 percent of the original joint width.
  - 14. Class 100 / 50: Sealant capable of handling movement of 50 percent contraction and 100 percent expansion.
  - 15. Use Related to Exposure:
    - a. Use NT: Nontraffic.
    - b. Use T: Traffic.
    - c. Use I: Immersible.
  - 16. Use Related to Material:
    - a. Use A: Sealant used in contact with aluminum.
    - b. Use G: Sealant used in contact with glass.
    - c. Use M: Sealant used in contact with mortar.
    - d. Use O: Sealants used in contact with all other materials other than those previously listed.

# 1.5 ADMINISTRATIVE REQUIREMENTS

- A. Submittal Procedures:
  - 1. Action Submittals and Informational Submittals shall be submitted in accordance with Section 01 3300, Submittal Procedures.
  - 2. Closeout Submittals shall be submitted in accordance with Section 01 7700, Closeout Procedures.
- B. Pre-Installation Meeting: Conduct at Project site. Review joint application procedures, compatibility tests, adhesion tests, and warranty requirements in a meeting involving Architect, Project Inspector, installer, manufacturer or manufacturer's representative.
- C. Coordination:
  - 1. Use of different manufacturer's sealant types for application at exterior wall and glazing systems is not permitted. It is required that a single source for silicone sealants be used on this Project. The Contractor is responsible for coordinating compliance with this requirement where installation of sealants is delegated to various Subcontractors installing the exterior envelope systems for the Project.
  - 2. Contractor shall coordinate and be responsible for compatibility and performance between sealants and other materials, and related Sections using sealants which may be in direct contact with work of this Section or adjacent to the other. Isolate and prevent of incompatibility between sealants in accordance with manufacturer's specifications, recommendations and instructions.

# 1.6 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated, demonstrate compliance with specified attributes.
  - 1. Include color chart from manufacturers for each joint sealant product required.
  - 2. Provide certification by joint sealant manufacturer that materials provided for this Section are 100 percent asbestos-free.
- B. Samples for initial Selection: In form of manufacturer's standard bead samples, consisting of strips of actual products showing full range of colors available, for each product exposed to view.
- C. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2 inch wide joints formed between two 6 inch long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

# 1.7 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Certificates: For each kind of joint sealant and accessory, from manufacturer.
- C. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, indicating that sealants comply with requirements.

## JOINT SEALANTS SECTION 07 9200 21-1504

- 1. Preconstruction Compatibility and Adhesion Test Reports from sealant manufacturer, indicating the following:
  - a. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
  - b. Interpretation of test results and written recommendations for primers and substrate preparation needed for adhesion.
- D. Sustainable Design:
  - 1. General:
    - a. Submit information necessary to establish and document compliance with the California Green Building Standards Code.
  - 2. The following information shall be provided:
    - a. Adhesives and Sealants: Evidence of compliance that products meet maximum VOC content limits specified in Section 01 6116.
- E. Sample of manufacturer's warranty.

# 1.8 CLOSEOUT SUBMITTALS

A. Warranty and Guarantee: Submit executed warranty and extended Contractor guarantee.

## 1.9 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of sealants and backing required for this Project.
- B. Use only new materials and products, unless existing materials or products are specifically shown otherwise on the Drawings to be salvaged and re-used.
- C. Single Source Responsibility: Obtain each kind of joint sealant from single source from single manufacturer.
- D. Materials, components, assemblies, workmanship and installation are to be observed by the Project Inspector. Work not so inspected is subject to uncovering and replacement.
- E. Mockups: Install sealant in mockups of assemblies specified in other Sections that are indicated to receive joint sealants specified in this Section. Use materials and installation methods specified in this Section.

# 1.10 DELIVERY, STORAGE AND HANDLING

- A. Deliver materials to project site in original factory wrappings and containers, labeled with identification of manufacturer, product name and designation, color, expiration period for use, pot life, curing time, and mixing instructions for multicomponent materials.
- B. Store and handle materials in compliance with manufacturer's recommendations to prevent their deterioration or damage due to moisture, high or low temperatures, contaminants, or other causes.

#### 1.11 FIELD CONDITIONS

- A. Environmental Conditions: Do not proceed with installation of joint sealants under the following conditions:
  - 1. When ambient and substrate temperature conditions are outside the limits permitted by joint sealant manufacturer.
  - 2. When joint substrates are wet.
- B. Joint Width Conditions: Do not proceed with installation of joint sealants where joint widths are less than allowed by joint sealant manufacturer for application indicated.
- C. Joint Substrate Conditions: Do not proceed with installation of joint sealants until contaminants capable of interfering with their adhesion are removed from joint substrates.

#### 1.12 WARRANTY AND GUARANTEE

- A. Manufacturer: In addition to the Contractor's and Subcontractor's Standard Guarantee, furnish Owner with manufacturer's fully executed written warranty for sealant against defects in materials and workmanship for a period of 5 years:
- B. Contractor: in addition to its standard Guarantee under the Contract, furnish Owner a special extended written five-year guarantee, cosigned by installer, for sealant, agreeing to replace any and all joints that leaks or otherwise fails to perform as required within guarantee period as a result of failure of materials or installation workmanship at no additional cost to the Owner.

#### PART 2 - PRODUCTS

#### 2.1 DESIGN AND PERFORMANCE CRITERIA

- A. Sustainable Design:
  - 1. VOC emissions for field-applied adhesives, sealants, and sealant primers must comply with limits specified in Section 01 6116.
- B. Building Envelope: Make watertight and weatherproof.
  - 1. Exterior work that does not remain watertight and all work which does not retain all properties inherent in the product as stipulated by the manufacturer will be considered faulty.
- C. Provide elastomeric joint sealants that have been produced and installed to establish and to maintain watertight and airtight continuous seals without causing staining or deterioration of joint substrates.
- D. Provide joint sealants for interior applications that have been produced and installed to establish and maintain airtight continuous seals that are water resistant and cause no staining or deterioration of joint substrates.

#### JOINT SEALANTS SECTION 07 9200 21-1504

- E. Design Requirements:
  - 1. Seal building joints with non-sag type sealant.
  - 2. Seal floor joints with self-leveling or slope grade self-leveling type sealant.

#### 2.2 MATERIALS, GENERAL

- A. Compatibility: Provide joint sealants, joint fillers, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
- B. Liquid-Applied Joint Sealants: Comply with ASTM C920 and other requirements indicated for each liquid-applied joint sealant specified, including those referencing ASTM C920 classifications for type, grade, class, and uses related to exposure and joint substrates.
  - 1. Suitability for Immersion in Liquids. Where sealants are indicated for Use I for joints that will be continuously immersed in liquids, provide products that have undergone testing according to ASTM C 1247. Liquid used for testing sealants is deionized water, unless otherwise indicated.
- C. Colors:
  - 1. General:
    - a. Match adjacent surfaces.
    - b. Not all locations will have the same color.
  - 2. Provide color of exposed joint sealants to comply with the following:
    - a. Provide colors matching selections made by Architects from manufacturer's full range of colors for products of type indicated.
    - b. Request color selection for exposed products listed without a preselected color.

#### 2.3 SILICONE JOINT SEALANTS

- A. Single-Component, Nonsag, Neutral-Curing Silicone Joint Sealant: ASTM C920, Type S, Grade NS, Class 100 / 50, for Use NT.
  - 1. Products: The following, or equal:
    - a. The Dow Chemical Company; "DOWSIL" 790.
    - b. Sika Corporation, Construction Products Division; "Sikasil" WS-290.
- B. Single-Component, Nonsag, Neutral-Curing Silicone Joint Sealant: ASTM C920, Type S, Grade NS, Class 50, for Use NT.
  - 1. Products: The following, or equal:
    - a. Dow Corning Corporation; "DOWSIL 795 Building Sealant".
    - b. Sika Corporation, Construction Products Division; "Sikasil WS-295."

- C. Single-Component, Nonsag, Non-Bleed, Neutral-Curing Silicone Joint Sealant: ASTM C920, Type S, Grade NS, Class 50, for Use G, M, A and O.
  - 1. Products: The following, or equal:
    - a. The Dow Chemical Company; "DOWSIL 756 SMS."
    - b. Momentive Performance Materials; "SCS9000 SilPruf NB."
- D. Single-Component, Nonsag, One Part RTV Neutral-Curing Silicone Joint Sealant: ASTM C920, Type S, Grade NS, Class 25, designed for adhering to low energy surfaces common in sheet or peel and stick weather resistant barriers.
  - 1. Products: The following, or equal:
    - a. The Dow Chemical Company; "DOWSIL" 758.
    - b. Sika Corporation, Construction Products Division; "Sikasil-N Plus."
- E. Mildew-Resistant, Single-Component, Acid-Curing Silicone Joint Sealant: ASTM C920, Type S, Grade NS, Class 25, for Use NT, A and O.
  - 1. Products: The following, or equal:
    - a. The Dow Chemical Company; "DOWSIL 786 Mildew Resistant."
    - b. Momentive Performance Materials; GE Silicones "Sanitary SCS1700."

#### 2.4 URETHANE JOINT SEALANTS

- A. Single-Component, Nonsag, Urethane Joint Sealant: ASTM C920, Type S, Grade NS, Class 35, for Use NT.
  - 1. Products: The following, or equal:
    - a. BASF Master Builders Solutions; "MasterSeal NP 1."
    - b. Sika Corporation, Construction Products Division; "Sikaflex-1a."
- B. Multicomponent, Nonsag, Urethane Joint Sealant: ASTM C920, Type M, Grade NS, Class 25, for Use NT, M, A and O.
  - 1. Products: The following, or equal:
    - a. BASF Master Builders Solutions; "MasterSeal NP 2."
    - b. Sika Corporation, Construction Products Division; "Sikaflex-2c NS."
- C. Multicomponent Urethane Joint Sealant: ASTM C920; self-leveling, Type M, Grade P, Class 25, Uses T, M, A, O, and approved by manufacturer for wide joints up to 1-1/2 inches.
  - 1. Products: The following or equal:
    - a. BASF Master Builders Solutions; "MasterSeal SL 2."
    - b. Sika Corporation, Construction Products Division; "Sikaflex 2c SL."

#### JOINT SEALANTS SECTION 07 9200 21-1504

#### 2.5 ACRYLIC LATEX JOINT SEALANTS

- A. Latex Joint Sealant: Acrylic latex or siliconized acrylic latex, nonsag, paintable, nonstaining. ASTM C 834, Type OP, Grade NF.
  - 1. Products: The following, or equal:
    - a. Pecora Corporation; "AC-20."
    - b. Sherwin Williams; 950A.

#### 2.6 JOINT SEALANT BACKING

- A. General: Provide sealant backings of material and type that are nonstaining; are compatible with joint substrates, sealants, primers and other joint fillers; and are approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
- B. Cylindrical Sealant Backer Rods: Compressible, non-gassing rod-stock complying with ASTM C1330; polyethylene-jacketed polyurethane foam; butyl-rubber foam; neoprene foam; or other flexible, permanent, durable, non-absorptive closed-cell (Type C), open cell (Type O), or bi-cellular material (Type B) and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.
  - 1. Open cell rods shall not be used at sealant joints for horizontal surfaces.
  - 2. Closed cell rods shall not be used at double sealant joints.
- C. Bond-Breaker Tape: Polyethylene tape or other plastic tape as recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint filler materials or joint surfaces at back of joint where such adhesion would result in sealant failure. Provide self-adhesive tape where applicable.

#### 2.7 SEALANT ACCESSORIES AND ADDITIONAL MATERIALS

- A. Primer: Material recommended by joint sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming in any way joint substrates and adjacent nonporous surfaces, and formulated to promote optimum adhesion of sealants with joint substrates.
- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.
- D. Spall Repair Mortar: Two-component structural epoxy binder and sand aggregate, producing a mortar that is easily worked and troweled. Early-set system designed specifically for the repair of industrial concrete floors subject to hard wheeled traffic. Compatible with joint filler and recommended by the joint filler manufacturer in writing.
  - 1. Products: The following, or equal:
    - a. Metzger/McGuire: "Armor-Hard."

#### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint sealant performance. Do not proceed with installation of joint sealants until unsatisfactory conditions have been corrected.
- B. Commencement of work indicates acceptance of substrates.

#### 3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with recommendations of joint sealant manufacturer and the following requirements:
  - 1. Remove foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
  - 2. Clean concrete, masonry, unglazed surfaces of ceramic tile, and similar porous joint substrate surfaces by brushing, grinding, blast cleaning, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining from above cleaning operations by vacuuming or blowing out joints with oil-free compressed air.
  - 3. Remove laitance and form release agents from concrete.
  - 4. Clean metal, glass, porcelain enamel, glazed surfaces of ceramic tile, and other nonporous surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants.
- B. Spall Repair: Repair spalled joints in concrete slabs to produce joints of profiles recommended by joint sealer manufacturers.
- C. Joint Priming:
  - 1. Prime joint substrates where indicated or where recommended by joint sealant manufacturer based on preconstruction joint sealant-substrate tests or prior experience.
  - 2. Apply primer to comply with joint sealant manufacturer's recommendations. Confine primers to areas of joint sealant bond; do not allow spillage or migration onto adjoining surfaces.
- D. Masking Tape:
  - 1. Use masking tape where required to prevent contact of sealant with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears.

#### JOINT SEALANTS SECTION 07 9200 21-1504

2. Remove tape immediately after tooling without disturbing joint seal.

#### 3.3 INSTALLATION OF JOINT SEALANTS

- A. General:
  - 1. Comply with joint sealant manufacturer's printed installation instructions applicable to products and applications indicated, except where more stringent requirements apply.
  - 2. Seal around penetrations, holes, gaps, surface mounted fixtures and pipes entering building including light fixtures, mounting brackets and other similar items.
- B. Sealant Installation Standard: Comply with recommendations of ASTM C1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Joint Sealants at Building Exterior and Interior:
  - 1. Seal the following joints with joint sealant:
    - a. Joints between dissimilar materials.
    - b. Joints between metal panels.
    - c. Control joints in interior partitions, including portion above ceilings.
    - d. Where shown and noted on the documents.
  - 2. Apply joint sealant at joints not specifically mentioned above which require sealant to meet the performance criteria cited in this Section.
- D. Installation of Sealant Backer Rods: Install sealant backer rods to comply with the following requirements:
  - 1. Install joint fillers of type indicated to provide support of sealants during application and at position required to produce the cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
    - a. Do not leave gaps between ends of joint fillers.
    - b. Do not stretch, twist, puncture, or tear joint fillers.
    - c. Remove absorbent joint fillers that have become wet prior to sealant application and replace with dry material.
  - 2. Install bond breaker tape between sealants where backer rods are not used between sealants and joint fillers or back of joints.
- E. Sealant Installation:
  - 1. Install sealants by proven techniques that result in sealants directly contacting and fully wetting joint substrates, completely filling recesses provided for each joint configuration, and providing uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
  - 2. Install sealants at the same time sealant backings are installed.
- F. Tooling of Nonsag Sealants:

- 1. Immediately after sealant application and prior to time skinning or curing begins, tool sealants to form smooth, uniform beads of configuration indicated, to eliminate air pockets, and to ensure contact and adhesion of sealant with sides of joint. Remove excess sealants from surfaces adjacent to joint.
- 2. Do not use tooling agents that discolor sealants or adjacent surfaces or are not approved by sealant manufacturer.
- 3. Profiles:
  - a. Provide concave joint configuration in accordance with Figure 8A in ASTM C1193, unless otherwise indicated.
  - b. Provide flush joint configuration in accordance with Figure 8B in ASTM C1193, where indicated.
  - c. Provide recessed joint configuration in accordance with Figure 8C in ASTM C1193, of recess depth and at locations indicated.
    - 1) Use masking tape to protect adjacent surfaces of recessed tooled joints.

#### 3.4 DEFECTIVE WORK

- A. Repair damaged and defective work and eliminate functional and visual defects. Where repair is not possible replace work. Adjust joints for uniform appearance.
- B. Cut out and remove damaged or deteriorated joint sealants immediately so that and installations with repaired areas are indistinguishable from original work.

#### 3.5 CLEANING AND PROTECTION

- A. Clean off excess sealants or sealant smears adjacent to joints as work progresses by methods and with cleaning materials approved by manufacturers of joint sealants and of products in which joints occur.
- B. Clean excess adhesive from exposed surfaces of neoprene compression seal with solvent cleaner as recommended by manufacturer.
- C. Protect joint sealants during and after curing period from contact with contaminating substances or from damage resulting from construction operations or other causes so that they are without deterioration or damage at time of Substantial Completion.

#### 3.6 SEALANT SCHEDULE

- A. General:
  - 1. Joints in construction between interior and exterior spaces and other designated or required locations to provide effective barrier against passage of elements:
    - a. Multicomponent, Nonsag, Urethane Joint Sealant: ASTM C920, Type M, Grade NS, Class 25, for Use NT, M, A and O.
    - b. Single-Component, Nonsag, Urethane Joint Sealant: ASTM C920, Type S, Grade NS, Class 25, for Use NT.
  - 2. Specialty perimeters where required for appearance or weather tightness:

- a. Multicomponent, Nonsag, Urethane Joint Sealant: ASTM C920, Type M, Grade NS, Class 25, for Use NT, M, A and O; capable of 50 percent extension and compression movement.
- b. Single-Component, Nonsag, Urethane Joint Sealant: ASTM C920, Type S, Grade NS, Class 35, for Use NT.
- c. Single-Component, Nonsag, Neutral-Curing Silicone Joint Sealant: ASTM C920, Type S, Grade NS, Class 50, for Use NT.
- d. Single-Component, Nonsag, Neutral-Curing Silicone Joint Sealant: ASTM C920, Type S, Grade NS, Class 100 / 50, for Use NT.
- B. Exterior Locations:
  - 1. All Exterior Joints:
    - a. Single-component, nonsag, neutral-curing silicone joint sealant, ASTM C920, Type S, Grade NS, Class 100 / 50, for Use NT.
    - b. Single-component, nonsag, neutral-curing silicone joint sealant, ASTM C920, Type S, Grade NS, Class 50, for Use NT.
    - c. Around perimeters of frames where door, window and louver frames abut concrete, masonry or other building materials.
    - d. Expansion and control joints in masonry.
    - e. Masonry at dissimilar material or at dissimilar masonry.
    - f. Miscellaneous locations where sealant is shown on Drawings.
- C. Interior Locations:
  - 1. Interior Wet Areas, Around Plumbing Fixtures, Mildew-resistant, singlecomponent, acid-curing silicone joint sealant, ASTM C920, Type S, Grade NS, Class 25, for Use NT, A and O.
  - 2. Interior Static Dry Joints as Required to Dress Appearance: Acrylic latex or siliconized acrylic latex joint sealant, ASTM C 834, Type OP, Grade NF

#### END OF SECTION

I:\1504 SCUSD Shade Structures Multiple Sites\5.02 Addenda\07 9200\_Joint Sealants.docx Last Updated: March 24, 2021

#### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section Includes: Painting and painter's finish on all exposed exterior and interior surfaces, except prefinished items and unless otherwise noted, as required to complete finishing of the Work. The Work includes, but is not necessarily limited to, the following specific items:
  - 1. Paint, stain or otherwise finish all new surfaces.
  - 2. Back priming of concealed surfaces, except as otherwise specified.
  - 3. Paint, repaint or finish of existing painted surfaces altered, defaced or damaged as a result of work of this Contract.
  - 4. Paint site items which are not prefinished, including posts, screens, panels, bollards, supports, rails and other similar improvements.
  - 5. Unpainted or unfinished exposed building components, pipes and conduit, which run exposed across finished or painted surfaces.
- B. Surface treatment, priming and coats of paint specified in this Section are in addition to shop priming and surface treatment specified under other Sections unless otherwise noted.
- C. Items Not Included in This Section:
  - 1. Factory and shop-prefinished items as specified in various Sections.
  - 2. Painting specified elsewhere and included in respective Sections, including but not necessarily limited to shop priming.

#### 1.2 WORK NOT TO BE PAINTED UNLESS OTHERWISE INDICATED

- A. Exposed exterior concrete and concrete slab surfaces, except as noted.
- B. Unfinished masonry, except where noted.
- C. Suspended acoustical ceilings and acoustical tile, except as noted.
- D. Pre-finished casework and other factory and shop-prefinished items as specified in various Sections.
- E. Finish hardware except prime coated items.
- F. Items typically not to be painted including, but not limited to, the following:
  - 1. Glass.
  - 2. Ceramic tile.
  - 3. Membrane roofing.
  - 4. Safety nosings.

## PAINTING SECTION 09 9100

- 21-1504
  - 5. Resilient floor covering and base.
  - 6. Carpet.
  - 7. Pre-finished paneling.
  - 8. Plastic laminate.
  - 9. Porcelain enamel.
  - 10. Vinyl wallcovering, except where noted.
  - G. Aluminum doors, windows, frames and railings.
  - H. Metal or plastic toilet partitions.
  - I. Items of chromium, copper, nickel, brass, bronze or stainless steel.
  - J. Surfaces in concealed areas such as furred spaces.
  - K. Tops of gravel stop flanges (including priming) where roofing material will be adhered to.
  - L. Wall areas concealed by cases, counters, cabinets, chalkboards, tackboards (prime coat only required).
  - M. Piping or conduit including brackets and similar items therewith running on or across unpainted or otherwise unfinished walls or ceilings.
  - N. Galvanized gratings, recessed foot grilles, and thresholds.
  - O. Structural steel scheduled to receive fireproofing.
  - P. Existing rooms or areas not affected by work of this project, unless specifically noted otherwise.

## 1.3 RELATED REQUIREMENTS

- A. Section 01 6116, Volatile Organic Compound (VOC) Restrictions; for VOC limits pertaining to adhesives, sealants, fillers, primers, and coatings.
- B. Section 05 5000, Metal Fabrications.
- C. Section 07 9200, Joint Sealants.
- D. Section 26 0150, Electrical Basic Materials and Methods

#### 1.4 **REFERENCES AND STANDARDS**

- A. California Building Code (CBC), edition as noted on the Drawings.
- B. California Green Building Standards Code (CAL Green), edition as noted on the Drawings.
- C. ASTM International (ASTM):
  - 1. D523: Standard Test Method for Specular Gloss.

- 2. D4263: Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method.
- D. Master Painters Institute (MPI):
  - 1. Architectural Painting Manual Guide Specification.

#### 1.5 ADMINISTRATIVE REQUIREMENTS

- A. Submittal Procedures:
  - 1. Action Submittals and Informational Submittals shall be submitted in accordance with Section 01 3300, Submittal Procedures.
  - 2. Closeout Submittals shall be submitted in accordance with Section 01 7700, Closeout Procedures.

#### 1.6 ACTION SUBMITTALS

A. Product Data: Submit list and complete descriptive data of products proposed for use. Include manufacturer's specifications, published warranty or guarantee, and application instructions. Cross-reference to paint system and locations of application areas.

#### 1.7 INFORMATIONAL SUBMITTALS

A. Statement of applicator qualifications.

#### 1.8 CLOSEOUT SUBMITTALS

A. Guarantee: Submit Subcontractor's guarantee.

#### 1.9 MAINTENANCE MATERIAL SUBMITTALS

- A. At completion of the Work, deliver to Owner extra stock of paint of each color used in each coating material used.
- B. Containers shall be full, tightly sealed, and clearly marked.

#### 1.10 QUALITY ASSURANCE

- A. Use only new materials and products.
- B. Single-Source Responsibility:
  - 1. To the maximum extent practicable, select a single manufacturer to provide all materials required by this Section, using additional manufacturers to provide systems not offered by the selected principal manufacturer.
  - 2. For each individual system:
    - a. Provide primer and other undercoat paint produced by same manufacturer as finish coat.
    - b. Use thinner within manufacturer's recommended limits.

## PAINTING SECTION 09 9100

21-1504

- C. Source Quality Control: Material shall be best grade products of type specified and listed below as regularly manufactured by these manufacturers. Materials not bearing manufacturer's identification as standard "best grade product" of their regular line will not be considered for use.
- D. Materials, components, assemblies, workmanship and installation are to be observed by the Owner's Project Inspector. Work not so inspected is subject to uncovering and replacement.
- E. Materials and application procedures shall comply with local, state and federal air pollution control regulations.
- F. Manufacturer's representative from coating supplier shall visit the site prior to application to review and approve the specified systems. Discrepancies or recommended changes shall be submitted to the Architect for consideration prior to finalization of submittal.

#### 1.11 DELIVERY, STORAGE AND HANDLING

- A. Deliver undamaged products to job in manufacturer's sealed containers and/or original bundles with tags and labels intact.
- B. Store materials in protected, clean, dry conditions off of ground and in areas which will not interfere with the progress of the Work.
- C. Transport, store and handle in strict accordance with the manufacturer's written recommendations and as specified below.
- D. Remove paint-soiled rags and waste from premises at end of each day's work or store in metal containers with metal covers.
- E. Paint stored at site, shall be in separate structure not less than 60 feet from any other building or structure. Remove empty containers and soiled rags as they accumulate. At completion, remove structure, cleanup area, and leave in original condition.

#### 1.12 FIELD CONDITIONS

- A. Do not apply paints and coatings under conditions which jeopardize quality or appearance of painting or finishing.
- B. Cover or otherwise protect finished work of other trades and surfaces not being painted concurrently or not to be painted.
- C. Exterior:
  - 1. Comply with manufacturer's recommendations as to environmental conditions under which coatings and coating systems can be stored and applied.
  - Do not apply exterior paint when air or surface temperature is under 50 degrees F or when air or surface temperature will be below 50 degrees F for 48 hours after painting.
  - 3. Do not apply immediately following snow, rain, dew or during foggy weather.

- 4. Do not apply when temperature is over 85 degrees F except in protected or shaded areas.
- D. Interior:
  - 1. Do not apply interior paint when air or surface temperature is below 50 degrees F unless temperature is maintained constantly.
  - 2. Do not apply when ventilation is inadequate to maintain humidity lower than dew point of coldest wall.
- E. Use moisture meter for determining proper moisture levels of surfaces for painting.
- F. Report to Architect in writing upon discovery of any prime coat painting specified in other Sections of Specifications that would prevent proper application of specified finish.
- G. Furnish, erect and remove scaffolding and planks required for work under this Section. Conform to state and local codes, rules and regulations.

#### 1.13 EXISTING CONDITIONS

- A. Existing Surfaces:
  - 1. Paint, stain or otherwise finish all existing surfaces as indicated or scheduled on the Drawings.
  - 2. Work includes primer, paint, repaint or finish of existing painted surfaces altered, defaced or damaged as a result of work under this Contract.
- B. Existing surfaces with paint, stain, varnish or similar type coating shall be assumed to contain various concentrations of lead. Cal/OSHA regulations are therefore applicable during disturbance, preparation or repainting of these surfaces.
- C. Existing surfaces to be painted include:
  - 1. Exterior wall surfaces, including fascia, trim.
  - 2. Soffits and exterior ceilings including exposed roof framing.
  - 3. Concrete foundation where exposed below painted wall surfaces.
  - 4. Other work as shown on the Drawings, specified, or as required for a complete Project.

#### 1.14 GUARANTEE

A. Contractor: In addition to his standard Guarantee under the Contract, Contractor shall guarantee that paint colors shall be substantially unchanged and finishes shall maintain their original adherence without showing blisters, flaking, peeling, scaling, staining or unusual deterioration or other defects.

#### 2.1 DESIGN AND PERFORMANCE CRITERIA

- A. Sustainable Design:
  - 1. VOC emissions for field-applied paints and coatings must comply with limits specified in Section 01 6116.

#### 2.2 MANUFACTURERS AND COATING PRODUCTS

- A. Products are specified under "Paint Systems" in Part 3 below and are manufactured by Kelly-Moore, except as otherwise indicated. Equivalent products to those scheduled manufactured by PPG Architectural Finishes, Glidden Professional, Benjamin Moore & Co., Sherwin-Williams, Dunn-Edwards, Vista, or equal are acceptable.
- B. Materials selected for coating systems for each type surface shall be the product of a single manufacturer or shall be acceptable to manufacturer of finish coating for system.
- C. If more than one quality level of product type is marketed, use material of highest quality.

#### 2.3 MIXING AND TINTING

- A. Deliver paints and stains ready mixed to jobsite. On-site color mixing or tinting will not be allowed.
- B. Each kind of coating for paint finishes shall be factory-mixed to match approved samples, colors, and ready for immediate application.
- C. Mix proprietary products in strict accordance with manufacturer's printed directions.
- D. Thinning, if permitted by manufacturer for a specific coating, shall be in accordance with manufacturer's instructions. Thinning of other products shall be in accordance with standard practice.

#### 2.4 COLORS

A. Colors to match existing adjacent surfaces.

#### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Prior to the work of this Section, carefully inspect and verify that the installed work of all other trades is complete to the point where this work may properly commence.
- B. Verify that painting may be performed in accordance with the approved design.
- C. In the event of discrepancy, immediately notify Architect. Do not proceed in discrepant areas until discrepancies have been fully resolved.

## 3.2 PREPARATION

- A. General:
  - 1. Surface preparation and product application shall be in accordance with manufacturer's printed instructions.
  - 2. In addition to prime coats indicated (primer, sealer, filler, undercoat), use two (2) finish coats minimum, and additional coats as required for complete coverage and good appearance of scheduled finish coat.
  - 3. Surfaces to receive new finish shall be properly prepared prior to application of finish coatings.
  - 4. Do not apply paint, enamel, stains or varnishes to wet, damp, dusty, finger-marked, rough, unfinished, or defective surfaces until such defects have been corrected.
- B. Wood Interior:
  - 1. Thoroughly sandpaper and dust off woodwork; putty nail holes, cracks, and other defects after first coat to match color of paint. Putty where finish will be clear.
  - 2. First coat on wood surfaces shall be sanded smooth. Other coats, except finish coat, shall be lightly sanded and dusted before and between each coat.
  - 3. Smoothing, rubbing and sand-papering shall be sufficient to insure good results. Sand down all raised grain or rough surfaces and re-coat. Knots, pitch pockets and sappy portion of wood, all nail holes, cuts, cracks and other defects in wood shall have any necessary extra treatment to provide proper paint base.
- C. Wood Exterior:
  - 1. Surfaces shall be dry and free of grease and splatters.
  - 2. Rough surfaces shall be sanded smooth. [Do not sandpaper resawn surfaces.]
  - 3. At opaque finish, fill nail holes, cracks, open joints, and other defects with filler after priming coat has dried. Exposed nail heads shall be spot primed.
  - 4. Avoid painting surfaces while exposed directly to hot sun.
  - 5. Smooth surfaces shall be sanded thoroughly to allow proper penetration and adhesion. Areas exhibiting tannic acid staining shall receive two coats of primer waiting 24 hours between coats. Sand and prime as soon as possible after installation to avoid UV degradation of unpainted wood surface.
  - 6. Mildew, if present, shall be removed by scrubbing with a commercial mildew wash in accordance with manufacturer's directions.
- D. Metals:
  - 1. On metal work, only such sanding will be required as is necessary to provide for complete bonding of coats.
  - 2. Steel and ironwork shall be scraped clean of scale, and rust and any grease shall be entirely removed.
  - 3. Touch-up scratched and damaged places on metal priming coats.

#### PAINTING SECTION 09 9100

21-1504

- 4. Galvanized or zinc-coated metal shall be given an approved acid treatment 48 hours before paint is applied.
- 5. Prep and prime coat factory or shop primed metal products, including metal doors and frames, exposed framing, and other exposed metal if material was not shop primed.
- 6. Metal surfaces receiving epoxy coatings shall have stripe coat applied at all welds, edges, joints, etc., with epoxy primer prior to application of primer.
- E. Gypsum Board:
  - 1. General:
    - a. Fill narrow, shallow cracks and small holes with spackling compound.
      - 1) Rake deep, wide cracks and deep holes.
      - 2) Dampen with clear water.
    - b. Fill with thin layers of drywall joint cement.
    - c. Allow to dry.
    - d. Sand smooth after drying. Do not raise nap of paper on gypsum board.]
  - 2. Gypsum Board to Receive Wall Covering and Carpeting:
    - a. Prep and prime surfaces scheduled to receive wall covering with scheduled primer. Refer to Section 09 7200, Wall Covering, for clear acrylic primer to be used at vinyl wall covering.
    - b. Sprayed applications of primer shall be back rolled to assure that the primer has thoroughly sealed the surface.
- F. Concrete:
  - 1. Cracks, gaps, hollow areas, bug holes, honey combs, voids, fins, form marks and other protrusions or rough edges are to be ground or stoned to provide a smooth continuous surface.
  - 2. Imperfections may require filling.
    - a. Patch concrete areas with cracks, gaps, hollow areas or other imperfections with compatible material to provide smooth continuous surface.
    - b. Material shall be compatible with and as recommended by the coating manufacturer.
  - 3. Moisture Content:
    - a. Prepared surfaces shall not be painted until they have completely cured and have stabilized moisture content within limits required by the coating manufacturer.
    - b. Testing for Moisture Vapor Emission Rate (MVER) shall be performed to verify suitability using a moisture meter, Delmhorst or equal, or method described in ASTM D4263.
  - 4. Surface shall be reviewed by Architect after surface preparation is complete and prior to application of primer. Additional patching and/or grinding necessary to provide a visually acceptable surface after application of paint coatings shall be accomplished at no additional cost.

- G. Surfaces that cannot be prepared or painted as specified, or to level required by the coating manufacturer, shall be immediately brought to the attention of the Architect, in writing.
  - 1. Starting of work without such notification will be considered acceptance by the Contractor of surfaces involved.
  - 2. Replace unsatisfactory work caused by improper or defective surfaces, as directed by Architect.

#### 3.3 REPAINTING EXISTING INTERIOR SURFACES

- A. Interior surfaces required to be repainted, except acoustic tile, shall be prepared as follows.
  - 1. Wash clean with solution of trisodium phosphate in water and thoroughly rinse or wash with approved self-neutralizing detergent.
  - 2. Spackle, patch, sandpaper, repair, spot or partially prime to provide "hold out" for finish coats of paint and otherwise properly prepare as necessary to provide suitable surfaces, reasonably equal to new, over which to apply specified paints.

#### 3.4 REPAINTING EXISTING EXTERIOR SURFACES

- A. General:
  - 1. Exterior surfaces required to be re-painted, shall be power washed with surfactant, followed by rinsing to remove all loose coatings, chalk, dirt, efflorescence, oils, and other contaminants that would inhibit bond of new coating.
  - 2. Mold or mildew shall be treated with bleach solution followed by thorough rinsing.
  - 3. Protect openings into interior spaces during power washing including louvers, vents, vent screeds, grilles, to prevent water from entering interior areas including, attics and soffits.
- B. Plaster and Concrete Masonry:
  - 1. Remove loose coatings using hand or power tools.
  - 2. Patch plaster areas where original material has cracked, spalled or otherwise been removed with compatible material. Fill areas completely to provide smooth, even surface for refinishing. Spot prime patches prior to proceeding.
  - 3. Patch masonry joints with cracks or missing material with compatible materials.
- C. Wood Siding and Trim:
  - 1. Remove loose, flaking or peeling coatings by scraping, chipping or sanding. Feather rough edges by sanding.
  - 2. Surfaces that exhibit moderate to heavy chalk deposits shall be thoroughly cleaned to sound substrate by wire brushing, sanding, or power washing.

#### PAINTING SECTION 09 9100

21-1504

- 3. Spot prime bare wood, exposed nail and fastener heads prior to application of specified prime coat.
- 4. Glossy surfaces shall be dulled by sanding. Crystalline deposits shall be removed by flushing with water from a hose.
- 5. Mildew, if present, shall be removed by scrubbing with a commercial mildew wash in accordance with manufacturer's directions.
- D. Concrete:
  - 1. Existing exposed concrete scheduled to receive new finish shall be pressure washed or scrubbed to completely remove all bond breakers and oils.
  - 2. Remove loose coatings not removed by pressure washing using hand or power tools.
  - 3. Efflorescence to be removed following procedures recommended by the paint manufacturer.
  - 4. Cracks, gaps, hollow areas, bug holes, honey combs, voids, fins, form marks and other protrusions or rough edges are to be ground or stoned to provide a smooth continuous surface.
  - 5. Imperfections may require filling.
    - a. Patch concrete areas with cracks, gaps, hollow areas or other imperfections with compatible material to provide smooth continuous surface.
    - b. Material shall be compatible with and as recommended by paint manufacturer.
  - 6. Test for moisture as specified for new concrete.
  - 7. Surface shall be reviewed by Architect after patching is complete and primer is applied. Additional patching and/or grinding necessary to provide a visually acceptable surface shall be accomplished at no additional cost.
- E. Stained Wood Surfaces:
  - 1. Thoroughly sand all surfaces.
  - 2. Fill holes, cracks and defects after first coat with color matched putty.
  - 3. Sand between coats to ensure proper adhesion.
- F. Casework to be Refinished: For painted casework, refer to Article 3.2. For lacquer or varnish systems, sand all exposed surfaces and both sides of all doors thoroughly.
- G. Exterior Ceramic Tile: Abrade surface to receive paint. Thoroughly power-sand all surfaces to remove smooth and/or glossy finish.

## 3.5 CAULKING

- A. Caulk all cracks in finished surfaces.
- B. Seal around any wall openings where original sealant is not fully sealing.
- C. Provide sealant at material transitions and intersections as required.

#### 3.6 **PROTECTION**

- A. Hardware, fixture canopies, outlet covers, switch plates and other such items shall be removed or loosened and replaced after completing work as required for painting and finishing. Protect items until reinstalled.
- B. Protect work and work of others during progress against damage. Leave such work clean and whole. Correct damage by cleaning, repairing, replacing or repainting as directed.
- C. Provide necessary drop cloths for protection of work. Cover finished surfaces adjacent to work.

#### 3.7 APPLICATION

- A. General:
  - 1. Do not apply initial coating until moisture content of surface is within limitations recommended by paint manufacturer.
  - 2. Apply coatings in accordance with manufacturer's recommendations and the additional requirements, as applicable, of the Architectural Painting Manual Guide Specifications for application methods and paint systems.
  - 3. Flow coat on evenly and well brushed in. Should dead spots occur, touch-up before next coat is applied. Should spots or cracks burn through after final coat is applied, apply additional coats to entire surface as necessary to remedy defects.
  - 4. Rate of application shall be within limits recommended by paint manufacturer for surface involved.
- B. Thicknesses: Rate of application shall be within limits recommended by paint manufacturer for surface involved and comply with the following.
  - 1. Paint materials shall be applied in manner to average 1.5 to 3 Dry Mils in thickness for the total number of coats scheduled.
  - 2. Provide Tooke Dry Mill Coating Inspection Gauge manufactured by Micro Metrics Company to the Project Inspector for inspection of finished coating systems if requested.
- C. Refinish whole area where portion of finish is not acceptable.
- D. Adjust natural finishes as necessary to obtain identical appearance on veneers and solid stock.
- E. Equipment adjacent to walls shall be disconnected, using workers skilled in appropriate trades, and moved to permit wall surfaces to be painted. Following completion of painting, they shall be expertly replaced and reconnected.
- F. Top and bottom edges of all doors shall receive same paint system finish required for door faces.
- G. Do not paint over fire-rating labels, fusible links, or sprinkler heads.

#### PAINTING SECTION 09 9100 21-1504

#### 3.8 DEFECTIVE WORK

A. Painter shall be responsible for damage or unsuitable work, including that caused by improperly prepared surfaces. Refinishing shall be at no cost to the Owner. Repair work damaged during construction; touch-up or refinish as necessary any abraded, stained or otherwise damaged surfaces.

#### 3.9 CLEANING AND PROTECTION

- A. Thoroughly clean any drips, splatters, spills, splashes, etc., from walls, floor or other surfaces, with no damage to those surfaces.
- B. Protect work and materials of this Section prior to and during installation, and protect the installed work and materials of other trades.
- C. In the event of damage, make all repairs and replacements necessary to the approval of the Architect at no additional cost to the Owner.

#### 3.10 PAINT SYSTEMS

- A. General:
  - 1. Only major areas are scheduled, but miscellaneous and similar items and areas within room or space shall be treated with suitable system.
  - 2. This Specification shall serve as guide and is meant to establish procedure and quality. Confer with the Architect to determine exact finish desired.
  - 3. Number of coats scheduled is minimum. Additional coats shall be applied at no additional cost as required to hide base material completely, produce uniform color, and provide required and satisfactory finish.
- B. Gloss and Sheen Ratings: Paint gloss shall be defined as the sheen rating of applied paint, in accordance with the following limits in conformance with Master Painters Institute, Inc. (MPI) Standards according to ASTM D523. Not all of the Gloss Levels are necessarily scheduled or used on this Project.

| Gloss<br>Level | Description          | Units<br>@ 60 degrees | Units<br>@ 85 degrees |
|----------------|----------------------|-----------------------|-----------------------|
| G1             | Matte or Flat finish | 0 to 5                | 10 max.               |
| G2             | Velvet finish        | 0 to 10               | 10 to 35              |
| G3             | Eggshell finish      | 10 to 25              | 10 to 35              |
| G4             | Satin finish         | 20 to 35              | 35 min.               |
| G5             | Semi-Gloss finish    | 35 to 70              |                       |
| G6             | Gloss finish         | 70 to 85              |                       |
| G7             | High-Gloss finish    | > 85                  |                       |

- C. Clarification of System Terminology:
  - 1. Interior paint Systems are specified and identified herein by initial letters "INT."
  - 2. Exterior paint Systems are specified and identified herein by initial letters "EXT."

- 3. The numbers following "INT" and "EXT" for each System identifies the substrate to be coated.
- 4. Initial numbers for each System identify the substrate to be coated summarized as follows with further clarification included with the System description:

| CODE | DESCRIPTION                |
|------|----------------------------|
| 3.1  | Concrete                   |
| 3.2  | Cement Plaster             |
| 4    | Masonry                    |
| 5    | Metal                      |
| 6    | Wood                       |
| 9.2  | Gypsum Board               |
| 9.3  | Acoustical Panels and Tile |
|      |                            |

5. The letter following substrate number identifies the general finish coat chemistry summarized as follows:

- A Standard acrylic
- B Non-bridging vinyl acrylic
- C Epoxy-like acrylic
- D Semi-transparent stain
- E Elastomeric
- F High performance epoxy-like acrylic
- G Lacquer
- H Aliphatic urethane
- I Fire Retardant Intumescent
- J Acrylic Urethane
- K PVÅ primer
  - Acrylic primer
- M Premium performance acrylic polymer
- 6. Hyphenated suffix identifies the topcoat gloss level.

#### 3.11 INTERIOR PAINTING SYSTEMS

L

| INT 3.1A-3<br>Acrylic on Concrete - Gloss Level 3               |                           |   |  |  |  |  |
|---|---------------------------|---|--|--|--|--|
| 1 coat  | 971 AcryPlex              | Vinyl Acrylic Primer (if not<br>previously painted) |  |  |  |  |
| 2 coats   | 1010 Premium Professional | Latex Eggshell                                      |  |  |  |  |
| INT 3.2A-3<br>Acrylic on Interior Cement Plaster- Gloss Level 3 |                           |   |  |  |  |  |
| 1 coat  | 971 AcryPlex              | Vinyl Acrylic Primer (if not<br>previously painted) |  |  |  |  |
| 2 coats   | 1010 Premium Professional | Latex Eggshell                                      |  |  |  |  |

| PAINTI<br>SECTIC<br>21-1504 | ON 09 9100                                     |  |   |
|-----------------------------|--|--|---|
|                             | INT 4.1A-1                                     |  |   |
|                             | Acrylic on Concrete Unit<br>1 coat             | t Masonry - Gloss Level 1; at th<br>521 Color Shield | neater stage<br>Acrylic Block Filler (if not<br>previously painted) |
|                             | 2 coats  | Speedhide 6-753 by<br>PPG Architectural Finishes     | Acrylic Latex Flat Black  |
|                             | INT 4.1A-3                                     |  |   |
|                             | Acrylic on Concrete Unit<br>1 coat             | t Masonry - Gloss Level 3; unle<br>521 Color Shield  |   |
|                             | 2 coats  | 1010 Premium Professional                            | Latex Eggshell  |
|                             |  |  | bilet rooms / food service areas                                    |
|                             | 1 coat   | 521 Color Shield                                     | Acrylic Block Filler (if not previously painted)                    |
|                             | 2 coats  | 1050 Premium Professional                            | Latex Semi-Gloss  |
|                             | 1 coat<br>2 coats                              | 5585 DTM   | Acrylic Primer<br>100% Acrylic Semi-Gloss                           |
|                             | Note: Modify scheduled                         | d finish coat if lower gloss level                   | is selected by Architect.   |
|                             | INT 6.4A-5<br>Acrylic on Plywood - Glo         | oss Level 5  |   |
|                             | 1 coat   | 973 AcryPlex   |   |
|                             | 2 coats  | 1050 Premium Professional                            | Latex Semi-Gloss  |
|                             | INT 9.2A-1<br>Acrylic on Gypsum Boar           | rd - Gloss Level 1; at theater st                    | age   |
|                             | 1 coat   | 970 AcryPlex   | PVA Primer/Sealer   |
|                             | 2 coats  | Speedhide 6-753 by<br>PPG Architectural Finishes     | Acrylic Latex Flat Black  |
|                             |  | rd, textured finish - Gloss Level                    |   |
|                             | 1 coat<br>2 coats                              | 1010 Premium Professional                            | PVA Primer/Sealer<br>Latex Eggshell                                 |
|                             | INT 9.2A-5<br>Acrylic on Gypsum Boar<br>1 coat | rd, smooth finish - Gloss Level                      | 5<br>PVA Primer/Sealer  |
|                             | 2 coats  | 1050 Premium Professional                            |   |
|                             |  | al topcoat at toilet rooms and for                   |   |
|                             |  | -  |   |

## 3.12 EXTERIOR PAINTING SYSTEMS

| EXT 3.2A-2         Acrylic on Cement Plaster - Gloss Level 2         1 coat       6001-XXXX         Acrylic on Cement Plaster - Gloss Level 2         1 coat       6001-XXXX         Acrylic on Concrete Unit Masonry - Gloss Level 2         1 coat       247 AcryShield         Acrylic on Concrete Unit Masonry - Gloss Level 2         1 coat       247 AcryShield         Acrylic Oncorrete Unit Masonry - Gloss Level 2         1 coat       247 AcryShield         Acrylic Over Unprimed Steel - Gloss Level 5         1 coat       5725 DTM         Acrylic Curethane over Epoxy on Shop Primed Steel – Gloss Level 6         1 coat       Rust-Oleum "ROC Prime"         Single component waterborne epoxy primer         1 coat       Rust-Oleum "Metalmax Plus DTM"         Single Component Acrylic Urethane Gloss         Note:       Provide additional topcoat if required to achieve manufacturer's recommended total DFT (primer plus finish coats), or to achieve complete hiding for selected color.         EXT 5.3A-5         Premium Acrylic over Waterborne Primer on Galvanized Metal – Gloss Level 5         Pretreatment       SSPC SP-1         1 coat       5725 DTM         Acrylic Drimer 1       Coats         2 coats       1250 AcryShield"         1 coat   | EXT 3.1A-2<br>Acrylic on Concrete<br>1 coat<br>2 coats  | - Gloss Level 2<br>247 AcryShield<br>1210 Premium Professional | Acrylic Masonry Primer<br>100% Acrylic Low Sheen |  |  |
|---|---|--|--|--|--|
| Acrylic on Cement Plaster - Gloss Level 2<br>1 coat 6001-XXXX Acrylic Bonding Primer<br>2 coats 1210 Premium Professional 100% Acrylic Low Sheen<br>EXT 4.1A-2<br>Acrylic on Concrete Unit Masonry - Gloss Level 2<br>1 coat 247 AcryShield Acrylic Masonry Primer<br>2 coats 1210 Premium Professional 100% Acrylic Low Sheen<br>EXT 5.1A-5<br>Acrylic over Unprimed Steel - Gloss Level 5<br>1 coat 5725 DTM Metal Primer<br>2 coats 1215 Premium Professional 100% Acrylic Semi-Gloss<br>EXT 5.2A-6<br>Acrylic Urethane over Epoxy on Shop Primed Steel – Gloss Level 6<br>1 coat Rust-Oleum "ROC Prime" Single component waterborne<br>epoxy primer<br>1 coat Rust-Oleum "Metalmax Plus DTM" Single component Acrylic<br>Urethane Gloss<br>Note: Provide additional topcoat if required to achieve manufacturer's recommended<br>total DFT (primer plus finish coats), or to achieve complete hiding for selected<br>color.<br>EXT 5.3A-5<br>Premium Acrylic over Waterborne Primer on Galvanized Metal – Gloss Level 5<br>Pretreatment SSPC SP-1 Heavy-duty cleaner<br>1 coat 5725 DTM Acrylic Primer<br>2 coats 1250 AcryShield" 100% Acrylic Semi-Gloss<br>Note: Provide pretreatment and primer if preparation and primer not applied in shop<br>EXT 5.4A-5<br>Acrylic over Waterborne Primer on Aluminum – Gloss Level 5<br>Pretreatment Devoe Devprep 88 Heavy-duty cleaner<br>1 coat "5725 DTM Acrylic Primer<br>2 coats 1215 Premium Professional 100% Acrylic Semi-Gloss | 2 00013   |  | 100 % Acrylic Low Glicen                         |  |  |
| Acrylic on Concrete Unit Masonry - Gloss Level 2<br>1 coat 247 AcryShield Acrylic Masonry Primer<br>2 coats 1210 Premium Professional 100% Acrylic Low Sheen<br>EXT 5.1A-5<br>Acrylic over Unprimed Steel - Gloss Level 5<br>1 coat 5725 DTM Metal Primer<br>2 coats 1215 Premium Professional 100% Acrylic Semi-Gloss<br>EXT 5.2A-6<br>Acrylic Urethane over Epoxy on Shop Primed Steel – Gloss Level 6<br>1 coat Rust-Oleum "ROC Prime" Single component waterborne<br>epoxy primer<br>1 coat Rust-Oleum "Metalmax Plus DTM" Single Component Acrylic<br>Urethane Gloss<br>Note: Provide additional topcoat if required to achieve manufacturer's recommended<br>total DFT (primer plus finish coats), or to achieve complete hiding for selected<br>color.<br>EXT 5.3A-5<br>Premium Acrylic over Waterborne Primer on Galvanized Metal – Gloss Level 5<br>Pretreatment SSPC SP-1 Heavy-duty cleaner<br>1 coat 5725 DTM Acrylic Primer<br>2 coats 1250 AcryShield" 100% Acrylic Semi-Gloss<br>Note: Provide pretreatment and primer if preparation and primer not applied in shop<br>EXT 5.4A-5<br>Acrylic over Waterborne Primer on Aluminum – Gloss Level 5<br>Pretreatment Devoe Devprep 88 Heavy-duty cleaner<br>1 coat "5725 DTM Acrylic Primer<br>2 coats 1215 Premium Professional 100% Acrylic Semi-Gloss   | Acrylic on Cement P 1 coat  | 6001-XXXX  | , ,  |  |  |
| Acrylic over Unprimed Steel - Gloss Level 5<br>1 coat 5725 DTM Metal Primer<br>2 coats 1215 Premium Professional 100% Acrylic Semi-Gloss<br>EXT 5.2A-6<br>Acrylic Urethane over Epoxy on Shop Primed Steel – Gloss Level 6<br>1 coat Rust-Oleum "ROC Prime" Single component waterborne<br>epoxy primer<br>1 coat Rust-Oleum "Metalmax Plus DTM" Single Component Acrylic<br>Urethane Gloss<br>Note: Provide additional topcoat if required to achieve manufacturer's recommended<br>total DFT (primer plus finish coats), or to achieve complete hiding for selected<br>color.<br>EXT 5.3A-5<br>Premium Acrylic over Waterborne Primer on Galvanized Metal – Gloss Level 5<br>Pretreatment SSPC SP-1 Heavy-duty cleaner<br>1 coat 5725 DTM Acrylic Primer<br>2 coats 1250 AcryShield" 100% Acrylic Semi-Gloss<br>Note: Provide pretreatment and primer if preparation and primer not applied in shop<br>EXT 5.4A-5<br>Acrylic over Waterborne Primer on Aluminum – Gloss Level 5<br>Pretreatment Devoe Devprep 88 Heavy-duty cleaner<br>1 coat "5725 DTM Acrylic Primer<br>2 coats 1215 Premium Professional 100% Acrylic Semi-Gloss   | Acrylic on Concrete 1 coat  | 247 AcryShield   |  |  |  |
| Acrylic Urethane over Epoxy on Shop Primed Steel – Gloss Level 6         1 coat       Rust-Oleum "ROC Prime"       Single component waterborne epoxy primer         1 coat       Rust-Oleum "Metalmax Plus DTM"       Single Component Acrylic Urethane Gloss         Note:       Provide additional topcoat if required to achieve manufacturer's recommended total DFT (primer plus finish coats), or to achieve complete hiding for selected color.         EXT 5.3A-5       Premium Acrylic over Waterborne Primer on Galvanized Metal – Gloss Level 5         Pretreatment       SSPC SP-1         1 coat       5725 DTM         2 coats       1250 AcryShield"         Note:       Provide pretreatment and primer if preparation and primer not applied in shop         EXT 5.4A-5       Acrylic over Waterborne Primer on Aluminum – Gloss Level 5         Pretreatment       Devoe Devprep 88         1 coat       "5725 DTM         2 coats       1250 Primer and primer not applied in shop  | Acrylic over Unprime 1 coat   | 5725 DTM   |  |  |  |
| 1       coat       Rust-Oleum "Metalmax Plus DTM"       Single Component Acrylic Urethane Gloss         Note:       Provide additional topcoat if required to achieve manufacturer's recommended total DFT (primer plus finish coats), or to achieve complete hiding for selected color.         EXT 5.3A-5       Premium Acrylic over Waterborne Primer on Galvanized Metal – Gloss Level 5         Pretreatment       SSPC SP-1       Heavy-duty cleaner         1       coat       5725 DTM       Acrylic Primer         2       coats       1250 AcryShield"       100% Acrylic Semi-Gloss         Note:       Provide pretreatment and primer if preparation and primer not applied in shop         EXT 5.4A-5       Acrylic over Waterborne Primer on Aluminum – Gloss Level 5         Pretreatment       Devoe Devprep 88       Heavy-duty cleaner         1       coat       "5725 DTM       Acrylic Primer         2       coats       1250 AcryShield"       100% Acrylic Semi-Gloss  | Acrylic Urethane over   |  |  |  |  |
| total DFT (primer plus finish coats), or to achieve complete hiding for selected<br>color.EXT 5.3A-5<br>Premium Acrylic over Waterborne Primer on Galvanized Metal – Gloss Level 5<br>PretreatmentPretreatmentSSPC SP-1<br>5725 DTM<br>Acrylic Primer1coat2coats1250 AcryShield"100% Acrylic Semi-GlossNote:Provide pretreatment and primer if preparation and primer not applied in shopEXT 5.4A-5<br>Acrylic over Waterborne Primer on Aluminum – Gloss Level 5<br>PretreatmentPretreatmentDevoe Devprep 88<br>1620 Devy-Guty cleaner1coat1coat2coats1215 Premium Professional100% Acrylic Semi-Gloss   | 1 coat R  | ust-Oleum "Metalmax Plus DTM"                                  | epoxy primer<br>Single Component Acrylic         |  |  |
| Premium Acrylic over Waterborne Primer on Galvanized Metal – Gloss Level 5PretreatmentSSPC SP-11 coat5725 DTM2 coats1250 AcryShield"100% Acrylic Semi-GlossNote:Provide pretreatment and primer if preparation and primer not applied in shopEXT 5.4A-5Acrylic over Waterborne Primer on Aluminum – Gloss Level 5Pretreatment1 coat"5725 DTM2 coats1 coat2 coats1 coat1 coat2 coats1215 Premium Professional100% Acrylic Semi-Gloss   | Note: Provide additional topcoat if required to achieve manufacturer's recommended total DFT (primer plus finish coats), or to achieve complete hiding for selected |  |  |  |  |
| EXT 5.4A-5<br>Acrylic over Waterborne Primer on Aluminum – Gloss Level 5<br>Pretreatment Devoe Devprep 88 Heavy-duty cleaner<br>1 coat "5725 DTM Acrylic Primer<br>2 coats 1215 Premium Professional 100% Acrylic Semi-Gloss  | Premium Acrylic over Waterborne Primer on Galvanized Metal – Gloss Level 5PretreatmentSSPC SP-11 coat5725 DTM2 coats1250 AcryShield"100% Acrylic Semi-Gloss         |  |  |  |  |
| Acrylic over Waterborne Primer on Aluminum – Gloss Level 5PretreatmentDevoe Devprep 881 coat"5725 DTM2 coats1215 Premium Professional100% Acrylic Semi-Gloss  | Note. Provide pretreatment and primer it preparation and primer not applied in shop   |  |  |  |  |
| PretreatmentDevoe Devprep 88Heavy-duty cleaner1 coat"5725 DTMAcrylic Primer2 coats1215 Premium Professional100% Acrylic Semi-Gloss  |   |  |  |  |  |
| 1 coat       "5725 DTM Acrylic Primer         2 coats       1215 Premium Professional 100% Acrylic Semi-Gloss   | •   |  |  |  |  |
| 2 coats 1215 Premium Professional 100% Acrylic Semi-Gloss   |   |  |  |  |  |
|   |   |  |  |  |  |
|   |   |  |  |  |  |

### PAINTING SECTION 09 9100 21-1504

#### 3.13 MISCELLANEOUS PAINTING

- A. Mechanical and Electrical Equipment, Conduits and Piping: Paint exposed items as scheduled using appropriate system for material and whether or not item has been factory-primed.
- B. Exposed Insulation-Covered Piping: Size with Arabol, or equal latex type adhesive, and apply 2 coats of semi-gloss enamel.
- C. Material Visible through Grilles, Screens, Louvers, Vents and Screens and Exposed Hardware Cloth Screening: Painted flat black to make them as unnoticeable as possible.
- D. Mechanical Equipment: Paint mechanical equipment housings where indicated on the Drawings.

#### END OF SECTION

i:\1504 scusd shade structures multiple sites\5.02 addenda\09 9100\_painting.docx Last Updated: September 15, 2021

# **Statement of General Conformance**

THE FOLLOWING DRAWINGS OR SHEETS LISTED ON THE COVER OR INDEX SHEET HAVE BEEN PREPARED BY OTHER DESIGN PROFESSIONALS OR CONSULTANTS WHO ARE LICENSED AND/OR AUTHORIZED TO PREPARE SUCH DRAWINGS IN THIS STATE. IT HAS BEEN EXAMINED BY ME FOR:

1) DESIGN INTENT AND APPEARS TO MEET THE APPROPRIATE REQUIREMENTS OF TITLE 24, CALIFORNIA CODE OF REGULATIONS AND THE PROJECT SPECIFICATIONS PREPARED BY ME, AND

2) COORDINATION WITH MY PLANS AND SPECIFICATIONS AND IS ACCEPTABLE FOR INCORPORATION INTO THE CONSTRUCTION OF THIS PROJECT.

THE STATEMENT OF GENERAL CONFORMANCE "SHALL NOT BE CONSTRUED AS RELIEVING ME OF MY RIGHTS, DUTIES, AND RESPONSIBILITIES UNDER SECTIONS 17302 AND 81138 OF THE EDUCATION CODE AND SECTIONS 4-336, 4-341, AND 4-344" OF TITLE 24, PART 1. (TITLE 24, PART 1, SECTION 4-317 (b))

NQ

4/21/22

SIGNATURE

DATE

ARCHITECT OR ENGINEER DESIGNATED TO BE IN GENERAL RESPONSIBLE CHARGE

Jeffrey Grau

PRINT NAME

C-14648 05/31/23

LICENSE NUMBER EXPIRATION DATE

LIST COMPLETELY, ITEMS REVIEWED AND ACCEPTED:

PC SHADE STRUCTURE

| DESIGN CRITERIA   |  |
|---|--|
| DESCRIPTION   | DESIGN VALUES  |
| DEAD AND LIVE LOADS   |  |
| ROOF LIVE LOAD  | 20 PSF   |
| ROOF DEAD LOAD (SUPERIMPOSED ON FRAME)  | 5 PSF MAX  |
| ROOF PANEL DEAD LOAD  | M=1.1 PSF, G = 1.2 PSF, S = 1.3 PSF  |
| COLLATERAL DEAD LOAD  | M = 3.9 PSF, G = 3.8 PSF, S = 3.7 PSF  |
| ROOF SNOW LOAD  |  |
| GROUND SNOW LOAD, Pg  | 20 PSF   |
| RISK CATEGORY   | l  |
| ROOF SNOW LOAD: SLOPED, P <sub>s</sub>  | 20 PSF   |
| SITE APPLICATION DSA REVIEWER SHALL VERIFY THE STRUCTURE BE LOCATED   | AT LEAST 20 FEET FROM ADJACENT STRUCTURE   |
| SNOW LOAD SLOPE FACTOR, C <sub>s</sub>  | 1.0  |
| SNOW EXPOSURE FACTOR, Ce  | 1.0  |
| SNOW LOAD IMPORTANCE FACTOR, Is   | 1.0  |
|   |  |
|   | 1.2  |
| WIND DESIGN   |  |
| BASIC WIND SPEED (3 SECOND GUST), V <sub>ult</sub>  | 100 MPH  |
|   |  |
| EXPOSURE CATEGORY   | С  |
| FACTORS: K <sub>z</sub> , K <sub>zt</sub> , K <sub>d</sub>  | 0.85, 1, 0.85  |
| $q_h$ = 0.00256 K <sub>z</sub> K <sub>zt</sub> K <sub>d</sub> V <sup>2</sup> FOR ALL EAVE HEIGHTS (8', 10' & 12')               | 18.50 PSF  |
| C <sub>NW</sub> PER ASCE FIGURE 27.4-5 ROOF ANGLE 18.43 - CLEAR / OBSTRUCTED  | CASE A (1.1 / -1.2) CASE B (0.01 / -0.69)  |
| C <sub>NL</sub> PER ASCE FIGURE 27.4-5 ROOF ANGLE 18.43 - CLEAR / OBSTRUCTED  | CASE A (-0.17 / -1.09) CASE B (-0.96 / -1.65)                                    |
| C <sub>N</sub> PER ASCE FIGURE 27.4-7 PARALLEL TO RIDGE - CLEAR / OBSTRUCTED  | CASE A (-0.6 / -0.9) CASE B (-0.5 / -0.5)  |
| COMPONENTS & CLADDING - $C_N$ ( PRESSURE/SUCTION) CLEAR / OBSTRUCTED  |  |
| $COMPONENTS & CLADDING - C_N (PRESSURE/SUCTION) CLEAR / OBSTRUCTED$   | ZONE 3 - (2.29 / -2.11) / (1.0 / -3.0)   |
|   | ZONE 2 - (1.77 / -1.63) / (0.8 / -2.3)<br>ZONE 1 - (1.15 / -1.05) / (0.5 / -1.5) |
| SEISMIC DESIGN  | ZONE 1 - (1.137 - 1.03)7 (0.37 - 1.3)  |
| LATERAL FORCE RESISTING SYSTEM  | STEEL - ORDINARY CANTILEVER COLUMN   |
| ANALYSIS PROCEDURE  | EQUIVALENT LATERAL FORCE   |
| SESIMIC IMORTANCE FACTOR, le  | 1.0  |
| SEISMIC SITE CLASS  | D  |
| MCE <sub>R</sub> SPECTRAL RESPONSE ACCELERATION @ 0.2 s, S <sub>S</sub>   | 2.60   |
| MCE <sub>R</sub> SPECTRAL RESPONSE ACCELERATION @ 0.2 s, S1   | 0.90   |
| SHORT PERIOD SITE COEFFICIENT, F <sub>a</sub>   | 1.20   |
| -   |  |
|   | 1.70   |
| FUNDAMENTAL PERIOD OF THE STRUCTURE, T  | 0.152 s  |
|   |  |
| DESIGN SPECTRAL RESPONSE ACCELERATION AT SHORT PERIOD, S <sub>DS</sub>  | 2.08   |
| DESIGN SPECTRAL RESPONSE ACCELERATION AT SHORT PERIOD, S <sub>DS</sub> - USED<br>TO DETERMINE Cs (WITH CAP PER ASCE-7 12.8.1.3) | 2.08 * 0.70 = 1.456  |
| DESIGN SPECTRAL RESPONSE ACCELERATION AT 1-S PERIODS, SD1   | 1.02   |
| SEISMIC DESIGN CATEGORY   | E  |
| RESPONSE MODIFICATION FACTOR, R   | 1.25   |
| OVERSTRENGTH FACTOR, Ω  | 1.25   |
| REDUNDANCY FACTOR, ρ  | 1.0  |
| HORIZONTAL OR VERTICAL IRREGULARITIES   | NONE   |
| SEISMIC RESPONSE COEFFICIENT, Cs (20' WIDE, 30' WIDE, 40' WIDE)   | 1.16,  |
| DESIGN BASE SHEAR, V (20' WIDE, 30' WIDE, 40' WIDE)   | 12.73 PSF, 13.41 PSF, 14.65 PSF  |
| ALLOWABLE SOIL BEARING FOR FOUNDATIONS  | VARIES - SEE FOUNDATION CHARTS   |
| FLOOD DESIGN - DESIGN IS ASSUMED TO NOT BE IN FLOOD HAZARD AREA   |  |
|   |  |

STRUCTURAL SEPARATION

ALLOWABLE SOIL VALUES SPECIFIED.

| ALL DEFLECTIONS SHOWN ALSO INCLUDE THE P-DE  | LTA ROTATION PER IR PC-7 |              | IONS ARE FOR (1) ST<br>CLASSES PER CBC TABLE 18 |               |
|--|--------------------------|--------------|---|---------------|
| MAXIMUM DRIFT $\delta_{max}$ SIDE COLUMNS  |                          | Soil Class 5 | <u>Soil Class 4</u>                             | <u>Soil C</u> |
| 20 WIDE (O'EAVE HT, 10'EAVE HEIGHT, 12'EAVE HT)  | (INCHES)                 | 2.40         | 2.55  | 2.0           |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                 | 2.25         | 2.35  | 2.4           |
| 19' WHEE (8' EAVE HT, 19' EAVE HEIGHT, 12' EAVE HT)<br>MINIMUM SEPARATION ( $\delta_m = C_d \delta_{max}$ ) $C_d = 1.25$ | (INGLIES)                | 2.20         | 2.25  | 2.:           |
| 20' WIDE (O' EAVE HT, 10' EAVE HEICHT, 12' EAVE HT)  | (INCHES)                 |              | 3.19  | 3.3           |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                 | 2.81         | 2.94  | 3.0           |
| 10' WHEE (C'EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)   | (INCHES)                 | 2.75         | 2.81  | 2.3           |
| MAXIMUM DRIFT $\delta_{max}$ CORNER COLUMNS  |                          | Soil Class 5 | So Class 4                                      | <u>so c</u>   |
| 20 WIDE (8 EAVE HT, 10 EAVE HEIGHT, 12 EAVE HT)  | (IIVEHES)                | 2.20         | 2.30  | 2.4           |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                 | 2.30         | <b>1</b> 5                                      | ₹.÷           |
| 10' WIDE (0' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)<br>MINIMUM SEPARATION ( $\delta_m = C_d \delta_{max}$ ) $C_d = 1.25$ | (INCHEC)                 | 2.10         | 2 55  | 2             |
| 20' WIDE (O'EAVE HT, 10'EAVE HEIGHT, 12'EAVE HT)   | (INCHEC)                 | 2.75         | <b>A</b> 88                                     | 3             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                 | 2.88         | <u> </u>  | <b>]</b>      |
| 40 WIDE (O EAVE HT, 10 EAVE HEIGHT, 12 EAVE HT)  |                          | 3.00         | <sup>3</sup> . 1                                | Į,            |
| MAXIMUM DRIFT $\delta_{max}$ END COLUMNS   |                          | Soil Class 5 | <u>Sci Class 4</u>                              | <u>Soi C</u>  |
| 20' WIDE (O' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INGHES)                 | 1.00         | 1.70  | 1.1           |
|  | (INCHES)                 | 2.00         | 2.45  | 2.2           |
| MINIMUM SEPARATION ( $\delta_m = C_d \delta_{max}$ ) $C_d = 1.25$  |                          | 2.50         | 2.30  | 2.8           |
| 20 WIDE (8 EAVE HT, 10 EAVE HEIGHT, 12 EAVE HT)  | (INCHES)                 | 2.00         | 2.13  | 2.1           |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                 | 2.50         | 3.06  | 2.8           |

| ARCHITEC TURAL REQUIREMENTS |   |  |  |
|-----------------------------|---|--|--|
| DESCRIPTION                 | DESIGN VAULES                             |  |  |
| TYPE OF CONSTRUCTION        | II-B                                      |  |  |
| OCCUPANCY CLASSIFICATION    | A-3                                       |  |  |
| NUMBER OF STORIES           | 1   |  |  |
| FIRE SPRINKLER SYSTEM       | NOT BY ICON/WEIGHT NOT INCLUDED IN DESIGN |  |  |

RELATED BUILDING CODES AND STANDARDS

| TITLE 24 CODES:   |
|---|
| 2019 CALIFORNIA ADMINISTRATIVE CODE (CAC)(PART 1, TITLE 24, CCR)<br>2019 CALIFORNIA BUILDING CODE (CBC), VOLUMES 1, AND 2.(PART 2, TITLE 24,<br>CCR)  |
| 2019 CALIFORNIA ELECTRICAL CODE(PART 3, TITLE 24, CCR)<br>2019 CALIFORNIA MECHANICAL CODE (CMC)(PART 4, TITLE 24, CCR)<br>2019 CALIFORNIA PLUMBING CODE (CPC)(PART 5, TITLE 24, CCR)<br>2019 CALIFORNIA ENERGY CODE(PART 6, TITLE 24, CCR)<br>2019 CALIFORNIA FIRE CODE (CFC) |
| REFERENCE CODE SECTIONS FOR APPLICABLE STANDARDS:<br>2019 CBC, CHAPTER 35<br>2019 CFC, CHAPTER 80<br>scope of work narrative  |
| SCOPE OF WORK MARINA ITVE   |

THESE DRAWINGS ILLUSTRATE THE FABRICATION AND INSTALLATION REQUIREMENTS FOR A FREE-STANDING PREFABRICATED STEEL SHADE STRUCTURE. THE ENTIRE STRUCTURAL SYSTEM IS COMPRISED OF HOLLOW STRUCTURAL STEEL MEMBERS SUPPORTED BY CONCRETE FOUNDATIONS. THE FLEXIBILITY INCLUDED HEREIN ALLOWS THE STRUCTURE TO COMPLY WITH A WIDE VARIETY OF PROJECT SITES AND LOADING REQUIREMENTS.

## <u>GENERAL:</u>

- WITH ANY WORK INVOLVED.
- 6. ASTM DESIGNATIONS AND ALL STANDARDS REFER TO THE LATEST AMENDMENTS.
- ARCHITEC T/ENGINEER OR OWNER.
- 10. THE SCHOOL DISTRICT INSPECTOR ON RECORD SHALL INSPECT AND APPROVE THE ERECTED FRAME PRIOR TO ROOF INSTALLATION.
- DETAILS OF ALL AREAS COMPLYING WITH THE WUI REQUIREMENTS.

# STRUCTURAL AND MISCELLANEOUS STEEL:

- CALIFORNIA BUILDING CODE.
- DRAWINGS (MAXIMUM INCREASE OF 1/8").

- 10.ALL ROOF DECKS SHALL CONFORM TO ASTM A-792, Fy = 50 KSI.

INSTRUCTIONS FOR ARCHITECTS SUBMITTING THESE PRE-CHECKED DRAWING TO DSA: BEFORE SUBMITTING THESE PRE-CHECKED DRAWINGS FOR YOUR PROJECT, FOLLOW THE STEPS BELOW TO PROPERLY DEFINE THE APPROVED OPTIONS:

-GABLE STRUCTURES UP TO 30' WIDE USE THE "RG 30" BASE FRAME -GABLE STRUCTURES UP TO 40' WIDE USE THE "RG 40" BASE FRAME -MAXIMUM WIDTH IS 40' (SEE "ARCHITECTURAL VIEWS" SHEET FOR REFERENCE) -THE 24', 44', 64', 84' AND 104' LENGTHS ARE SUGGESTED BECAUSE THEY ARE THE MOST COMMON (20' BAYS ARE THE MOST ECONOMICAL) -FRAME LENGTHS ASSUME 2' OVERHANGS (UNO BY ARCHITECT - 2' MAX DIMENSION)

STEP 2: SELECT ROOF DECK FOR YOUR PROJECT -"M" REPRESENTS MCELROY METAL "MULTI-RIB" ROOF PANEL -"G" REPRESENTS MCELROY METAL "MEGA-RIB" ROOF PANEL

-"S" REPRESENTS MCELROY METAL "MEDALLION-LOK" 16" STANDING SEAM ROOF PANEL STEP 3: IDENTIFY THE Ss ACCELERATION (g) FOR YOUR PROJECT -Ss VALUE DETERMINES THE REQUIRED SEISMIC DESIGN FORCES -Ss VALUE DEPENDS ON THE PROJECTS GEOGRAPHICAL LOCATION (VALUES RANGE FROM 0.00 TO 3.73)

- DEAD LOAD SHOWN IN STEP 4 FOR YOUR SS VALUE
- -IDENTIFY THE APPLICABLE SHEET INDEX
- STEP 9: INCLUDE APPLICABLE SHEETS WITH YOUR DSA SUBMITTAL

| <u>N01</u> | TICE OF DIS            |
|------------|------------------------|
| 1.         | PER TITLE              |
| 2.         | BE GIVEN<br>FOR THE S  |
| 3.         | GENERAL F              |
| •••        | PREPARAT               |
| 4.         | STRUC TUR<br>RESPONSIE |
| 5.         | ALL CONST<br>ENGINEER  |
|            | BUT ARE                |
|            | CONSTRUC<br>COMPLETE   |
| 6.         | J.R. MILLEF            |

CONSTRUCTION.

#### 1. GENERAL NOTES AND TYPICAL DETAILS SHALL APPLY TO ALL PARTS OF THE JOB EXCEPT WHERE THEY MAY CONFLICT WITH DETAILS AND NOTES ON OTHER SHEETS. WHERE CONDITIONS ARE NOT SPECIFICALLY INDICATED BUT ARE OF SIMILAR CHARACTER TO DETAILS SHOWN, SIMILAR DETAILS OF CONSTRUCTION SHALL BE USED SUBJECT TO REVIEW BY THE STRUCTURAL ENGINEER FOR THIS PROJECT. 2. WORK SHALL CONFORM TO THE REQUIREMENTS, AS AMENDED TO DATE, OF THE LATEST ADOPTED EDITION OF THE CBC, C.A.C. TITLE 24, AND ALL OTHER LOCAL, STATE AND FEDERAL REGULATIONS.

3. OMISSIONS OR CONFLICTS BETWEEN THE VARIOUS ELEMENTS OF THE WORKING DRAWINGS AND/OR SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE STRUCTURAL ENGINEER FOR THIS PROJECT PRIOR TO PROCEEDING 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE WORK OF ALL TRADES AND SHALL CHECK ALL

DIMENSIONS, ALL DISCREPANCIES SHALL BE CALLED TO THE ATTENTION OF THE STRUCTURAL ENGINEER FOR THIS PROJECT AND BE RESOLVED BEFORE PROCEEDING WITH THE WORK.

5. THESE CONSTRUCTION DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE AND DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES, INCLUDING, BUT NOT LIMITED TO, BRACING, TEMPORARY SUPPORTS, AND SHORING. OBSERVATION VISIT TO THE SITE BY FIELD REPRESENTATIVES OF THE ARCHITECT/ENGINEER SHALL NOT INCLUDE INSPECTIONS OF THE PROTECTIVE MEASURES OR THE CONSTRUCTION PROCEDURES. ANY SUPPORT SERVICES PERFORMED BY THE ARCHITECT/ENGINEER DURING THE CONSTRUCTION SHALL BE DISTINGUISHED FROM CONSTRUCTION AND DETAILED INSPECTION SERVICES WHICH ARE FURNISHED BY OTHERS. THESE SUPPORT SERVICES PERFORMED BY THE ARCHITECT/ENGINEER, WHETHER OF MATERIAL OR WORK, ARE FOR THE PURPOSE OF ASSISTING IN QUALITY CONTROL AND IN ACHIEVING CONFORMANCE WITH CONTRACT DOCUMENTS, BUT DO NOT GUARANTEE CONSTRUCTION.

7. CONFORM TO APPLICABLE CAL/OSHA CONSTRUCTION SAFETY REGULATIONS FOR ALL WORK PERFORMED DURING CONSTRUCTION. JOB SITE SAFETY IS STRICTLY THE RESPONSIBILITY OF THE CONTRACTOR AND NOT THE

8. THE ENGINEER AND THEIR CONSULTANTS SHALL HAVE NO RESPONSIBILITY FOR THE DISCOVERY, HANDLING, REMOVAL OR DISPOSAL OF HAZARDOUS MATERIALS AT THE PROJECT SITE, INCLUDING BUT NOT LIMITED TO ASBESTOS, ASBESTOS PRODUCTS, POLYCHLORINATED BIPHENYL (PCB) OR OTHER TOXIC SUBSTANCES. 9. SHOULD ANY CONDITIONS DEVELOP NOT COVERED BY THE CONTRACT DOCUMENTS, OR IF A CHANGE IN THE SCOPE OF WORK IS PROPOSED, A CONSTRUCTION CHANGE DOCUMENT DETAILING AND SPECIFYING THE REQUIRED CHANGE(S) SHALL BE SUBMITTED TO AND APPROVED BY DSA BEFORE PROCEEDING WITH THE WORK.

11. SEE REQUIREMENTS FOR LOCATION IN ANY FIRE HAZARD SEVERITY ZONE FOR WILDLAND URBAN INTERFACE AREAS (WUI) AS SPECIFIED IN THE APPLICABLE VERSION OF THE CALIFORNIA BUILDING CODE. PROVIDE PROTECTION AND

12. LOCATING THIS STRUCTURE CLOSER THAN 20 FEET TO OTHER STRUCTURES MAY AFFECT THE ALLOWABLE AREA FOR THE EXISTING CONSTRUCTION PER THE APPLICABLE VERSION OF THE CALIFORNIA BUILDING CODE. 13. VIEWS AND DETAILS ARE NOT DRAWN TO SCALE (UNLESS NOTED OTHERWISE). DO NOT SCALE THESE DRAWINGS.

1. ALL STRUCTURAL STEEL SHALL BE DETAILED, FABRICATED AND ERECTED IN ACCORDANCE WITH THE AMERICAN INSTITUE OF STEEL CONSTRUCTION (AISC) SPECIFICATION MANUAL REFERENCED BY THE LATEST EDITION OF THE

2. PIPE SECTIONS SHALL CONFORM TO ASTM A53, Fy = 35 KSI, GRADE B OR A501 UNLESS NOTED OTHERWISE. 3. STRUCTURAL TUBING (HSS SHAPES) SHALL CONFORM TO ASTM A-500, GRADE B (OR C), Fy = 46 KSI (MIN).

4. IF MATERIAL AVAILABILITY IS LIMITED, MEMBER THICKNESS CAN BE INCREASED BEYOND WHAT IS SHOWN IN THESE 5. ALL CHANNELS, ANGLES, AND MISC. STEEL SHALL CONFORM TO ASTM A-36, Fy = 36 KSI.

6. ALL PLATE STEEL SHALL CONFORM TO ASTM A-572, Fy= 50 KSI. 7. ALL COLD FORM STEEL SHALL CONFORM TO ASTM A-653, CS = TYPE B, Fy = 50 KSI.

8. STRUCTURAL STEEL AND DECK SHALL BE IDENTIFIED FOR CONFORMITY PER CBC 2202A.1.

9. ALL ROOF DECKS SHALL HAVE KYNAR 500 METAL COATING.

# STEP 1: SELECT FRAME DIMENSIONS FOR YOUR PROJECT -GABLE STRUCTURES UP TO 20' WIDE USE THE "RG 20" BASE FRAME

STEP 4: IDENTIFY THE Ss REGION FOR YOUR PROJECT -THE REGIONS ARE DEPENDANT ON THE SS VALUE DETERMINED IN STEP 3 -THE SS REGION DICTATES THE MAXIMUM DEAD LOAD PERMITTED ON THE FRAME (SEE TABLE TO RIGHT)

STEP 5: IDENTIFY THE ROOF DEAD LOAD FOR YOUR PROJECT -THE ROOF DECK DEAD LOAD WILL ALWAYS BE INCLUDED -THE COLLATERAL LOAD REPRESENTS ADDITIONAL LOAD THAT CAN BE SUPPORTED BY THE FRAME -BE SURE THE TOTAL ROOF DEAD LOAD FOR YOUR PROJECT IS LESS THAN OR EQUAL TO THE MAX

-Sds VALUE USED IN CALCULATION IS THE CAPPED Sds (SEE DESIGN CRITERIA)

STEP 6: IDENTIFY THE FOUNDATION REQUIREMENTS FOR YOUR PROJECT -IDENTIFY SOIL CLASS FOR PROJECT SITE PER SITE SPECIFIC SOIL CONDITIONS -USE THIS TO SELECT CORRECT FOUNDATION SIZE ON FOUNDATION SHEET

STEP 7: SELECT MISCELLANEOUS OPTIONS FOR YOUR PROJECT -MAXIMUM CLEAR HEIGHT IS 12'-0"; (SEE "ARCHITECTURAL VIEWS" SHEET FOR REFERENCE) -MARK UP PC DRAWINGS WITH SIZE AND LOCATION OF CUTOUTS BEFORE SUBMITTING TO DSA

STEP 8: SELECT APPLICABLE SHEET INDEX FOR YOUR PROJECT -REFERENCE THE BASE FRAME (STEP 1) AND THE ROOF PANEL TYPE (STEP 2)

-INCLUDE 'MISC DESIGN OPTIONS' SHEET FOR PROJECTS WITHOUT ELECTRICAL CUTOUTS OR GUTTERS

## ISCLAIMER FOR STRUCTURAL ENGINEERING RESPONSIBILITY

24, PART 1, SECTION 4-316(e) OF THE CALIFORNIA CODE OF REGULATIONS, THIS NOTICE SHALL TO DSA PRIOR TO THE APPROVAL OF PLANS AND SPECIFICATIONS. SITE SPECIFIC PROJECT, J. R. MILLER & ASSOCIATES IS NOT THE DESIGN PROFESSIONAL IN

RESPONSIBLE CHARGE. SITE SPECIFIC PROJECT, J.R. MILLER & ASSOCIATES' RESPONSIBILITY IS LIMITED TO THE TION OF THE PLANS AND SPECIFICATIONS FOR THE SHELTERS OF THIS PC ONLY.

RAL OBSERVATION OF CONSTRUCTION IS SPECIFICALLY EXCLUDED FROM J.R. MILLER & ASSOCIATES' IBILITY FOR THE SITE SPECIFIC PROJECT. STRUCTION ACTIVITIES RELATED TO STRUCTURAL ENGINEERING SHALL BE DELEGATED TO A QUALIFIED BY THE DESIGN PROFESSIONAL IN GENERAL RESPONSIBLE CHARGE. THESE ACTIVITIES INCLUDE, NOT LIMITED TO, APPROVAL OF INSPECTOR QUALIFICATIONS, STRUCTURAL OBSERVATION OF CTION, REVIEW OF INSPECTION REPORTS, AND SIGNING OFF OF THE VERIFIED REPORT FOR

ED WORK J.R. MILLER & ASSOCIATES WILL BE RESPONSIBLE FOR RESPONDING TO QUESTIONS PERTAINING TO THE PLANS AND SPECIFICATIONS FOR THE SHELTERS OF THIS PC WHICH ARISE DURING PLAN REVIEW AND

## WELDING:

- 1. ALL WELDING SHALL COMPLY WITH AWS D1.1 SPECIFICATIONS AND SHALL BE DONE BY AWS QUA CERTIFIED FOR THE TYPE OF WELDING TO BE PERFORMED AS REQUIRED BY DSA. 2. ALL WELDING SHALL BE DONE BY GAS METAL ARC PROCESS WITH E70XX ELECTRODES. FLUX CC
- SHALL CONFORM TO CHARPY NOTCH TOUGHNESS RATING OF 20 ft-16 @ (0°F). 3. ALL WELDING SHALL BE DONE IN THE SHOP WITH REQUIRED INSPECTION, PRE-APPROVED BY DS/
- PROPER MATERIAL ID AND WELDING. 4. WELD FILLER METAL MANUFACTURER SHALL PROVIDE WRITTEN CERTIFICATION OF COMPLIANCE WI

## <u>BOLTING:</u>

SPECIFIC ATIONS.

- 1. ALL BOLTS SHOWN ON THESE DRAWINGS ARE ASTM F3125 GRADE A325 HIGH STRENGTH BOI CONFORMING TO ASTM A-563.
- 2. HIGH STRENGTH BOLTS SHALL BE VERIFIED AND INSPECTED PER CBC 1705A2.1. 3. BEFORE ERECTING THE FRAME, VERIFY ALL BOLTS AND NUTS ARE CLEAN OF DEBRIS AND
- THE HARDWARE ALREADY FASTENED INSIDE THE MEMBERS. CHASING SOME OF THE BOLTS REQUIRED.
- 4. HARDENED STEEL WASHERS SHALL CONFORM TO ASTM F-436. 5. THE BOLTING INSTALLATION REQUIREMENTS OUTLINED BELOW ARE CRITICAL TO THE STRUCT PERFORMANCE. THE INSTALLER IS REQUIRED TO COORDINATE THIS PHASE OF CONSTRUCTION BOLTING INSPECTOR AND THE INSPECTOR OF RECORD PRIOR TO THE ERECTION OF THE FRA BE INSTALLED AND INSPECTED PER THE APPLICABLE VERSION OF AISC'S "SPECIFICATION FO USING HIGH-STRENGTH BOLTS", CBC 1705A.2.1; AISC 341-16 J7; AISC 360-16 N5.6. A)PRETENSIONED JOINTS MUST BE INSTALLED AND INSPECTED TO MEET ONE OF THE FOL 1. TURN-OF-NUT PRETENSIONING
  - 2. CALIBRATED WRENCH PRETENSIONING

#### 3. DIRECT-TENSION-INDICATOR PRETENSIONING (CONTRACTOR RESPONSIBLE FOR REQUIRED WASHERS)

- FOUNDATIONS: 1. ALLOWABLE SOIL PRESSURES ASSUME CLASS 5 SOIL CLASSIFICATION PER CBC TABLE 1806A OTHERWISE.
- 2. PER CBC SECTION 1803A.2, GEOTECHNICAL REPORTS ARE NOT REQUIRED FOR ONE-STORY BUILDINGS OF TYPE II CONSTRUCTION AND 4,000 SQUARE FOOT OR LESS IN FLOOR AREA EARTHQUAKE FAULT ZONESOR SIESMIC HAZARD ZONES AS SHOWN ON THE MOST RECENT CGS. ALLOWABLE FOUNDATION AND LATERAL SOIL PRESSURE VALUES MAY BE DETERMINED
- 3. FILL AND BACKFILL SHALL BE COMPACTED TO 95% OF MAX. DENSITY IN ACCORDANCE WITH
- D-1557 OR AS RECOMMENDED BY THE GEO-TECH ENGINEER. FLOODING NOT PERMITTED. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING, ETC. NECESSARY TO SUPPORT
- BANKS DURING EXCAVATION, AND FORMING AND PLACEMENT OF CONCRETE. 5. MINIMUM SETBACK FROM TOE OF SLOPE ON AN ASCENDING SLOPE SHALL BE 15 FEET AND
- FROM TOE OF SLOPE ON A DESCENDING SLOPE SHALL BE 40 FEET 6. PER CBC SECTION 1803A.6, GEOHAZARD REPORTS ARE NOT REQUIRED FOR ONE-STORY LIGH OF TYPE II CONSTRUCTION AND 4,000 SQUARE FOOT OR LESS IN FLOOR AREA AND NOT LOC FAULT ZONESOR SIESMIC HAZARD ZONES AS SHOWN ON THE MOST RECENT MAPS PUBLISHED
- 7. GEOHAZRD REPORTS ARE TO COMPLY WITH DSA IR A-4 PER IR-7 SECTION 1.8
- 8. SITE SPECIFIC GEOTECHNICAL REPORT IS REQUIRED AT THE TIME OF SITE APPLICATION IS US CLASS 5 SOIL, PER DSA IR PC-7 9. LATERAL BEARING HAS BEEN INCREASED PER CBC 1806A.3.4 & HAS BEEN DESIGNED FOR I
- CONCRETE:

| STRENGTH Pc<br>(28 DAYS) | MENTS: (NORMAL WEIGH <sup>-</sup><br>W/C RATIO<br>(NON-AIR ENTRAINED) | W/C RATIO<br>(AIR ENTRAINED) | SLUMP (±1 |
|--------------------------|---|------------------------------|-----------|
| 4500 PSI                 | 0.44  | 0.35                         | 3"        |
|                          | GN PARAMETERS ARE GC<br>HESE CATEGORIES SHAL                          |                              |           |

- ENTRAINMENT FOR THESE CATEGORIES SHALL BE AS FOLLOWS: F0-0, F1-4.5, F2-0 3. AGGREGATES SHALL CONFORM TO THE ASTM C-33 WITH PROVEN SHRINKAGE CHAR MAX AGGREGATE SIZE = 1".
- 4. CEMENT SHALL CONFORM TO ASTM C-150 (TYPE V) UNLESS NOTED OTHERWISE ON 5. CONCRETE SHALL BE MAINTAINED IN A MOIST CONDITION FOR A MINIMUM OF FIVE
- ALTERNATE METHODS WILL BE APPROVED IF SATISFACTORY PERFORMANCE CAN BE 6. CONCRETE SHALL NOT FREE FALL MORE THAN FIVE FEET.
- 7. CONCRETE DURABILITY SHALL BE PER CBC 1904A.1 & ACI 318-14 CHAPTER 19. 8. CONCRETE SHALL BE TESTED PER CBC 1903A, TABLE 1705A.3. AND ACI 318-14

STEP 10: IDENTIFY PROJECT NAME AND SCHOOL DISTRICT

|          |       | PROJECT NAME:                         |           |        |                | SCHOO | DISTRICT: |                              |               |  |
|----------|-------|---------------------------------------|-----------|--------|----------------|-------|-----------|------------------------------|---------------|--|
|          |       | SHADE STRUCTURE AT<br>ELEMENTARY SCHC |           |        |                | SAC   |           | TO CITY UNIFI<br>DL DISTRCIT |               |  |
|          |       |                                       |           |        |                |       |           |                              |               |  |
| _        |       |                                       | DIMENSION | 5      |                |       |           |                              |               |  |
| STFP     |       |                                       |           | GESTED |                |       |           |                              |               |  |
|          | ,<br> | FRAME WIDTH                           |           | 20'    | X              |       | [] 40'    |                              |               |  |
|          |       | FRAME LENGTH                          | [] 4      | 14'    | X              | 64'   | []84'     | [] 104                       | 1'            |  |
|          |       |                                       |           |        |                |       |           |                              |               |  |
|          | 7     |                                       |           |        |                | RO    | OF PANEL  |                              |               |  |
|          | STEP  | ROOF PANEL TYPE                       |           |        | []             | М     | [] G      | 🗙 s                          |               |  |
|          | _     | PROJECT SITE - SS ACCELERATION (g)    |           |        |                |       |           |                              |               |  |
| STF      |       | 0.539                                 |           |        |                |       |           |                              |               |  |
|          |       |                                       |           |        |                |       |           |                              |               |  |
|          |       |                                       |           |        |                | Ss    | REGION    |                              |               |  |
|          |       |                                       |           |        | Ss REGIONS     |       |           |                              |               |  |
| 4        |       |                                       |           |        |                | Х     | 0         | 0 < Ss <= 2.14               |               |  |
| STEP     |       |                                       | ľ         |        |                |       | 2.14      | 4 < Ss <= 2.5                |               |  |
| ST       |       | DESCRIPTION                           |           |        |                |       |           | 2.50                         | ) < Ss <= 2.7 |  |
|          |       |                                       |           | ľ      |                |       |           | 2.75                         | 5 < Ss <= 3.0 |  |
|          |       |                                       |           |        |                |       |           | S                            | s > 3.73 MAX  |  |
| -        |       |                                       |           |        |                |       |           | •                            |               |  |
|          |       |                                       |           |        | ΤΟΤΑΙ          | ROC   | F DEAD LO | AD                           |               |  |
|          |       |                                       |           |        | D              | EAD   | LOAD      |                              | EX            |  |
| <u>Б</u> |       | ROOF DECK                             |           |        | <u>1.3</u> PSF |       |           | M=1.1                        | PSF; G=1.2PSF |  |
| STEP     |       | COLLATERAL                            |           |        |                |       | _ PSF     |                              | LIGH          |  |
|          |       |                                       |           |        |                |       |           |                              |               |  |

CONSTRUCTION NOTES

TOTAL


1. A DSA-CERTIFIED CLASS 3 PROJECT INSPECTOR IS REQUIRED FOR TH 2. CHANGES TO THE APPROVED DRAWINGS AND SPECIFICATIONS SHALL


<u>1.3</u> PSF

ADD ROOF DECK

- DOCUMENT (CCD) APPROVED BY DSA, AS REQUIRED BY SECTION 4-3. A "DSA CERTIFIED" PROJECT INSPECTOR EMPLOYED BY THE DISTRICT CONTINUOUS INSPECTION OF WORK, THE DUTIES OF THE INSPECTOR
- 4. A DSA ACCEPTED TESTING LABORATORY DIRECTLY EMPLOYED BY THE TESTS AND INSPECTIONS FOR THE PROJECT. 5. THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS ARE THAT ALL RECONSTRUCTION IS TO BE IN ACCORDANCE WITH TITLE 24, CCR. SH OR NON-COMPLYING CONSTRUCTION BE DISCOVERED WHICH IS NOT C FINISHED WORK WILL NOT COMPLY WITH TITLE 24, CCR, A CONSTRUCT
- PLANS AND SPECIFICATIONS, DETAILING AND SPECIFYING THE REQUIRED BEFORE PROCEEDING WITH THE WORK, (SECTION 4-317(c), PART 1, TI 6. GRADING PLANS, DRAINAGE IMPROVEMENTS, ROAD AND ACCESS REQUI SHALL COMPLY WITH ALL LOCAL ORDINANCES

| <form><form><form><form></form></form></form></form>  |  | REINFORCING STE                     | <u>EL:</u>                            |                       |                    |                           |                               |  |
|---|--|-------------------------------------|---------------------------------------|-----------------------|--------------------|---------------------------|-------------------------------|--|
|   |  |                                     |                                       | ED STEEL CONFORMI     | NG TO THE RE       | QUIREMENTS OF ASTM        | M A-615,                      |  |
| <text></text>   | ALIFIED WELDERS                                    |                                     |                                       |                       |                    |                           |                               |  |
| <form></form>   | ORE ARC WELD                                       |                                     |                                       | N OF REINFORCING E    | BARS SHALL C       | CONFORM TO THE AC         | I                             |  |
| <form></form>   | SA, TO ENSURE                                      | 3. MIN. COVE                        | R FOR CAST-IN-PLACE CON               | ICRETE SHALL BE AS    |                    | IE STRUC TURES."          |                               |  |
| <text></text>   | NTH CODE AND                                       |                                     |                                       |                       |                    |                           |                               |  |
| <form></form>   |  |                                     | •••                                   |                       | 4"                 |                           |                               |  |
| <form></form>   |  | 4. BARS SHA                         | LL BE CLEAN OF RUST, GRE              | •                     | RIAL LIKELY 1      | O IMPAIR BOND.            |                               |  |
|   | DLTS (UNO), WITH THE NUTS                          | 5. REINFORCI                        | NG SHALL BE LAP SPLICED F             |                       |                    | TEMS SHALL BE WELL        | SECURED IN POSITION.          |  |
|   |  | 7. WELDING C                        | F REINFORCING IS NOT ALLO             | WED.                  |                    |                           |                               |  |
|   |  |                                     |                                       |                       |                    |                           | _                             | REV  |
| <form></form>   |  |                                     |                                       |                       |                    |                           |                               | REV DATE   |
|   | N WITH THE SPECIAL                                 |                                     |                                       | NC PHOSPHATE IN A     | N MINIMUM EI       | GHT STAGE ELEC TRO        | DEPOSITION                    |  |
|   |  | PRIMER(E                            | -COAT) AND COATED TO A                | UNIFORM THICKNESS     | OF A MINIMU        | M OF 0.7 TO 0.9 MIL       | S. THE E-COATING SHALL        |  |
| <form></form>   | ULLOWING REQUIREMENTS:                             | 4. THE STEEL                        | SHALL THEN HAVE A TGIC                | POLYESTER COLOR C     | OAT APPLIED        | OVER THE E-COATE          | D SURFACE.                    |  |
|   |  | ULTRAVIO                            | LET LIGHT, TO HELP PREVEN             | T FADING.             |                    |                           |                               |  |
|   | R PURCHASE OF                                      | 7. ALL CARB                         | ON STEEL MEMBERS (COLUM               | NS, BEAMS, PLATES,    | ETC.) NOT PO       | OWDER-COATED SHAL         | L BE PAINTED WITH PRIME       |  |
|   | A. UNLESS NOTED                                    |                                     |                                       | JARD PRACTICE" AND    | D THE "AISC        | SPECIFIC ATION SEC TIC    | ON M3'(UNLESS NOTED           |  |
|   |  |                                     |                                       |                       | мрн                | MII F                     | S PER HOUR                    | ARCHITECTS ENGINEERS                                 |
|   | AND NOT LOCATED WITHIN                             |                                     |                                       |                       |                    |                           |                               | T. 714.524.1870   F. 714.524.1875                    |
|   |  |                                     | · · · · · · · · · · · · · · · · · · · | ,                     | _                  |                           |                               | - PROFESS/OK   |
|   |  |                                     |                                       |                       |                    |                           |                               |  |
|   |  |                                     |                                       |                       |                    |                           |                               |  |
|   |  |                                     |                                       |                       |                    |                           |                               | - AUCTURE  |
|   | CATED WITHIN EARTHQUAKE                            |                                     |                                       |                       |                    |                           |                               | GF CALLFOR   |
|   |  |                                     |                                       |                       | _                  | POUNDS P                  |                               |  |
|   |  |                                     |                                       | ARC HITEC T           |                    |                           |                               | -  |
|   | P-DELTA EFFEC TS                                   |                                     |                                       |                       |                    |                           |                               | -  |
|   |  |                                     |                                       |                       |                    |                           |                               | -  |
| Image: Normal biology       Image: Normal bio   |  |                                     |                                       | INCH                  |                    |                           | ROOF PANEL (MCELROT)          | <u> </u>   |
| (a) (b) (b) (c) (c) (c) (c) (c) (c) (c) (c) (c) (c  | · · · · · · · · · · · · · · · · · · ·              |                                     |                                       |                       |                    |                           |                               |  |
|   | DAYS AFTER PLACEMENT.<br>E ASSURED.                |                                     |                                       |                       |                    |                           |                               | FLO ACS CG   |
| II. I de MAN3         III. I de MAN3         IIIII. I de MAN3         IIII. I de MAN3         IIIII. I de MAN3         IIIII. I de MAN3         IIIII. I de MAN3         IIIII. I de MAN3         IIIIIIIIII.   |  | و بر م<br>SOIL                      | . CLASS 5 (BEARING)-1500 PSF          |                       |                    |                           | ASS 3 (BEARING)-3000 PSF [ ]  |  |
| Image: Selection of the se |  |                                     | ASS 5 (LATERAL BEARING)-100           |                       |                    |                           | S 3 (LATERAL BEARING)—200 PSF |  |
| Image: Selection of the se | L J (NO MAX)                                       |                                     |                                       | MISC                  | ELLANEOUS          |                           |                               |  |
| MAX DEAD LOAD       OBS. FRAME       102 20       103 40       R0 40       5       R0 40         1       100 F PARL 197E       M       6       3       M       6       5       M       6       5         1       3 PST       05       9 PST       05       9 PST       05       101       11   |  |                                     | CLEAR HEIG                            | <br>НТ                | []                 |                           |                               |  |
| MAX DEAD LOAD       OBS. FRAME       102 20       103 40       R0 40       5       R0 40         1       100 F PARL 197E       M       6       3       M       6       5       M       6       5         1       3 PST       05       9 PST       05       9 PST       05       101       11   |  |                                     |                                       | TOUTS                 |                    |                           |                               |  |
| MAX DEAD LOAD       OBS. FRAME       102 20       103 40       R0 40       5       R0 40         1       100 F PARL 197E       M       6       3       M       6       5       M       6       5         1       3 PST       05       9 PST       05       9 PST       05       101       11   |  |                                     | GUTEKS                                |                       |                    | K TES                     |                               |  |
| MAX DLAD LOAD         Statustic ion         I <td></td> <td></td> <td>BASE FRAME</td> <td></td> <td></td> <td>RG 30</td> <td>RG 40</td> <td></td>   |  |                                     | BASE FRAME                            |                       |                    | RG 30                     | RG 40                         |  |
| S       PSF       O       S       PSF         00       S       FSF       S  |  |                                     |                                       |                       |                    |                           |                               |  |
| 15       5       PSF         10       4       PSF       FRAMO PLAN       LS2.0       LS2.0       LS2.0       LS3.0       LS3.0       LS4.0  |  |                                     |                                       |                       |                    |                           |                               |  |
| AD       4 P JA       CANNON PLAN       CLAST   |  |                                     |                                       |                       |                    |                           |                               |  |
| Image: Set state 2 = 1 = 2 = 1 = 2 = 1 = 2 = 1 = 2 = 1 = 2 = 2  | 00 4 PSF   | S TEP                               |                                       |                       |                    | 3.1 LS3.1 LS3.1           |                               |  |
| F. IS-13PSF (SEE STEP 2)<br>ITING, ETC         AND COLLATERAL LOADS<br>XX 5 PSF)  | 3 PSF  |                                     |                                       |                       |                    |                           |                               | Ë  |
| F. IS-13PSF (SEE STEP 2)<br>ITING, ETC         AND COLLATERAL LOADS<br>XX 5 PSF)  |  |                                     |                                       |                       |                    |                           |                               |  |
| Distriction       Description       Design Values         AND COLLATERAL LOADS       WIND DESIGN       II         MUND DESIGN       II       III         BASIC WIND SPEED (S SECOND GUST), V <sub>uit</sub> 94 MPH       III         BASIC WIND SPEED (S SECOND GUST), V <sub>uit</sub> 94 MPH       III         Strike Trees concentry       II       III         COWNER) AND APPROVED BY DSA SHALL PROVDE<br>ARE DEFINED IN SECTION 4–342, PART 1, TITLE 24, CCR.       D       D         Strike TV and Condition of the section of the sectin of the section of the section of the section of the section of t  |  |                                     |                                       | DESIGN CRITERIA       | FOR 3110 60        | TH STREET, SACRAME        | ENTO, CA 95820                |  |
| MIND DESIGN       Distinction         HIS PROJECT.       BASIC WIND SPEED (3 SECOND GUST), V <sub>uit</sub> 94 MPH         HIS PROJECT.       BE MADE BY ADDENDA OR CONSTRUCTION CHANGE       II       III         -338, PART 1, TITLE 24, CCR.       C       C         (OWNER) AND APPROVED BY DSA SHALL PROVIDE<br>ARE DEFINED IN SECTION 4-342, PART 1, TITLE 24, CCR.       D       D       COPYRIGHT 2004, ICON SHELT<br>SYSTEMS, INC.         SEISMIC SITE CLASS       D       0.539       0.539       016.396.0919         NOULD ANY EXISTING CONDUCT ALL THE REQUIRED       *All information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       616.396.0919         *AULINFORMED DOCUMENTS WHEREIN THE<br>TON CHANGE DOCUMENT (CCD), OR A SEPARATE SET OF<br>D WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA<br>ITLE 24, CCR)       PRE-CHECK (PC) DOCUMENT<br>Code: 2019 CBC       LSTI.O         RREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS       PRE-CHECK (PC) DOCUMENT<br>Code: 2019 CBC       LSTI.O   | · /  |                                     |                                       |                       |                    | N                         |                               |  |
| MIND DESIGN       Distinction         HIS PROJECT.       BASIC WIND SPEED (3 SECOND GUST), V <sub>uit</sub> 94 MPH         HIS PROJECT.       BE MADE BY ADDENDA OR CONSTRUCTION CHANGE       II       III         -338, PART 1, TITLE 24, CCR.       C       C         (OWNER) AND APPROVED BY DSA SHALL PROVIDE<br>ARE DEFINED IN SECTION 4-342, PART 1, TITLE 24, CCR.       D       D       COPYRIGHT 2004, ICON SHELT<br>SYSTEMS, INC.         SEISMIC SITE CLASS       D       0.539       0.539       016.396.0919         NOULD ANY EXISTING CONDUCT ALL THE REQUIRED       *All information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       616.396.0919         *AULINFORMED DOCUMENTS WHEREIN THE<br>TON CHANGE DOCUMENT (CCD), OR A SEPARATE SET OF<br>D WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA<br>ITLE 24, CCR)       PRE-CHECK (PC) DOCUMENT<br>Code: 2019 CBC       LSTI.O         RREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS       PRE-CHECK (PC) DOCUMENT<br>Code: 2019 CBC       LSTI.O   |  |                                     |                                       |                       |                    |                           | DESIGN VALUES                 |  |
| HIS PROJECT.       II         BE MADE BY ADDENDA OR CONSTRUCTION CHANGE       II         .338, PART 1, TITLE 24, CCR.       C         (OWNER) AND APPROVED BY DSA SHALL PROVIDE       SEISMIC DESIGN         ARE DEFINED IN SECTION 4-342, PART 1, TITLE 24, CCR.       D         SISTRICT (OWNER) SHALL CONDUCT ALL THE REQUIRED       SISSIC SITE CLASS       D         THE WORK OF THE ALTERATION, REHABILITATION OR       SS       0.539       616.396.0919         YOURD ANY EXISTING CONDITIONS SUCH AS DETERIORATION       SOURD ANY EXISTING CONDUCT ALL THE REQUIRED       *All information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       616.396.0919         YOURK SHALL BE SUBMITTED TO AND APPROVED BY DSA       THE WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA       THE C24, CCR)       III information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       616.396.0944 FX         ITLE 24, CCR)       III information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       616.396.0944 FX         USUEND ANY EXISTING CONDUMENT AL HEALTH CONSIDERATIONS       FRE-CHECK (PC) DOCUMENT       LS1.0         ITLE 24, CCR)       III information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       LS1.0         III EXISTING CONSIDERATIONS       SEISMIC SITE CLASS       D       SEISMIC SITE CLASS       LS1.0         III EXIS LINCOLUMENT SAN  | ·  |                                     |                                       | BASIC WIND SPE        |                    |                           | 94 MPH                        |  |
| HIS PROJECT.         BE MADE BY ADDENDA OR CONSTRUCTION CHANGE         '338, PART 1, TITLE 24, CCR.         (OWNER) AND APPROVED BY DSA SHALL PROVIDE         ARE DEFINED IN SECTION 4-342, PART 1, TITLE 24, CCR.         DISTRICT (OWNER) SHALL CONDUCT ALL THE REQUIRED  |  |                                     |                                       | RISK CATEGORY         | -                  |                           | ll                            | WWW.ICONSHELTERS.COM<br>COPYRIGHT 2004, ICON SHELTER |
| Instructed by Addenda or Construction Change       SEISMIC DESIGN       HOLLAND MI, 4942         -338, PART 1, TITLE 24, CCR.       0.539       0.539         (OWNER) AND APPROVED BY DSA SHALL PROVIDE       SEISMIC SITE CLASS       0.539         ARE DEFINED IN SECTION 4-342, PART 1, TITLE 24, CCR.       0.539       616.396.0919         So DISTRICT (OWNER) SHALL CONDUCT ALL THE REQUIRED       Seismic oprovided by https://asce7hazardtool.online/and https://seismicmaps.org/       616.396.0944 FX         AULD ANY EXISTING CONDITIONS SUCH AS DETERIORATION OR       NO APPROVED BY DSA UTLE CONTRACT DOCUMENTS WHEREIN THE       FMI information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       LS16.396.0944 FX         D WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA ITLE 24, CCR.       PRE-CHECK (PC) DOCUMENT       LS1.0         Inte 24, CCR)       PRE-CHECK (PC) DOCUMENT       LS1.0         IREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS       PRE-CHECK (PC) DOCUMENT       LS1.0  |  |                                     |                                       | EXPOSURE CATEO        | JURY               |                           | C                             |  |
| Ss       0.539         ARE DEFINED IN SECTION 4–342, PART 1, TITLE 24, CCR.       5s         E DISTRICT (OWNER) SHALL CONDUCT ALL THE REQUIRED       *All information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       616.396.0919         NOT THE WORK OF THE ALTERATION, REHABILITATION OR       *All information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       616.396.0944 FX         OULD ANY EXISTING CONDITIONS SUCH AS DETERIORATION       *All information provided by https://asce7hazardtool.online/and https://seismicmaps.org/       616.396.0944 FX         OVERED BY THE CONTRACT DOCUMENTS WHEREIN THE       TION CHANGE DOCUMENT (CCD), OR A SEPARATE SET OF       F         D WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA       PRE-CHECK (PC) DOCUMENT       LS1_0         ITLE 24, CCR)       PRE-CHECK (PC) DOCUMENT       LS1_0         IREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS       Aseparate project application for construction is required.       LS1_0   | BE MADE BY ADDENDA OR                              |                                     | HANGE                                 |                       |                    | N                         | <br>                          | HOLLAND MI, 49423                                    |
| *All information provided by https://asce7hazardtool.online/and https://seismicmaps.org/<br>*All information provided by https://asce7hazardtool.online/and https://seismicmaps.org/<br>616.396.0944 FX<br>800.748.0985<br>616.396.0944 FX<br>616.396.0944 FX<br>616.396.0944 FX<br>616.396.0944 FX<br>616.396.0944 FX<br>100 CHANGE DOCUMENT (CCD), OR A SEPARATE SET OF<br>D WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA<br>ITLE 24, CCR)<br>IREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS  | (OWNER) AND APPROVED E<br>ARE DEFINED IN SECTION 4 | BY DSA SHALL PF<br>—342, PART 1, TI | TLE 24, CCR.                          | Ss                    |                    |                           | 0.539                         |  |
| HOULD ANY EXISTING CONDITIONS SUCH AS DETERIORATION<br>COVERED BY THE CONTRACT DOCUMENTS WHEREIN THE<br>TION CHANGE DOCUMENT (CCD), OR A SEPARATE SET OF<br>D WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA<br>ITLE 24, CCR)<br>IREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS<br>IREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS<br>INCLUDENT CODE: 2019 CBC<br>A separate project application for construction is required.   | E DISTRICT (OWNER) SHALL                           | CONDUCT ALL TH                      | E REQUIRED                            | *All information prov | vided by https://a | asce7hazardtool.online/ar | nd https://seismicmaps.org/   |  |
| TION CHANGE DOCUMENT (CCD), OR A SEPARATE SET OF<br>D WORK SHALL BE SUBMITTED TO AND APPROVED BY DSA<br>ITLE 24, CCR)<br>IREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS<br>IREMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS<br>A separate project application for construction is required.   | HOULD ANY EXISTING CONDI-                          | TIONS SUCH AS D                     | ETERIORATION                          |                       |                    |                           |                               |  |
| ITLE 24, CCR)         INFRMENTS AND ENVIRONMENTAL HEALTH CONSIDERATIONS         PRE-CHECK (PC) DOCUMENT<br>Code: 2019 CBC         A separate project application for construction is required.  | TION CHANGE DOCUMENT (C                            | CCD), OR A SEPA                     | RATE SET OF                           |                       |                    |                           |                               |  |
| Code: 2019 CBC<br>A separate project application for construction is required.  | ITLE 24, CCR)                                      |                                     |                                       |                       |                    | PRE-                      |                               | LS1.0  |
| PRINTED ON :  |  |                                     |                                       |                       |                    | A separate project        |                               | required.  |
|   |  |                                     |                                       |                       |                    |                           |                               | PRINTED ON :   |





c:\Users\mark.luzi\Documents\1504.07\_Tahoe\_Central\_mark.lu

|        | 103-19: LISTING OF STRUCTURAL TES  | STS & SPECIA   | L INSPEC                     | TIONS (SOILS), 2019 CBC<br>School District:   | $\neq$   |             |
|--------|--|----------------|------------------------------|---|--|-------------|
| 04-0   | Incaron Number:         School Name:           00000         ICON Shelter Systems           File Number:         Increment Number: |                |                              | PC Submittal<br>Date Created:   |  |             |
| D J M  |  |                |                              | 2021-07-14 05:50:33   |  |             |
|        | 5. RETAINING WALLS   |                |                              |   |  |             |
|        | Test or Special Inspection   | Туре           |                              | d Code References and Notes   |  |             |
|        | a. Placement, compaction and inspection of backfill.   | Continuous     | By<br>GE*                    | 1705A.6.1. * By geotechnical ingineer or his or her qualified   |  |             |
|        |  |                |                              | representative. (See Section 2 above).  |  |             |
|        | b. Placement of soil reinforcement and/or drainage   | Continuous     | GE*                          | * By geotechnical engineer or his or her qualified representative   |  |             |
|        | devices.<br>c. Segmental retaining walls; inspect placement of   | Continuous     | GE*                          | * By geotechnical engineer or his or her qualified representative   |  |             |
|        | units, dowels, connectors, etc.<br>d. Concrete retaining walls.  | Provide tests  | and inspect                  | See DSA IR 16-3.  | ICON STD RH/DS   | SA-PC       |
|        |  |                | $\rightarrow$                | ons per MASONRY section below.  | DRAWN BY AN  | NGEL        |
|        |  |                |                              | <b>\</b>  |  | /2021       |
|        | 6. OTHER SOIL<br>Test or Special Inspection  | Туре           | Performe                     | d Code Roterences and Notes   |  | / 2021      |
|        |  |                | Ву                           |   | REV  |             |
|        | a. Soil Improvements   | Test           | GE*                          | Submit a comprehensive report documenting final soil improvemen<br>constructed, construction observation and the results of the confirm<br>testing and analysis to COS for final acceptance.<br>* By geotechnical engineer of his or her qualified representative |  |             |
|        | b. Inspection of Soil Improvements   | Continuous     | GE*                          | * By geotechnical engineer or his other qualified representative  |  |             |
|        |  |                |                              |   |  |             |
|        |  |                |                              |   |  |             |
|        |  |                |                              |   |  |             |
| DGS [  | DSA 103 9 (Revised 07/16/2020)   |                |                              |   |  |             |
| DIVISI | ON OF THE STATE ARCHITECT  |                | T OF GENERAL<br>Page 4 of 11 | SERVICES STATE OF CAL   | IFORMA   |             |
|        |  |                | Page 4 of 11                 |   |  | $ \prod $   |
|        |  |                |                              |   |  |             |
|        | 103-19: LISTING OF STRUCTURAL TEST   |                |                              | IONS (Concrete) 2010 CPC  | ARCHITECTS ENGI  | NEERS       |
| Table  | 1705A.3; ACI 318-14 Sections 26.12 & 26.13   |                | INSPECT                      |   | 2700 SATURN ST I BREA, CA 9<br>T. 714.524,1870   F. 714.524. |             |
| 04-00  | cation Number: School Name:<br>0000 ICON Shelter Systems<br>ile Number: Increment Number:  |                |                              | School District:<br>PC Submittal<br>Date Created:   | WWW.JRMA.COM   |             |
| JJAF   |  |                |                              | 2021-07-14 05:50:33   | PROFESSION   |             |
|        | 19.1 SHOP WELDING:   |                |                              | /   |  | 381         |
|        | Test or Special Inspection   | Туре           |                              | Code References and Notes   |  | 翱           |
| 7      | a. Inspect groove welds, multi-pass fillet webs, single pa   | ess Continuous | By<br>SI                     | Table 1705A.2.1 Items 53:1-4; AISC 360-16 (and AISC 341-16 as   |  | // /H       |
|        | fillet welds > 5/16", plug and slot welds.<br>b. Inspect single-pass fillet welds $\leq$ 5/16", floor and rook                     | Periodic       | SI                           | applicable); DSA IR 17-7.<br>1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC  | OF CALIFO  | <b>\$\$</b> |
|        | deck welds.  | Pekiodic       | SI                           | 341-16 as applicable); DSA IR 17-3.<br><b>1705</b> 2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1  |  | /29/2       |
|        | and provide the raining systems.   |                |                              | DS TR 17-3.   |  |             |
|        | d. Verification of reinforcing steel weldability other than ASTM A706.   | Periodic       | X                            | 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported or mill certificates.   | n  |             |
|        | e. Inspect welding of reinforcing steel.   | Continuous     | sı                           | Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8<br>ANS D1.4; DSA IR 17-3.   | 3;   |             |
|        |  |                |                              |   |  |             |
|        | 23. ANCHOR BOLTS AND ANCHOR RODS:  |                |                              |   |  |             |
|        | Test or Special Inspection   |                | Performed<br>By              | Code References and Notes   |  |             |
| 1      | a. Anchor Bolts and Anchor Rods  | Test           | LOR                          | Sample and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-1   | er   |             |
|        | <b>b</b> . Threaded rod not used for foundation anchorage.   | Test           | LOR                          | Sample and test threaded rods not reach, identifiable per procedures noted in DSA IR 17-11.   | APPROVED   |             |
|        |  |                |                              |   | DIV. OF THE STATE ARCHITECT                                  |             |
|        |  |                |                              |   | APP: 04-120013 PC  |             |
| DGS DS | GA 103-1 (Revised 07/16/2020)  |                |                              | <b>\</b>  |  |             |
|        | DF OF THE STATE ARCHITECT  | DEPARTMENT     |                              | RVICES STATE OF CALIFO  | SS ☑ FLS ☑ ACS ☑ CG □<br>DATE:08/06/2021                     |             |
|        |  | Pa             | ge 8 of 11                   |   |  |             |
|        |  |                |                              |   |  | ~           |
|        | FOR ALL TESTING AND  |                |                              |   |  |             |
|        | NSPECTION ITEMS SEE  |                |                              |   |  |             |
|        | THE DSA APPROVED 103<br>FOR THIS PROJECT.  |                |                              |   |  |             |
| Ľ      |  |                |                              |   |  |             |
|        |  |                |                              |   |  |             |
|        |  |                |                              |   |  |             |
|        |  |                |                              |   |  |             |
|        |  |                |                              |   |  |             |
|        |  |                |                              |   |  |             |
|        |  |                |                              |   |  |             |

| PRE-CHECK (PC) DOCUMENT                              |
|--|
| Code: 2019 CBC                                       |
| eparate project application for construction is requ |

PRINTED ON :

M

 $\bigcirc$ 

 $\square$ 

\_\_\_\_\_

 $\sim$ 

\_\_ (N


DISTINCTIVE STEEL SHELTERS


WWW.ICONSHELTERS.COM COPYRIGHT 2004, ICON SHELTER


SYSTEMS, INC. 1455 LINCOLN AVE HOLLAND MI, 49423

> 616.396.0919 800.748.0985 616.396.0944 FX


LS1









:\Users\mark.luzi\Documents\1504.07\_Tahoe\_Central\_mark.luzi.rv







## EXISTING TOPOGRAPHY

*⊾123* 

-----

•

~~--~~

99.9

99.99

x-----x-----x--

| <br>= | PROPERTY LIN |
|-------|--------------|
| <br>= | CENTERLINE   |

- \_\_\_\_ \_ \_ \_ \_ \_ \_ = EASEMENT
  - = PROPERTY CORNER FOUND AS NOTED
  - = PROPERTY CORNER NOTHING FOUND OR SET
  - = TEMPORARY BENCHMARK (SEE TBM LIST FOR INFO)
- = SWALE OR DRAINAGE FLOW
  - = DRAINAGE FLOW = FENCE (TYPE NOTED)
  - = TREE (SIZE/TYPE INDICATED)
  - = SLOPE
- \_\_\_\_\_ 100 \_\_\_\_\_ = CONTOUR
  - = CONCRETE SURFACE
  - = EDGE OF ASPHALT
  - = EDGE OF BUILDING
  - = SIGN
  - = POST OR BOLLARD
  - = GROUND ELEVATION
  - = HARD SURFACE ELEVATION

## FXISTING UTHITIES

| <u>EXISTIN</u>   | <u>NG UTILITIES</u>   |
|------------------|---|
| 12"SD            | = STORM DRAIN LINE  |
| 12"SD            | (SIZE & DIRECTION OF FLOW)<br>= STORM DRAIN LINE  |
|                  | (RECORD INFORMATION)  |
| 1 <u>2"SD</u>    | = STORM DRAIN LINE<br>(UNDERGROUND LOCATING)  |
| SD               | = STORM DRAIN MANHOLE   |
| 0                | = STORM DRAIN CLEANOUT  |
|                  | = DROP INLET  |
| ¢                | = AREA DRAIN  |
| ∘ <i>RW</i> L    | = RAIN WATER LEADER   |
| • <i>DS</i>      | = DOWNSPOUT   |
| <u>12"SS</u>     | = SANITARY SEWER LINE   |
| <u>12"SS</u>     | (SIZE & DIRECTION OF FLOW)<br>= SANITARY SEWER LINE   |
| 12"SS            | (RECORD INFORMATION)<br>= SANITARY SEWER LINE   |
|                  | (UNDERGROUND LOCATING)  |
| 63               | = SANITARY SEWER MANHOLE  |
| 0                | = SANITARY SEWER CLEANOUT   |
| W                | = WATER LINE (SIZE INDICATED)   |
| - <i>—-W</i> — — | <ul><li>WATER LINE (RECORD INFORMATION)</li><li>WATER LINE (UNDERGROUND LOCATING)</li></ul> |
|                  | = WATER LINE (UNDERGROUND LOCATING)<br>= WATER MANHOLE                                      |
| $\otimes$        | = WATER MANHOLE<br>= WATER VALVE  |
| wm.              | = WATER METER   |
| W                | = WATER BOX   |
| 0                | = IRRIGATION CONTROL VALVE  |
| Q                | = FIRE HYDRANT  |
|                  | = BACKFLOW PREVENTER  |
| •                | = SPRINKLER   |
| φ                | = HOSE BIBB   |
| — <i>ОН-Е</i> —  | = OVERHEAD ELECTRIC LINE  |
| — <i>E</i> —     | = UNDERGROUND ELECTRIC LINE   |
| — <i>——</i> Е——— | = UNDERGROUND ELECTRIC LINE<br>(RECORD INFORMATION)   |
| — —E— —          | = UNDERGROUND ELECTRIC LINE<br>(UNDERGROUND LOCATING)                                       |
| Ē                | = ELECTRIC MANHOLE  |
| -0-              | = UTILITY POLE (WITH GUY WIRE)  |
| EM               | = ELECTRIC METER  |
| E                | = ELECTRIC BOX  |
| SLB              | = STREET LIGHTING BOX   |
| •¤ <i>OR</i> 💢   | = LIGHT STANDARD  |
|                  | = SIGNAL LIGHT  |
| Œ                | = FLOOD LIGHT   |
|                  | = ELECTRICAL OUTLET   |
|                  | = GAS LINE (SIZE INDICATED)   |
|                  | = GAS LINE (RECORD INFORMATION)   |
| -                | = GAS LINE (UNDERGROUND LOCATING)   |
| Ŭ                | = GAS MANHOLE<br>= GAS VALVE  |
| G)               | = GAS VALVE<br>= GAS METER  |
|                  | = GAS METER<br>= TELEPHONE LINE   |
|                  | = TELEPHONE LINE (RECORD INFORMATION)   |
|                  | = TELEPHONE LINE (UNDERGROUND LOCATING)   |
| SD               | = STORM DRAIN BOX   |
|                  |   |

- = TRAFFIC SIGNAL BOX

## A.P.N 060-0240-012 \_ ELEV. <u>52.03</u> BENCHMARK NO. <u>CO. B.M. 21–53</u> FOUND 7/8" METAL DISC STAMPED "CO. B.M. 21-53"

LOCATED IN TOP OF VERTICAL CURB IN CHISELED SQUARE ABOVE D.I. SOUTH SIDE OF KIEFER BLVD. APPROX. 40' WEST OF CONCRETE WALK TO ENTRANCE TO ROSEMONT FIRST BAPTIST CHURCH AND 0.10 MILE EAST OF MANLOVE

# TRM LIST

TS

| <u>NUMB</u> | <u>ER</u> | DESCRIPTION  | NORTHING | EASTING | ELEV  |
|-------------|-----------|--------------|----------|---------|-------|
| 1           | CPS       | CHISELED "+" | 4785.90  | 5392.83 | 48.79 |
| 2           | CPS       | PK+WASHER    | 5013.76  | 5552.23 | 48.70 |
| 3           | CPS       | CHISELED "+" | 4894.67  | 5443.45 | 49.44 |
| 4           | CPS       | CHISELED "+" | 4719.71  | 5218.18 | 49.14 |
| 5           | CPS       | CHISELED "+" | 4882.88  | 5294.81 | 48.61 |
| 6           | CPS       | CHISELED "+" | 5045.53  | 5138.24 | 47.98 |

| ASB<br>BO                                    |
|--|
| BV   |
| BW   |
| C/L  |
| CB<br>CL                                     |
| CMP  |
| CATV   |
| CO   |
| COMM<br>CONC.                                |
| CONC.<br>CONST.                              |
| CR   |
| CS   |
| DC<br>DDC                                    |
| DG   |
| DI   |
| DIA  |
| DIP<br>DWG                                   |
| DS   |
| E  |
| EP   |
| ESMT<br>EX                                   |
| FS   |
| FDC  |
| FL   |
| FM<br>FF                                     |
| FH   |
| G  |
| GR   |
| GRD<br>GV                                    |
| HB   |
| HBD  |
| HDPE   |
| HP<br>INV                                    |
| JP   |
| LF   |
| LIP  |
| LT<br>MS                                     |
| NTS  |
| ОН   |
| PCC  |
| PD<br>PIV                                    |
| P/I  |
| P/L<br>PP                                    |
| PUE  |
| PVC<br>RCP                                   |
| RCP  |
| RIM  |
| RP   |
| RW   |
| SCH<br>SD<br>SDMH<br>SG<br>SS<br>SSMH<br>STD |
| SDMH   |
| SG   |
| SS   |
| SSMH<br>STD                                  |
| S/W  |
| Т  |
| TC<br>TD                                     |
|  |
| TDCB<br>TP                                   |
| TR   |
| TRW  |
| TSW<br>TW                                    |
| U  |
| UG   |
| UON<br>VCP                                   |
| VCP  |

W/

WV

W/0

AD

APN

ARV

ASB

## CIVIL ABBREVIATIONS AND LEGEND

|             | ABBREVIATIONS   |
|-------------|---|
|             | NOT ALL ABBREVIATIONS                                 |
|             | E USED ON THESE PLANS.<br>AGGREGATE BASE              |
| AC          | ASPHALTIC CONCRETE<br>AREA DRAIN                      |
| PN          | ASSESSOR'S PARCEL NUMBER<br>AIR RELEASE VALVE         |
| SB          | AGGREGATE SUB-BASE                                    |
| 3V          | BLOW-OFF VALVE<br>BUTTERFLY VALVE                     |
| C/L         | BACK OF WALK<br>CENTERLINE                            |
| L           | CATCH BASIN<br>CLASS                                  |
| CATV        | CORRUGATED METAL PIPE<br>CABLE TELEVISION             |
| CO<br>COMM  | CLEANOUT<br>COMMUNICATION                             |
|             | CONCRETE<br>CONSTRUCT                                 |
| R           | CURB RETURN<br>CONCRETE SURFACE                       |
| )C          | DOUBLE CHECK VALVE<br>DOUBLE DETECTOR CHECK VALVE     |
| )G          | DECOMPOSED GRANITE<br>DROP INLET                      |
| AI          | DIAMETER<br>DUCTILE IRON PIPE                         |
|             | DRAWING<br>DOWNSPOUT                                  |
| -<br>-      | ELECTRIC  |
| SMT         | EDGE OF PAVEMENT<br>EASEMENT                          |
| X<br>S      | EXISTING<br>FIRE SERVICE LINE                         |
| DC<br>L     | FIRE DEPARTMENT CONNECTION<br>FLOWLINE                |
| М<br>F      | SANITARY SEWER FORCE MAIN<br>FINISHED FLOOR ELEVATION |
| Ή<br>;      | FIRE HYDRANT<br>GAS                                   |
| SR<br>SRD   | GRATE ELEVATION<br>GRADE ELEVATION                    |
| SV<br>IB    | GATE VALVE<br>HOSE BIBB                               |
| IBD<br>IDPE | HEADER BOARD<br>HIGH DENSITY POLYETHYLENE PIPE        |
| IP<br>NV    | HIGH POINT<br>PIPE INVERT ELEVATION                   |
| IP<br>.F    | JOINT UTILITY POLE<br>LINEAL FEET                     |
| .IP         | LIP OF GUTTER<br>LEFT                                 |
| 1S          | MOWSTRIP<br>NOT TO SCALE                              |
| ЭН          | OVERHEAD<br>PORTLAND CEMENT CONCRETE                  |
|             | PLANTER DRAIN<br>POST INDICATOR VALVE                 |
| P∕L         | PROPERTY LINE<br>POWER POLE                           |
|             | PUBLIC UTILITY EASEMENT<br>POLYVINYL CHLORIDE         |
| RCP         | REINFORCED CONCRETE PIPE                              |
| RIM         | RADIUS<br>MANHOLE RIM ELEVATION (SOLID COVER)         |
| R<br>R<br>W | REDUCED PRESSURE BACKFLOW PREVENTER<br>RIGHT OF WAY   |
| SCH<br>SD   | SCHEDULE<br>STORM DRAIN                               |
| G           | STORM DRAIN MANHOLE<br>SUBGRADE ELEVATION             |
| SMH         | SANITARY SEWER<br>SANITARY SEWER MANHOLE              |
| STD<br>S/W  | STANDARD<br>SIDEWALK                                  |
| -           | TELEPHONE<br>TOP OF CURB                              |
| D<br>DCB    | TRENCH DRAIN<br>TRENCH DRAIN CATCH BASIN              |
| P<br>R      | TELEPHONE POLE<br>TOP OF RAMP ELEVATION               |
| RW          | TOP OF RETAINING WALL<br>TOP OF SEAT WALL             |
| W           | TOP OF WALK ELEVATION<br>UTILITY                      |
| JG          | UNDERGROUND<br>UNLESS OTHERWISE NOTED                 |
| /CP         | VITRIFIED CLAY PIPE<br>WATER                          |
|             | WATER<br>WITH   |

WITH WITHOUT

WATER VALVE

| LEGEND                           |  |  |  |  |
|----------------------------------|--|--|--|--|
| NOTE: NOT ALL<br>BE USED ON 1    |  |  |  |  |
|                                  | & DRAINAGE SYMBOLS:                          |  |  |  |
| 8" SD                            | STORM DRAIN LINE<br>(SIZE AND FLOW SHOWN)    |  |  |  |
| •                                | STORM DRAIN MANHOLE<br>(SDMH)                |  |  |  |
| =                                | CATCH BASIN (CB)                             |  |  |  |
| <b></b>                          | DROP INLET (DI)                              |  |  |  |
| <b>—</b>                         | AREA DRAIN (AD)                              |  |  |  |
| •                                | PLANTER DRAIN (PD) OR<br>FLOOR DRAIN (FD)    |  |  |  |
| <b>0</b> co                      | STORM DRAIN CLEANOUT                         |  |  |  |
| 99.99                            | ELEVATION                                    |  |  |  |
| FF=100.00                        | FINISHED FLOOR ELEVATION                     |  |  |  |
| PAD=99.33                        | BUILDING PAD ELEVATION                       |  |  |  |
|                                  | CONCRETE SIDEWALK                            |  |  |  |
| $\longrightarrow$                | GRADED DIRECTION FOR<br>DRAINAGE FLOW        |  |  |  |
| $\rightarrow \cdots \rightarrow$ | SWALE  |  |  |  |
|                                  | SLOPE  |  |  |  |
| $\bigotimes$                     | TREE TO BE REMOVED                           |  |  |  |
|                                  | RETAINING WALL                               |  |  |  |
| ROPOSED SANITARY                 | SEWER SYMBOLS:                               |  |  |  |
| 6" SS                            | SANITARY SEWER LINE<br>(SIZE AND FLOW SHOWN) |  |  |  |
| •                                | SANITARY SEWER<br>MANHOLE (SSMH)             |  |  |  |
| <b></b> CO                       | SEWER CLEANOUT<br>FLUSHER BRANCH             |  |  |  |
| ROPOSED WATER SY                 | MBOLS:                                       |  |  |  |
| 8" W                             | WATER LINE & SIZE                            |  |  |  |
| 8" FS                            | FIRE LINE & SIZE                             |  |  |  |
| [8" DW                           | DOMESTIC WATER LINE & SIZE                   |  |  |  |
| [8" RW]                          | RECLAIMED WATER LINE & SIZE                  |  |  |  |
| 8" IRR                           | IRRIGATION SERVICE LINE & SIZE               |  |  |  |
| 8"NP                             | NON POTABLE WATER LINE & SIZE                |  |  |  |
| 8" SP                            | FIRE SPRINKLER SERVICE LINE & SIZE           |  |  |  |
| →                                | GATE VALVE                                   |  |  |  |
| M                                | WATER METER                                  |  |  |  |
| FH                               | FIRE HYDRANT ASSEMBLY                        |  |  |  |
| Y FDC<br>DC                      | FIRE DEPARTMENT CONNECTION                   |  |  |  |
|                                  | DETECTOR CHECK VALVE                         |  |  |  |
| RP                               | DOUBLE DETECTOR CHECK VALVE                  |  |  |  |
|                                  | REDUCED PRESSURE<br>BACKFLOW PREVENTER       |  |  |  |
|                                  | BUTTERFLY VALVE                              |  |  |  |
| <b>↓</b> 1"                      | AIR RELEASE VALVE + SIZE                     |  |  |  |

BLOW-OFF VALVE + SIZE

POST INDICATOR VALVE

PIV

## **DEMOLITION GENERAL NOTES**

- SHALL BE IMMEDIATELY NOTIFIED FOR DIRECTIONS.
- 2. NO BURNING OR BLASTING SHALL BE PERMITTED. ADDITIONAL DEMOLITION INFORMATION MAY BE SHOWN ON THE
- PREPARED BY OTHER DISCIPLINES FOR THIS PROJECT. 4. ALL DEMOLISHED ITEMS SHALL BE DISPOSED OF OFFSITE AT A
- SUITABLE, LEGAL, DUMP SITE OR OTHER FACILITY. 5. ALL DISPOSED OF MATERIALS SHALL BE RECYCLED IF POSSIBLE.
- 6. THE TYPES, LOCATIONS, SIZES AND/OR DEPTHS OF EXISTING EFFORT HAS BEEN MADE TO LOCATE AND DELINEATE ALL KNOWN UNDERGROUND UTILITIES. HOWEVER, WARREN CONSULTING ENGINEERS CAN
- EXTEND.
- NOTED OTHERWISE.
- FROM DAMAGE DURING CONSTRUCTION.
- TO BE REMOVED SHALL REMAIN AND BE PROTECTED.

UTILITY VERIFICATION NOTE PRIOR TO THE START OF CONSTRUCTION, VERIFY AND POTHOLE ALL UTILITY POINTS OF CONNECTION FOR LOCATION, DEPTH, AND SIZE. IF CONFLICT IS FOUND, CONTACT THE ENGINEER IMMEDIATELY FOR DIRECTION.

IRRIGATION DEMOLITION NOTE WITHIN LANDSCAPE AREAS TO BE DEMOLISHED THERE MAY BE EXISTING IRRIGATION LINES NOT SHOWN ON THIS PLAN. CONTRACTOR SHALL REMOVE LATERAL LINES AND HEADS ENCOUNTERED. MAIN LINES AND CONTROL WIRES MAY ONLY BE REMOVED PROVIDED THAT ROUTING IS KNOWN AND REMOVAL WILL NOT DEACTIVATE AN IRRIGATION SYSTEMS INTENDED TO REMAIN. IF CONFLICT IS FOUND, CONTACT THE ENGINEER FOR DIRECTION.

IN THE EVENT THAT ANY UNUSUAL CONDITIONS NOT COVERED BY THE GEOTECHNICAL INVESTIGATION REPORT OR ARE ENCOUNTERED DURING GRADING OPERATIONS THE GEOTECHNICAL ENGINEER AND THE ARCHITECT

# GRADING, DRAINAGE, AND UTILITY PLANS, AND THOSE PLANS

UNDERGROUND UTILITIES AS SHOWN IN THESE PLANS WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. THE CONTRACTOR IS CAUTIONED THAT ONLY ACTUAL EXCAVATION WILL REVEAL THE TYPES, EXTENT, SIZES, LOCATIONS, AND DEPTHS OF SUCH UNDERGROUND UTILITIES. A REASONABLE

ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF ITS DELINEATION OF SUCH UNDERGROUND UTILITIES, NOR FOR THE EXISTENCE OF OTHER BURIED OBJECTS OR UTILITIES WHICH MAY BE ENCOUNTERED BUT WHICH ARE NOT SHOWN ON THESE DRAWINGS. THE CONTRACTOR OR ANY SUBCONTRACTOR FOR THIS CONTRACT SHALL NOTIFY THE DISTRICT TWO (2) WORKING DAYS IN ADVANCE OF PERFORMING ANY EXCAVATION WORK IN ORDER TO VERIFY TO THE GREATEST EXTENT POSSIBLE THE EXISTING UTILITY LINES, CONFLICTS AND PROPOSED UTILITY CONNECTION POINTS.

7. THE SCHOOL DISTRICT SHALL HAVE SALVAGE RIGHTS TO ANY DEMOLISHED ITEMS SHOWN HEREON. THE CONTRACTOR SHALL GIVE THE DISTRICT NOTICE 7 DAYS PRIOR TO THE START OF DEMOLITION. THE DISTRICT SHALL MOVE ANY RETAINED ITEMS OUT OF THE CONTRACTORS WORK AREA, UNLESS ANOTHER ARRANGEMENT IS MADE WITH THE CONTRACTOR. ANY REMAINING ITEMS BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE. ANY ITEMS NOT SHOWN FOR REMOVAL SHALL REMAIN AND SHALL BE PROTECTED FROM DAMAGE DURING CONSTRUCTION TO A REASONABLE

8. EXISTING UTILITY STRUCTURES IN AREAS OF NEW PAVING SHALL BE REMOVED AND REPLACED WITH NEW BOX/COVER AT NEW GRADE UNLESS SPECIFICALLY

9. ITEMS OUTSIDE THE LIMITS OF DEMOLITION SHALL REMAIN AND BE PROTECTED

10. EXISTING UTILITY STRUCTURES AND PIPING NOT SHOWN ON DEMOLITION PLAN

1. THE TYPES, LOCATIONS, SIZES, AND/OR DEPTHS OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THESE PLANS WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. THE CONTRACTOR IS CAUTIONED THAT ONLY ACTUAL EXCAVATION WILL REVEAL THE TYPES, EXTENT, SIZES, LOCATIONS AND DEPTHS OF SUCH UNDERGROUND UTILITIES. A REASONABLE EFFORT HAS BEEN MADE TO LOCATE AND DELINEATE ALL KNOWN UNDERGROUND UTILITIES. HOWEVER, WARREN CONSULTING ENGINEERS CAN ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF ITS DELINEATION OF SUCH UNDERGROUND UTILITIES, NOR FOR THE EXISTENCE OF OTHER BURIED OBJECTS OR UTILITIES WHICH MAY BE ENCOUNTERED BUT WHICH ARE NOT SHOWN ON THESE PLANS. THE CONTRACTOR OR ANY SUBCONTRACTOR FOR THIS CONTRACT SHALL NOTIFY MEMBERS OF UNDERGROUND SERVICE ALERT (USA) TWO (2) WORKING DAYS IN ADVANCE OF PERFORMING ANY EXCAVATION WORK BY CALLING TOLL FREE 1-800-227-2600, OR 811.



- 2. WARREN CONSULTING ENGINEERS, INC. (WCE) ASSUMES NO RESPONSIBILITY FOR ERRORS IN PHYSICAL LOCATION OF IMPROVEMENTS, HORIZONTAL OR VERTICAL, IF STAKED BY OTHERS. IN ADDITION, ANY SUCH ERRORS IN PHYSICAL LOCATION MAY AFFECT THE INTENDED DESIGN OF SUCH IMPROVEMENTS AND WCE CANNOT BE HELD RESPONSIBLE FOR SUCH CONDITIONS WHICH ARE A RESULT OF ERRORS IN SURVEYING, OR IMPROPER CONSTRUCTION.
- 3. IF SUBSURFACE CULTURAL RESOURCES, REMAINS, AND/OR ARTIFACTS ARE UNCOVERED DURING PROJECT CONSTRUCTION, ALL WORK IN THE VICINITY SHALL BE STOPPED UNTIL SUCH ITEMS CAN BE ASSESSED BY AN APPROPRIATE MEMBER OF THE COUNTY ENVIRONMENTAL IMPACT SECTION STAFF.
- 4. CONTRACTOR AGREES THAT HE/SHE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY: THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND SHALL NOT BE LIMITED TO NORMAL WORKING HOURS: AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER AND ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.
- 5. THE CONTRACTOR SHALL OBTAIN AN EXCAVATION PERMIT FROM THE STATE OF CALIFORNIA DEPARTMENT OF INDUSTRIAL SAFETY FOR ALL EXCAVATIONS OF 5 FEET OR MORE IN DEPTH.
- 6. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO MAKE ALL NECESSARY PRE-BID AND PRE-CONSTRUCTION SITE INSPECTION, AND/OR OBSERVATIONS ON THE SITE TO PRE-DETERMINE ALL HIS/HER MEANS AND METHODS NECESSARY TO COMPLETE THE IMPROVEMENTS SHOWN ON THESE PLANS AND PER THE PROJECT SPECIFICATIONS. IT IS THE CONTRACTORS RESPONSIBILITY TO DETERMINE, AND INCLUDE IN HIS/HER CONTRACT, ALL MEANS AND METHODS NECESSARY TO PERFORM A COMPLETE AND ACCEPTABLE JOB.
- 7. WHERE IMPROVEMENTS LIE WITHIN AN EXISTING DEVELOPED AREA, CONTRACTOR SHALL USE CAUTION WHEN ACCESSING THE SITE THROUGH THESE EXISTING IMPROVEMENTS. IT IS THE CONTRACTORS RESPONSIBILITY TO PROTECT ANY SUCH EXISTING IMPROVEMENTS OUTSIDE THE PROJECT BOUNDARY, OR EXISTING IMPROVEMENTS WITHIN THE BOUNDARY WHICH ARE TO REMAIN. PROPER PRECAUTIONS SHALL BE PROVIDED AND MAINTAINED THROUGHOUT CONSTRUCTION. ANY DAMAGE SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE OWNER.
- 8. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO KEEP DETAILED RECORDS OF MINOR CHANGES OR ADJUSTMENTS MADE DURING CONSTRUCTION (WHICH WERE NOT FORMALLY ISSUED). UPON PROJECT COMPLETION, THESE RECORDS AND/OR INFORMATION SHALL BE PROVIDED TO THE OWNER AND WARREN CONSULTING ENGINEERS, INC. UNLESS AN OFFICIAL "AS-BUILT" SET OF PLANS IS A REQUIREMENT OF THE CONTRACT. IF AS-BUILT PLANS ARE A REQUIREMENT OF THE CONTRACT, REFER TO SPECIFICATIONS FOR AS-BUILT DELIVERABLE REQUIREMENTS.
- 9. IN VEHICULAR PATHWAYS, EXISTING ASPHALTIC AND/OR CONCRETE SURFACES SHALL BE CUT TO A NEAT AND STRAIGHT LINE, PARALLEL OR PERPENDICULAR TO THE VEHICULAR TRAVELED PATH. THIS IS TYPICALLY THE ROADWAY CENTERLINE, BUT MAY VARY. THAT SAWCUT EDGE SHALL BE PROTECTED FROM DAMAGE DURING CONSTRUCTION SO A CLEAN EDGE REMAINS FOR PATCH BACK .. IF EDGE IS DAMAGED, A NEW SAW CUT WILL BE REQUIRED. THE EXPOSED EDGE SHALL BE "TACKED" WITH EMULSION PRIOR TO PAVING.
- 10. NO BURNING OR BLASTING SHALL BE ALLOWED ONSITE UNLESS SPECIFICALLY ADDRESSED ON PLANS, OR SPECIFICALLY APPROVED AND COORDINATED WITH THE ARCHITECT, ENGINEER, AND LOCAL AGENCY OR OTHER ADMINISTRATIVE AUTHORITY.
- 11. SUBGRADE AND RESULTING FINISHED GRADE SHALL BE CONSTRUCTED SMOOTH AND UNIFORM BETWEEN SPOT ELEVATIONS, CONTOURS OR OTHER STRUCTURE ELEVATIONS SHOWN ON GRADING OR OTHER PLANS. NO MOUNDS, RUTS, DEPRESSIONS OR OTHER GRADING DEFICIENCIES WILL BE ALLOWED UNLESS SPECIFICALLY SHOWN ON PLANS.
- 12. ON NEW WATER SYSTEMS, SERVICE LATERALS SHALL BE MADE USING APPROPRIATE "TEE" AND "WYE" FITTINGS. SADDLE TAPS WILL ONLY BE ALLOWED WHEN MAKING CONNECTIONS TO EXISTING WATER MAINS.
- 13. CURING COMPOUND SHALL BE APPLIED IN A CONTINUOUS SOLID WET FLOWING COAT. ANY "SPOTTY" APPLICATIONS SHALL BE RECOATED IMMEDIATELY. APPLICATION SHALL BE INSPECTED BY PROJECT INSPECTOR DURING APPLICATION.
- 14. EMBEDMENT OF FEATURES IN CONCRETE PAVING, CURBS, OR WALLS, SUCH AS SQUARE OR ROUND TUBING, POSTS, OR COLUMNS, STEEL BOLTED PLATES, OR OTHER STRUCTURES, SHALL REQUIRE ADDITIONAL SCORE OR EXPANSION JOINTS TO PREVENT UNCONTROLLED CRACKING. THOSE ADDITIONAL JOINTS MAY OR MAY NOT BE SPECIFICALLY SHOWN ON PLANS BUT SHALL BE PROVIDED BY THE CONTRACTOR.
- 15. EMBEDMENT OF FEATURES IN CONCRETE PAVING, CURBS, OR WALLS, SUCH AS SQUARE OR ROUND TUBING, POSTS, OR COLUMNS, STEEL BOLTED PLATES, OR OTHER STRUCTURES, SHALL REQUIRE A MINOR ADJUSTMENT OF REBAR WITHIN CONCRETE TO ALLOW FOR SUCH STRUCTURE. THAT REBAR ADJUSTMENT MAY NOT BE SPECIFICALLY SHOWN ON PLANS. 16. NO MORE THAN 1 GALLON OF WATER PER YARD OF CONCRETE CAN BE ADDED TO THE TRUCK AFTER ARRIVAL TO
- PROJECT SITE. THE ADDITION OF WATER CAN ONLY BE ADDED UNDER THE SUPERVISION OF THE CONCRETE INSPECTOR OR LABORATORY TECHNICIAN. 17. WHEN PUMPING CONCRETE FOR PLACEMENT, ABSOLUTELY NO WATER IS TO BE ADDED TO PUMP HOPPER. ANY
- WATER ADDED TO HOPPER WILL BE REASON FOR CONCRETE REJECTION AT THE CONTRACTORS EXPENSE. 18. ALL CONTRACTION/CONSTRUCTION JOINTS "CJ" SHALL BE 1/4 THE SLAB THICKNESS DEEP, BUT NO LESS THAN 1" FOR CONTROLLING OF CRACKING. CONTRACTOR SHALL EXERCISE CAUTION WHEN FINAL TROWELING OF CONCRETE SO AS NOT TO FILL IN THESE JOINTS WITH CONCRETE CREAM. ANY CRACKS OUTSIDE OF JOINTS WHICH WERE CONSTRUCTED LESS THAN 1" DEEP, SHALL BE CAUSE FOR CONCRETE SLAB(S) TO BE REMOVED AND REPLACE AT
- CONTRACTORS EXPENSE. 19. ANY SCREED BOARDS SET WITHIN CONCRETE SLABS SHALL BE AN "OVERHEAD SCREED" SO THERE IS NO
- INTERFERENCE WITH THE PLACEMENT AND ALIGNMENT OF SLAB REINFORCING. 20. 3-1/2" FELT JOINTS WILL NOT BE ACCEPTED. PROVIDE A FULL 4" FELT JOINT FOR 4" SLAB CONSTRUCTION, AND
- 21. SHOULD ANY SHRINKAGE CRACKS OCCUR OUTSIDE OF EITHER THE EXPANSION JOINTS OR CRACK CONTROL JOINTS, THEN THE CONCRETE SLAB SHALL BE SAWCUT AT THE NEAREST JOINTS ON EACH SIDE OF THE CRACK AND THE CONCRETE SECTION SHALL BE, REMOVED AND REPLACED. NEW CONCRETE SHALL BE DOWELED INTO EXISTING CONCRETE PER DRAWING DETAIL.
- 22. ALL AREAS DISTURBED BY GRADING OPERATIONS WHETHER SHOWN ON THE DRAWINGS OR NOT SHALL BE HYDRO SEEDED UNLESS OTHERWISE NOTED. HYDRO SEEDING SHALL CONFORM TO LOCAL CITY/COUNTY STANDARDS.
- 23. REPAIR OR PATCHING OF GALVANIZED METALS, SUCH AS AFTER WELDING GALVANIZED COMPONENTS, SHALL BE MADE USING A ZINC COMPOSITION "HOT STICK" APPLICATION PER ASTM A 780-01. GALVANIZING PAINTS WILL NOT BE ALLOWED.

# **GENERAL PAVING SURFACE NOTES:**

A 6" FELT JOINT FOR A 6" SLAB SLAB CONSTRUCTION.

- 1. PROVIDE EQUIVALENT OF MEDIUM BROOM FINISH AT SLOPES UP TO 5.99%, TYPICAL. PROVIDE EQUIVALENT OF HEAVY BROOM FINISH AT SLOPES 6% AND GREATER. REFER TO SPECIFICATIONS.
- 2. ALL NEW PEDESTRIAN WALKWAYS (NON-RAMP) SHALL BE SLOPED NO GREATER THAN 2.0%, AND NO LESS THAN 0.75% IN ANY DIRECTION, UNLESS SPECIFICALLY LABELED OTHERWISE. ALL CONCRETE SHALL MEET THE FOLLOWING SLOPE REQUIREMENTS: - NO GREATER THAN 5% SLOPE IN THE DIRECTION OF TRAVEL.
- NO GREATER THAN 2% SLOPE CROSSING THE DIRECTION OF TRAVEL. - NO GREATER THAN 2% SLOPE IN ANY DIRECTION IN COURTYARD OR PLAZA AREAS.


## CIVIL SHEET INDEX


- CO.1 CIVIL GENERAL NOTES AND ABBREVIATIONS
- C1.1 DEMOLITION PLAN
- C2.1 GRADING, DRAINAGE AND PAVING PLAN
- C3.1 DETAILS AND SECTIONS

 $\sqrt{0}$ 


LANDSCAPE/IRRIGATION NOTE:

GENERAL CONTRACTOR IS REQUIRED TO HIRE A LANDSCAPE SUBCONTRACTOR TO PERFORM ALL LANDSCAPE AND IRRIGATION REPAIRS.







|                                   | $\bigcirc$ | DEMOLITION NOTES  |
|-----------------------------------|------------|---|
|                                   | 1.         | SAWCUT, REMOVE AND DISPOSE OF EXISTING CONCRETE<br>PAVING AND ASSOCIATED AGGREGATE BASE. SAWCUT SHALL<br>BE A NEAT STRAIGHT LINE, MAINTAIN CLEAN, STRAIGHT CUT<br>EDGE UNTIL NEW PAVING IS PLACED.  |
|                                   | 2.         | SAWCUT, REMOVE AND DISPOSE OF EXISTING ASPHALT<br>PAVING AND ASSOCIATED AGGREGATE BASE. SAWCUT SHALL<br>BE A NEAT STRAIGHT LINE, MAINTAIN CLEAN, STRAIGHT CUT<br>EDGE UNTIL NEW PAVING IS PLACED.   |
| $\times$                          | 3.         | REMOVE AND DISPOSE OF EXISTING TREE, TRUNK AND ASSOCIATED ROOTS.  |
| ₩ — ₩ — ¶<br>  ₩ ₩ ₩  <br>₩ _ ₩ _ | 4.         | REMOVE AND DISPOSE OF EXISTING LANDSCAPING, TURF AND<br>ASSOCIATED IRRIGATION PIPING/SPRINKLERS WITHIN AREAS<br>OF WORK. CUT AND CAP ANY MAINLINES NEAR WHERE THEY<br>ENTER THE BOUNDARY OF THE PROJECT. MARK ALL CAPPED<br>LINES WITH AN IRRIGATION VALVE BOX. ALL EXISTING<br>IRRIGATION AREAS OUTSIDE THE PROJECT WORK AREA<br>SHALL BE PRESERVED AND OPERATIONAL. INTEGRITY SHALL<br>BE MAINTAINED WITH PROPER SPRINKLER COVERAGE TO<br>TURF AREAS TO REMAIN. |
|                                   | 5.         | REMOVE AND DISPOSE OF EXISTING CONCRETE PAD AND BENCH.  |
|                                   | 6.         | REMOVE AND DISPOSE OF EXISTING CONCRETE CURB TO EXTENT SHOWN.   |
|                                   | 7.         | REMOVE AND DISPOSE OF EXISTING CHAIN LINK FENCE TO EXTENT SHOWN.  |
|                                   | 8.         | REMOVE AND DISPOSE OF EXISTING BACKSTOP.  |
|                                   | 9.         | REMOVE AND DISPOSE OF EXISTING CONCRETE VALLEY<br>GUTTER TO EXTENT SHOWN.   |
| {                                 | 10.        | REMOVE AND DISPOSE OF EXISTING WATER PIPE TO EXTENT SHOWN.  |
|                                   | $\sim$     |   |










|              | SU         | IBGRADE PREPARATION  |
|--------------|------------|--|
|              | 1.         | FOLLOWING SITE DEMOLITION ACTIVITIES:  |
|              |            | EXCAVATE DOWN TO ROUGH SUBGRADE ELEVATION, SCARIFY THE<br>EXISTING SOILS TO A MINIMUM DEPTH OF 12 INCHES, MOISTURE<br>CONDITION TO AT LEAST 2 PERCENT ABOVE THE OPTIMUM<br>MOISTURE AND COMPACT TO AT LEAST 90 PERCENT OF THE<br>MAXIMUM DRY DENSITY DETERMINED BY THE ASTM D1557 TEST<br>METHOD. UPPER 12 INCHES OF SUBGRADE SUPPORTING ASPHALT<br>PAVEMENT SHALL BE COMPACTED TO 95 PERCENT. |
| (            | $\bigcirc$ | CONSTRUCTION NOTES   |
|              | 1.         | MATCH EXISTING GRADE/ELEVATION.  |
|              | 2.         | CONSTRUCT CONCRETE SIDEWALK PER<br>PLACE 5"PCC WITH #4 REBAR AT 24" O.C.E.W.<br>OVER 12" CL2 AGGREGATE BASE ON COMPACTED<br>SUBGRADE.  |
|              | 3.         | CONSTRUCT CONCRETE SIDEWALK PER<br>PLACE 6"PCC WITH #4 REBAR AT 24" O.C.E.W.<br>OVER 16" CL2 AGGREGATE BASE ON COMPACTED<br>SUBGRADE.  |
|              | 4.         | DOWEL INTO EXISTING CONCRETE PER $\begin{pmatrix} 1 \\ C3.1 \end{pmatrix}$   |
|              | 5.         | PLACE 3"AC OVER 16"AB ON COMPACTED SUBGRADE.   |
| *******      | 6.         | CONSTRUCT CONCRETE CURB PER $\begin{pmatrix} 2 \\ C3.1 \end{pmatrix}$  |
| ✓ ↓<br>↓ ∖   | 7.         | PLACE SOD IN ALL AREAS DISTURBED BY CONSTRUCTION<br>ACTIVITIES THAT ARE NOT TO RECEIVE PAVEMENT. PROVIDE<br>NEW SPRINKLER HEADS AND PIPING AS REQUIRED TO ACHIEVE<br>PROPER COVERAGE.  |
|              | 8.         | PLACE 6" STORM DRAIN PER $\begin{pmatrix} 3 \\ C3.1 \end{pmatrix}$   |
|              | 9.         | CONSTRUCT DROP INLET PER $(4)$ (C3.1)  |
|              | 10.        | CONNECT TO EXISTING STORM DRAIN. PROVIDE ALL FITTINGS NECESSARY TO MAKE CONNECTION.  |
|              | 11.        | REFER TO ELECTRICAL PLANS FOR CONDUIT PLACEMENT AND 5<br>DETAILING. PATCH BACK PAVING PER DETAIL   |
|              | 12.        | CONSTRUCT CONCRETE VALLEY GUTTER PER   |
|              | 13.        | CONSTRUCT FLUSH CONCRETE CURB PER $\begin{pmatrix} 9 \\ C3.1 \end{pmatrix}$  |
|              | 14.        | CONSTRUCT AREA DRAIN PER $\begin{pmatrix} 8 \\ C3.1 \end{pmatrix}$   |
| <pre>{</pre> | 15.        | PLACE IRRIGATION/WATER PIPE. SIZE TO MATCH C3.1  |
| ł            | 16.        | CONNECT TO EXISTING WATER PIPE. PROVIDE ALL FITTINGS   |
|              | 17.        | PLACE 2-SACK CONCRETE SLURRY FROM TOP OF EXISTING<br>ELECTRICAL CONDUIT TO 6" MIN. ABOVE PIPE, EXTENDING 6"<br>ON EITHER SIDE OF PIPE.   |
|              | 18.        | CONSTRUCT TRASH ENCLOSURE WALL PER   |








| * / /   |
|---|
|   |
|   |
|   |
|   |
| 5 /   |
|   |
|   |
|   |
| NSED ARCU   |
| CERREY ALAW PLEA  |
| ★ C-14648 ★   |
| 5/31/23<br>RENEWAL<br>DATE<br>OF<br>CALLE   |
| STATE<br>THE CONTRACT<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE<br>STATE |
|   |
|   |
| ALARGED PLAN A1.1.1 DATE: 04/29/22<br>ADE STRUCTURE AT SEQUOIA ELEMENTARY PROJECT 21 1504 05  |
| ADE STRUCTURE AT SEQUOIA ELEMENTARY<br>HOOL<br>CRAMENTO CITY UNIFIED SCHOOL DISTRICT SHEET:   |
| CRAMENTO, CA<br>A APP.02-119975 AD0.04  |
|   |
|   |





- **SHEET NOTES:** 1. ALL EXISTING EQUIPMENT, DEVICES, CONDUIT AND WIRING, ETC., SHOWN ON PLANS ARE BASED ON AVAILABLE EXISTING DRAWINGS AND LIMITED
- SITE SURVEYS, AND SHOWN FOR CLARITY ONLY. 2. SEE ONE LINE DIAGRAM AND PANEL SCHEDULE ON SHEET <u>E2.1</u> FOR REFERENCE.


- **KEYED NOTES:** PROVIDE TRENCH FOR 24 INCH MINIMUM COVER. LOCATE AND PROTECT (E) UTILITIES, I.E. IRRIGATION, SEWER, DRAINAGE PIPES, ETC. SAW CUT AND PATCH BACK (E) ASPHALT. PROVIDE SAND TO COVER CONDUIT TO SIX(6) INCHES, THEN ADD TRACER TAPE. COMPLETE BACKFILL TO GRADE, COMPACTING IN SIX(6)-INCH LIFTS. FINISH TO MATCH EXISTING. SEE DETAIL
- 2 CONDUIT TO PENETRATE WALL. PATCH BACK TO MATCH (E) BUILDING CONSTRUCTION.
- 3 PENETRATE WALL AND RUN HIGH ON WALL TO WRAP AROUND SOUTHEAST ALCOVE. PENETRATE WALL AND DROP CONDUIT TO BELOW CONCRETE/ASPHALT. TRENCH TO SHADE LOCATION, INTERCEPTING THE CHRISTY BOX ALONG THE WAY. PAINT EXPOSED CONDUIT TO MATCH (E) FINISH.
- FINISH.
   PROVIDE AT MINIMUM TWO(2) GROUND RODS, ONE AT THE PULL BOX AND ONE NEAR THE CORNER POST OF THE SHADE STRUCTURE, EACH 5/8" BY TEN(10) FEET LONG, CU, AT LEAST TEN(10) FEET APART. BOND TO METAL OF SHADE STRUCTURE. SEE DETAILS <u>5/E3.1</u> AND <u>2/E3.1</u>.
   LOCKABLE, WEATHERPROOF RECEPTACLE TO HAVE A TWO-GANG BACK BOX WITH 1" THREADED PORT(S). MOUNT RECEPTACLES 36" ABOVE GRADE UNLESS SPECIFIED OTHERWISE. SEE DETAIL <u>4/E3.1</u>.
- 6 PROVIDE 8" BY 6" BY 4" NEMA 3R PULL BOX.
- 7 PROVIDE CHRISTY B1324 PULL BOX WITHIN FIVE(5) FT OF SHADE STRUCTURE. CHRISTY BOX TO HAVE HOLD DOWN BOLTS AND BE LABELED FOR POWER. B RUN CONDUIT BELOW SHADE STRUCTURE CONCRETE PAD.
- 5 SAW CUT AND PATCH BACK (E) CONCRETE AS REQUIRED FOR TRENCHING.

















# **Statement of General Conformance**

THE FOLLOWING DRAWINGS OR SHEETS LISTED ON THE COVER OR INDEX SHEET HAVE BEEN PREPARED BY OTHER DESIGN PROFESSIONALS OR CONSULTANTS WHO ARE LICENSED AND/OR AUTHORIZED TO PREPARE SUCH DRAWINGS IN THIS STATE. IT HAS BEEN EXAMINED BY ME FOR:

1) DESIGN INTENT AND APPEARS TO MEET THE APPROPRIATE REQUIREMENTS OF TITLE 24, CALIFORNIA CODE OF REGULATIONS AND THE PROJECT SPECIFICATIONS PREPARED BY ME, AND

2) COORDINATION WITH MY PLANS AND SPECIFICATIONS AND IS ACCEPTABLE FOR INCORPORATION INTO THE CONSTRUCTION OF THIS PROJECT.

THE STATEMENT OF GENERAL CONFORMANCE "SHALL NOT BE CONSTRUED AS RELIEVING ME OF MY RIGHTS, DUTIES, AND RESPONSIBILITIES UNDER SECTIONS 17302 AND 81138 OF THE EDUCATION CODE AND SECTIONS 4-336, 4-341, AND 4-344" OF TITLE 24, PART 1. (TITLE 24, PART 1, SECTION 4-317 (b))

NQ

4/21/22

SIGNATURE

DATE

ARCHITECT OR ENGINEER DESIGNATED TO BE IN GENERAL RESPONSIBLE CHARGE

Jeffrey Grau

PRINT NAME

C-14648 05/31/23

LICENSE NUMBER EXPIRATION DATE

LIST COMPLETELY, ITEMS REVIEWED AND ACCEPTED:

PC SHADE STRUCTURE

| DESIGN CRITERIA   |   |
|---|---|
| DESCRIPTION   | DESIGN VALUES                                 |
| DEAD AND LIVE LOADS   |   |
| ROOF LIVE LOAD  | 20 PSF  |
| ROOF DEAD LOAD (SUPERIMPOSED ON FRAME)  | 5 PSF MAX                                     |
| ROOF PANEL DEAD LOAD  | M=1.1 PSF, G = 1.2 PSF, S = 1.3 PSF           |
| COLLATERAL DEAD LOAD  | M = 3.9 PSF, G = 3.8 PSF, S = 3.7 PSF         |
| ROOF SNOW LOAD  |   |
| GROUND SNOW LOAD, Pg  | 20 PSF  |
| RISK CATEGORY   |   |
|   | 20 PSF  |
| SITE APPLICATION DSA REVIEWER SHALL VERIFY THE STRUCTURE BE LOCATED   |   |
| SNOW LOAD SLOPE FACTOR, C <sub>s</sub>  | 1.0   |
| SNOW EXPOSURE FACTOR, C <sub>e</sub>  | 1.0   |
| SNOW LOAD IMPORTANCE FACTOR, $I_s$  | 1.0   |
| THERMAL FACTOR, Ct  | 1.2   |
| WIND DESIGN   |   |
| BASIC WIND SPEED (3 SECOND GUST), V <sub>ult</sub>  | 100 MPH                                       |
| RISK CATEGORY   | II  |
| EXPOSURE CATEGORY   | С   |
| FACTORS: Kz, Kzt, Kd  | 0.85, 1, 0.85                                 |
| q <sub>h</sub> = 0.00256 K <sub>z</sub> K <sub>zt</sub> K <sub>d</sub> V <sup>2</sup> FOR ALL EAVE HEIGHTS (8', 10' & 12')      | 18.50 PSF                                     |
| C <sub>NW</sub> PER ASCE FIGURE 27.4-5 ROOF ANGLE 18.43 - CLEAR / OBSTRUCTED  | CASE A (1.1 / -1.2) CASE B (0.01 / -0.69)     |
| C <sub>NL</sub> PER ASCE FIGURE 27.4-5 ROOF ANGLE 18.43 - CLEAR / OBSTRUCTED  | CASE A (-0.17 / -1.09) CASE B (-0.96 / -1.65) |
|   |   |
| C <sub>N</sub> PER ASCE FIGURE 27.4-7 PARALLEL TO RIDGE - CLEAR / OBSTRUCTED  | CASE A (-0.6 / -0.9) CASE B (-0.5 / -0.5)     |
| COMPONENTS & CLADDING - $C_N$ ( PRESSURE/SUCTION) CLEAR / OBSTRUCTED  | ZONE 3 - (2.29 / -2.11) / (1.0 / -3.0)        |
|   | ZONE 2 - (1.77 / -1.63) / (0.8 / -2.3)        |
| SEISMIC DESIGN  | ZONE 1 - (1.15 / -1.05) / (0.5 / -1.5)        |
| LATERAL FORCE RESISTING SYSTEM  | STEEL - ORDINARY CANTILEVER COLUMN            |
| ANALYSIS PROCEDURE  | EQUIVALENT LATERAL FORCE                      |
| SESIMIC IMORTANCE FACTOR, le  | 1.0   |
| SEISMIC SITE CLASS  | D   |
| MCE <sub>R</sub> SPECTRAL RESPONSE ACCELERATION @ 0.2 s, S <sub>S</sub>   | 2.60  |
| MCE <sub>R</sub> SPECTRAL RESPONSE ACCELERATION @ 0.2 s, S <sub>1</sub>   | 0.90  |
| SHORT PERIOD SITE COEFFICIENT, Fa   | 1.20  |
| LONG PERIOD COEFFICIENT, $F_v$  | 1.70  |
| FUNDAMENTAL PERIOD OF THE STRUCTURE, T  | 0.152 s                                       |
| FUNDAMENTAL FERIOD OF THE STRUCTURE, I  | 0.152 S                                       |
| DESIGN SPECTRAL RESPONSE ACCELERATION AT SHORT PERIOD, $S_{DS}$   | 2.08  |
| DESIGN SPECTRAL RESPONSE ACCELERATION AT SHORT PERIOD, S <sub>DS</sub> - USED<br>TO DETERMINE Cs (WITH CAP PER ASCE-7 12.8.1.3) | 2.08 * 0.70 = 1.456                           |
|   | 100   |
| DESIGN SPECTRAL RESPONSE ACCELERATION AT 1-S PERIODS, Sp1   | 1.02  |
| SEISMIC DESIGN CATEGORY   | E 125   |
| RESPONSE MODIFICATION FACTOR, R<br>OVERSTRENGTH FACTOR, Ω   | 1.25  |
| REDUNDANCY FACTOR, $\rho$   | 1.25  |
| HORIZONTAL OR VERTICAL IRREGULARITIES   | NONE  |
| SEISMIC RESPONSE COEFFICIENT, Cs (20' WIDE, 30' WIDE, 40' WIDE)   | 1.16,   |
| DESIGN BASE SHEAR, V (20' WIDE, 30' WIDE, 40' WIDE)   | 12.73 PSF, 13.41 PSF, 14.65 PSF               |
| ALLOWABLE SOIL BEARING FOR FOUNDATIONS  | VARIES - SEE FOUNDATION CHARTS                |
|   |   |
| FLOOD DESIGN - DESIGN IS ASSUMED TO NOT BE IN FLOOD HAZARD AREA   |   |
| IF PROJECT IS LOCATED IN A FLOOD ZONE OTHERTHAN ZONE X, A LETTER  |   |

STRUCTURAL SEPARATION

ALLOWABLE SOIL VALUES SPECIFIED

| ALL DEFLECTIONS SHOWN ALSO INCLUDE THE P-D   | DELTA ROTATION PER IR PC-7 |              | TIONS ARE FOR (1) STI<br>- CLASSES PER CBC TABLE 18 |                 |
|--|----------------------------|--------------|---|-----------------|
| MAXIMUM DRIFT $\delta_{max}$ SIDE COLUMNS  |                            | Soil Class 5 | <u>Soil Class 4</u>                                 | <u>Soil Cla</u> |
| 20' WIDE (O'EAVE HT, 10'EAVE HEIGHT, 12'EAVE HT)   | (INCHES)                   | 2.40         | 2.55  | 2.6             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                   | 2.25         | 2.35  | 2.4             |
| 18' WIDE (6' EAVE HT, 18' EAVE HEIGHT, 12' EAVE HT) MINIMUM SEPARATION ( $\delta_m = C_d  \delta_{max}$ ) $C_d = 1.25$   | (INOHEO)                   | 2.20         | 2.25  | 2.2             |
| 20 WIDE (O'EAVE HT, 10'EAVE HEIGHT, 12'EAVE HT)-   | (INCHES)                   | 3.00         | 3.19  | 3.3             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                   | 2.81         | 2.94  | 3.0             |
| 40 WIDE (8 EAVE HT, 10 EAVE HEIGHT, 12 EAVE HT)  | (INCHES)                   | 2.75         | 2.81  | 2.7             |
| MAXIMUM DRIFT $\delta_{max}$ CORNER COLUMNS  |                            | Soil Class 5 | Soi Class 4   | <u>Sol Cla</u>  |
| 20' WIDE (O' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)-   | (INOHEO)                   | 2.20         | 2.30  | 2.4             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                   | 2.30         | <b>4</b> 4  | 2.5             |
| 10' WIDE (0' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)<br>MINIMUM SEPARATION ( $\delta_m = C_d \delta_{max}$ ) $C_d = 1.25$ | (INOHEO)                   | 2.10         | 245   | 1.6             |
| 20' WIDE (O' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)-   | (INCHES)                   | 2.75         | 248   | 3.              |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                   | 2.88         | <u>1</u> .06  | 3.              |
| 48' WIDE (8' EAVE HT, 18' EAVE HEIGHT, 12' EAVE HT)-   | (HNCHES)                   | 0.00         | <sup>B.1</sup>                                      | 33              |
| MAXIMUM DRIFT $\delta_{max}$ END COLUMNS   |                            | Soil Class 5 | <u>Sci Class 4</u>                                  | <u>Soil Cla</u> |
| 20' WIDE (O' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (HNCHEO)                   | 1.60         | 1.70  | 1.7             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)<br>10' WIDE (8' EAVE HT, 19' EAVE HEIGHT, 12' EAVE HT)               | (INCHES)                   | 2.00         | 2.45  | 2.2             |
| MINIMUM SEPARATION $(\delta_m = C_d \delta_{max})$ $C_d = 1.25$  |                            | 2.00         | 2.30  | 2.8             |
| 20 WIDE (O' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)   | (INOHEO)                   | 2.00         | 2.13  | 2.1             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                   | 2.50         | 3.06  | 2.8             |
| 10' WIDE (C'EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT) -   | (INCHES)                   | 3.43         | 2.88  | 3.5             |

| ARCHITEC TURAL REQUIREMENTS |   |  |  |  |  |  |
|-----------------------------|---|--|--|--|--|--|
| DESC RIPTION                | DESIGN VAULES                             |  |  |  |  |  |
| TYPE OF CONSTRUCTION        | II-B                                      |  |  |  |  |  |
| OCCUPANCY CLASSIFICATION    | A-3                                       |  |  |  |  |  |
| NUMBER OF STORIES           | 1   |  |  |  |  |  |
| FIRE SPRINKLER SYSTEM       | NOT BY ICON/WEIGHT NOT INCLUDED IN DESIGN |  |  |  |  |  |

RELATED BUILDING CODES AND STANDARDS

| TITLE 24 CODES:   |
|---|
| 2019 CALIFORNIA ADMINISTRATIVE CODE (CAC)(PART 1, TITLE 24, CCR)<br>2019 CALIFORNIA BUILDING CODE (CBC), VOLUMES 1, AND 2.(PART 2, TITLE 24,<br>CCR)  |
| 2019 CALIFORNIA ELECTRICAL CODE(PART 3, TITLE 24, CCR)<br>2019 CALIFORNIA MECHANICAL CODE (CMC)(PART 4, TITLE 24, CCR)<br>2019 CALIFORNIA PLUMBING CODE (CPC)(PART 5, TITLE 24, CCR)<br>2019 CALIFORNIA ENERGY CODE(PART 6, TITLE 24, CCR)<br>2019 CALIFORNIA FIRE CODE (CFC) |
| REFERENCE CODE SECTIONS FOR APPLICABLE STANDARDS:<br>2019 CBC, CHAPTER 35<br>2019 CFC, CHAPTER 80   |
| <u>SCOPE OF WORK NARRATIVE</u>  |

THESE DRAWINGS ILLUSTRATE THE FABRICATION AND INSTALLATION REQUIREMENTS FOR A FREE-STANDING PREFABRICATED STEEL SHADE STRUCTURE. THE ENTIRE STRUCTURAL SYSTEM IS COMPRISED OF HOLLOW STRUCTURAL STEEL MEMBERS SUPPORTED BY CONCRETE FOUNDATIONS. THE FLEXIBILITY INCLUDED HEREIN ALLOWS THE STRUCTURE TO COMPLY WITH A WIDE VARIETY OF PROJECT SITES AND LOADING REQUIREMENTS.

### <u>GENERAL:</u>


- WITH ANY WORK INVOLVED.

- 6. ASTM DESIGNATIONS AND ALL STANDARDS REFER TO THE LATEST AMENDMENTS.
- ARCHITEC T/ENGINEER OR OWNER.
- INSTALLATION.
- DETAILS OF ALL AREAS COMPLYING WITH THE WUI REQUIREMENTS.

# STRUCTURAL AND MISCELLANEOUS STEEL:

- CALIFORNIA BUILDING CODE.
- DRAWINGS (MAXIMUM INCREASE OF 1/8").

- 10.ALL ROOF DECKS SHALL CONFORM TO ASTM A-792, Fy = 50 KSI.



- -IDENTIFY THE APPLICABLE SHEET INDEX

| <u>NOT</u> | ICE               | OF   | DIS |
|------------|-------------------|------|-----|
| 1.         | PER               |      |     |
| 2.         | BE<br>FOR         |      |     |
| 3.         | FOR<br>GEN<br>FOR | ERA  | L F |
| -          | PRE               | PAR  | AT  |
| 4.         | STR<br>RES        |      |     |
| 5.         | ALL               | СО   | NS  |
|            | ENG<br>BUT        |      |     |
|            | CON               |      |     |
| 6.         | J.R.              | ΜIL  | LEF |
|            | AND               | - SF | 'ΕC |

CONSTRUCTION.

#### 1. GENERAL NOTES AND TYPICAL DETAILS SHALL APPLY TO ALL PARTS OF THE JOB EXCEPT WHERE THEY MAY CONFLICT WITH DETAILS AND NOTES ON OTHER SHEETS. WHERE CONDITIONS ARE NOT SPECIFICALLY INDICATED BUT ARE OF SIMILAR CHARACTER TO DETAILS SHOWN, SIMILAR DETAILS OF CONSTRUCTION SHALL BE USED SUBJECT TO REVIEW BY THE STRUCTURAL ENGINEER FOR THIS PROJECT. 2. WORK SHALL CONFORM TO THE REQUIREMENTS, AS AMENDED TO DATE, OF THE LATEST ADOPTED EDITION OF THE CBC, C.A.C. TITLE 24, AND ALL OTHER LOCAL, STATE AND FEDERAL REGULATIONS.

3. OMISSIONS OR CONFLICTS BETWEEN THE VARIOUS ELEMENTS OF THE WORKING DRAWINGS AND/OR SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE STRUCTURAL ENGINEER FOR THIS PROJECT PRIOR TO PROCEEDING 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE WORK OF ALL TRADES AND SHALL CHECK ALL

DIMENSIONS, ALL DISCREPANCIES SHALL BE CALLED TO THE ATTENTION OF THE STRUCTURAL ENGINEER FOR THIS PROJECT AND BE RESOLVED BEFORE PROCEEDING WITH THE WORK.

5. THESE CONSTRUCTION DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE AND DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES, INCLUDING, BUT NOT LIMITED TO, BRACING, TEMPORARY SUPPORTS, AND SHORING. OBSERVATION VISIT TO THE SITE BY FIELD REPRESENTATIVES OF THE ARCHITECT/ENGINEER SHALL NOT INCLUDE INSPECTIONS OF THE PROTECTIVE MEASURES OR THE CONSTRUCTION PROCEDURES. ANY SUPPORT SERVICES PERFORMED BY THE ARCHITECT/ENGINEER DURING THE CONSTRUCTION SHALL BE DISTINGUISHED FROM CONSTRUCTION AND DETAILED INSPECTION SERVICES WHICH ARE FURNISHED BY OTHERS. THESE SUPPORT SERVICES PERFORMED BY THE ARCHITECT/ENGINEER, WHETHER OF MATERIAL OR WORK, ARE FOR THE PURPOSE OF ASSISTING IN QUALITY CONTROL AND IN ACHIEVING CONFORMANCE WITH CONTRACT DOCUMENTS, BUT DO NOT GUARANTEE CONSTRUCTION.

7. CONFORM TO APPLICABLE CAL/OSHA CONSTRUCTION SAFETY REGULATIONS FOR ALL WORK PERFORMED DURING CONSTRUCTION. JOB SITE SAFETY IS STRICTLY THE RESPONSIBILITY OF THE CONTRACTOR AND NOT THE

8. THE ENGINEER AND THEIR CONSULTANTS SHALL HAVE NO RESPONSIBILITY FOR THE DISCOVERY, HANDLING, REMOVAL OR DISPOSAL OF HAZARDOUS MATERIALS AT THE PROJECT SITE, INCLUDING BUT NOT LIMITED TO ASBESTOS, ASBESTOS PRODUCTS, POLYCHLORINATED BIPHENYL (PCB) OR OTHER TOXIC SUBSTANCES. 9. SHOULD ANY CONDITIONS DEVELOP NOT COVERED BY THE CONTRACT DOCUMENTS, OR IF A CHANGE IN THE SCOPE OF WORK IS PROPOSED, A CONSTRUCTION CHANGE DOCUMENT DETAILING AND SPECIFYING THE REQUIRED CHANGE(S) SHALL BE SUBMITTED TO AND APPROVED BY DSA BEFORE PROCEEDING WITH THE WORK.

10. THE SCHOOL DISTRICT INSPECTOR ON RECORD SHALL INSPECT AND APPROVE THE ERECTED FRAME PRIOR TO ROOF 11. SEE REQUIREMENTS FOR LOCATION IN ANY FIRE HAZARD SEVERITY ZONE FOR WILDLAND URBAN INTERFACE AREAS (WUI) AS SPECIFIED IN THE APPLICABLE VERSION OF THE CALIFORNIA BUILDING CODE. PROVIDE PROTECTION AND

12. LOCATING THIS STRUCTURE CLOSER THAN 20 FEET TO OTHER STRUCTURES MAY AFFECT THE ALLOWABLE AREA FOR THE EXISTING CONSTRUCTION PER THE APPLICABLE VERSION OF THE CALIFORNIA BUILDING CODE. 13. VIEWS AND DETAILS ARE NOT DRAWN TO SCALE (UNLESS NOTED OTHERWISE). DO NOT SCALE THESE DRAWINGS.

1. ALL STRUCTURAL STEEL SHALL BE DETAILED, FABRICATED AND ERECTED IN ACCORDANCE WITH THE AMERICAN INSTITUE OF STEEL CONSTRUCTION (AISC) SPECIFICATION MANUAL REFERENCED BY THE LATEST EDITION OF THE

2. PIPE SECTIONS SHALL CONFORM TO ASTM A53, Fy = 35 KSI, GRADE B OR A501 UNLESS NOTED OTHERWISE. 3. STRUCTURAL TUBING (HSS SHAPES) SHALL CONFORM TO ASTM A-500, GRADE B (OR C), Fy = 46 KSI (MIN).

4. IF MATERIAL AVAILABILITY IS LIMITED, MEMBER THICKNESS CAN BE INCREASED BEYOND WHAT IS SHOWN IN THESE 5. ALL CHANNELS, ANGLES, AND MISC. STEEL SHALL CONFORM TO ASTM A-36, Fy = 36 KSI.

6. ALL PLATE STEEL SHALL CONFORM TO ASTM A-572, Fy= 50 KSI. 7. ALL COLD FORM STEEL SHALL CONFORM TO ASTM A-653, CS = TYPE B, Fy = 50 KSI.

8. STRUCTURAL STEEL AND DECK SHALL BE IDENTIFIED FOR CONFORMITY PER CBC 2202A.1.

9. ALL ROOF DECKS SHALL HAVE KYNAR 500 METAL COATING.

INSTRUCTIONS FOR ARCHITECTS SUBMITTING THESE PRE-CHECKED DRAWING TO DSA: BEFORE SUBMITTING THESE PRE-CHECKED DRAWINGS FOR YOUR PROJECT, FOLLOW THE STEPS BELOW TO PROPERLY DEFINE THE APPROVED OPTIONS:

#### STEP 1: SELECT FRAME DIMENSIONS FOR YOUR PROJECT -GABLE STRUCTURES UP TO 20' WIDE USE THE "RG 20" BASE FRAME -GABLE STRUCTURES UP TO 30' WIDE USE THE "RG 30" BASE FRAME -GABLE STRUCTURES UP TO 40' WIDE USE THE "RG 40" BASE FRAME -MAXIMUM WIDTH IS 40' (SEE "ARCHITECTURAL VIEWS" SHEET FOR REFERENCE)

-THE 24', 44', 64', 84' AND 104' LENGTHS ARE SUGGESTED BECAUSE THEY ARE THE MOST COMMON (20' BAYS ARE THE MOST ECONOMICAL) -FRAME LENGTHS ASSUME 2' OVERHANGS (UNO BY ARCHITECT - 2' MAX DIMENSION)

STEP 2: SELECT ROOF DECK FOR YOUR PROJECT -"M" REPRESENTS MCELROY METAL "MULTI-RIB" ROOF PANEL -"G" REPRESENTS MCELROY METAL "MEGA-RIB" ROOF PANEL

-"S" REPRESENTS MCELROY METAL "MEDALLION-LOK" 16" STANDING SEAM ROOF PANEL STEP 3: IDENTIFY THE Ss ACCELERATION (g) FOR YOUR PROJECT -Ss VALUE DETERMINES THE REQUIRED SEISMIC DESIGN FORCES

## -Ss VALUE DEPENDS ON THE PROJECTS GEOGRAPHICAL LOCATION (VALUES RANGE FROM 0.00 TO 3.73)

STEP 4: IDENTIFY THE Ss REGION FOR YOUR PROJECT -THE REGIONS ARE DEPENDANT ON THE Ss VALUE DETERMINED IN STEP 3 -THE SS REGION DICTATES THE MAXIMUM DEAD LOAD PERMITTED ON THE FRAME (SEE TABLE TO RIGHT)

STEP 5: IDENTIFY THE ROOF DEAD LOAD FOR YOUR PROJECT -THE ROOF DECK DEAD LOAD WILL ALWAYS BE INCLUDED -THE COLLATERAL LOAD REPRESENTS ADDITIONAL LOAD THAT CAN BE SUPPORTED BY THE FRAME -BE SURE THE TOTAL ROOF DEAD LOAD FOR YOUR PROJECT IS LESS THAN OR EQUAL TO THE MAX DEAD LOAD SHOWN IN STEP 4 FOR YOUR SS VALUE

-Sds VALUE USED IN CALCULATION IS THE CAPPED Sds (SEE DESIGN CRITERIA) STEP 6: IDENTIFY THE FOUNDATION REQUIREMENTS FOR YOUR PROJECT

-IDENTIFY SOIL CLASS FOR PROJECT SITE PER SITE SPECIFIC SOIL CONDITIONS -USE THIS TO SELECT CORRECT FOUNDATION SIZE ON FOUNDATION SHEET

STEP 7: SELECT MISCELLANEOUS OPTIONS FOR YOUR PROJECT -MAXIMUM CLEAR HEIGHT IS 12'-0"; (SEE "ARCHITECTURAL VIEWS" SHEET FOR REFERENCE) -MARK UP PC DRAWINGS WITH SIZE AND LOCATION OF CUTOUTS BEFORE SUBMITTING TO DSA

STEP 8: SELECT APPLICABLE SHEET INDEX FOR YOUR PROJECT -REFERENCE THE BASE FRAME (STEP 1) AND THE ROOF PANEL TYPE (STEP 2)

STEP 9: INCLUDE APPLICABLE SHEETS WITH YOUR DSA SUBMITTAL

-INCLUDE 'MISC DESIGN OPTIONS' SHEET FOR PROJECTS WITHOUT ELECTRICAL CUTOUTS OR GUTTERS

### ISCLAIMER FOR STRUCTURAL ENGINEERING RESPONSIBILITY

24, PART 1, SECTION 4-316(e) OF THE CALIFORNIA CODE OF REGULATIONS, THIS NOTICE SHALL TO DSA PRIOR TO THE APPROVAL OF PLANS AND SPECIFICATIONS. SITE SPECIFIC PROJECT, J. R. MILLER & ASSOCIATES IS NOT THE DESIGN PROFESSIONAL IN

RESPONSIBLE CHARGE. SITE SPECIFIC PROJECT, J.R. MILLER & ASSOCIATES' RESPONSIBILITY IS LIMITED TO THE TION OF THE PLANS AND SPECIFICATIONS FOR THE SHELTERS OF THIS PC ONLY.

RAL OBSERVATION OF CONSTRUCTION IS SPECIFICALLY EXCLUDED FROM J.R. MILLER & ASSOCIATES' IBILITY FOR THE SITE SPECIFIC PROJECT. STRUCTION ACTIVITIES RELATED TO STRUCTURAL ENGINEERING SHALL BE DELEGATED TO A QUALIFIED BY THE DESIGN PROFESSIONAL IN GENERAL RESPONSIBLE CHARGE. THESE ACTIVITIES INCLUDE, NOT LIMITED TO, APPROVAL OF INSPECTOR QUALIFICATIONS, STRUCTURAL OBSERVATION OF CTION, REVIEW OF INSPECTION REPORTS, AND SIGNING OFF OF THE VERIFIED REPORT FOR

D WORK ER & ASSOCIATES WILL BE RESPONSIBLE FOR RESPONDING TO QUESTIONS PERTAINING TO THE PLANS CIFICATIONS FOR THE SHELTERS OF THIS PC WHICH ARISE DURING PLAN REVIEW AND

#### WELDING:

- 1. ALL WELDING SHALL COMPLY WITH AWS D1.1 SPECIFICATIONS AND SHALL BE DONE BY AWS QUA CERTIFIED FOR THE TYPE OF WELDING TO BE PERFORMED AS REQUIRED BY DSA. 2. ALL WELDING SHALL BE DONE BY GAS METAL ARC PROCESS WITH E70XX ELECTRODES. FLUX CC
- SHALL CONFORM TO CHARPY NOTCH TOUGHNESS RATING OF 20 ft-16 @ (0°F). 3. ALL WELDING SHALL BE DONE IN THE SHOP WITH REQUIRED INSPECTION, PRE-APPROVED BY DS
- PROPER MATERIAL ID AND WELDING. 4. WELD FILLER METAL MANUFACTURER SHALL PROVIDE WRITTEN CERTIFICATION OF COMPLIANCE WI

#### <u>BOLTING:</u>

SPECIFIC ATIONS.

- 1. ALL BOLTS SHOWN ON THESE DRAWINGS ARE ASTM F3125 GRADE A325 HIGH STRENGTH BOI CONFORMING TO ASTM A-563.
- 2. HIGH STRENGTH BOLTS SHALL BE VERIFIED AND INSPECTED PER CBC 1705A2.1.
- 3. BEFORE ERECTING THE FRAME, VERIFY ALL BOLTS AND NUTS ARE CLEAN OF DEBRIS AND THE HARDWARE ALREADY FASTENED INSIDE THE MEMBERS. CHASING SOME OF THE BOLTS REQUIRED.
- 4. HARDENED STEEL WASHERS SHALL CONFORM TO ASTM F-436. 5. THE BOLTING INSTALLATION REQUIREMENTS OUTLINED BELOW ARE CRITICAL TO THE STRUCT PERFORMANCE. THE INSTALLER IS REQUIRED TO COORDINATE THIS PHASE OF CONSTRUCTION BOLTING INSPECTOR AND THE INSPECTOR OF RECORD PRIOR TO THE ERECTION OF THE FRA BE INSTALLED AND INSPECTED PER THE APPLICABLE VERSION OF AISC'S "SPECIFICATION FO USING HIGH-STRENGTH BOLTS", CBC 1705A.2.1; AISC 341-16 J7; AISC 360-16 N5.6. A)PRETENSIONED JOINTS MUST BE INSTALLED AND INSPECTED TO MEET ONE OF THE FOL 1. TURN-OF-NUT PRETENSIONING
  - 2. CALIBRATED WRENCH PRETENSIONING
  - 3. DIRECT-TENSION-INDICATOR PRETENSIONING (CONTRACTOR RESPONSIBLE FOR REQUIRED WASHERS)
- FOUNDATIONS: 1. ALLOWABLE SOIL PRESSURES ASSUME CLASS 5 SOIL CLASSIFICATION PER CBC TABLE 1806A OTHERWISE.
- 2. PER CBC SECTION 1803A.2, GEOTECHNICAL REPORTS ARE NOT REQUIRED FOR ONE-STORY BUILDINGS OF TYPE II CONSTRUCTION AND 4,000 SQUARE FOOT OR LESS IN FLOOR AREA EARTHQUAKE FAULT ZONESOR SIESMIC HAZARD ZONES AS SHOWN ON THE MOST RECENT CGS. ALLOWABLE FOUNDATION AND LATERAL SOIL PRESSURE VALUES MAY BE DETERMINED
- 3. FILL AND BACKFILL SHALL BE COMPACTED TO 95% OF MAX. DENSITY IN ACCORDANCE WITH
- D-1557 OR AS RECOMMENDED BY THE GEO-TECH ENGINEER. FLOODING NOT PERMITTED. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING, ETC. NECESSARY TO SUPPOR
- BANKS DURING EXCAVATION, AND FORMING AND PLACEMENT OF CONCRETE. 5. MINIMUM SETBACK FROM TOE OF SLOPE ON AN ASCENDING SLOPE SHALL BE 15 FEET AND
- FROM TOE OF SLOPE ON A DESCENDING SLOPE SHALL BE 40 FEET 6. PER CBC SECTION 1803A.6, GEOHAZARD REPORTS ARE NOT REQUIRED FOR ONE-STORY LIGH OF TYPE II CONSTRUCTION AND 4,000 SQUARE FOOT OR LESS IN FLOOR AREA AND NOT LOC FAULT ZONESOR SIESMIC HAZARD ZONES AS SHOWN ON THE MOST RECENT MAPS PUBLISHED
- 7. GEOHAZRD REPORTS ARE TO COMPLY WITH DSA IR A-4 PER IR-7 SECTION 1.8 8. SITE SPECIFIC GEOTECHNICAL REPORT IS REQUIRED AT THE TIME OF SITE APPLICATION IS US
- CLASS 5 SOIL, PER DSA IR PC-7 9. LATERAL BEARING HAS BEEN INCREASED PER CBC 1806A.3.4 & HAS BEEN DESIGNED FOR
- <u>CONCRETE:</u>

| STRENGTH Pc<br>(28 DAYS) | W/C RATIO<br>(NON-AIR ENTRAINED) | W/C RATIO<br>(AIR ENTRAINED) | SLUMP (±1 |
|--------------------------|----------------------------------|------------------------------|-----------|
| 4500 PSI                 | 0.44                             | 0.35                         | 3"        |
| 2. CONCRETE MIX DESIG    |                                  | DOD FOR EXPOSURE CAT         |           |

- ENTRAINMENT FOR THESE CATEGORIES SHALL BE AS FOLLOWS: F0-0, F1-4.5, F2-0 3. AGGREGATES SHALL CONFORM TO THE ASTM C-33 WITH PROVEN SHRINKAGE CHAR MAX AGGREGATE SIZE = 1".
- 4. CEMENT SHALL CONFORM TO ASTM C-150 (TYPE V) UNLESS NOTED OTHERWISE ON 5. CONCRETE SHALL BE MAINTAINED IN A MOIST CONDITION FOR A MINIMUM OF FIVE
- ALTERNATE METHODS WILL BE APPROVED IF SATISFACTORY PERFORMANCE CAN BE 6. CONCRETE SHALL NOT FREE FALL MORE THAN FIVE FEET.
- 7. CONCRETE DURABILITY SHALL BE PER CBC 1904A.1 & ACI 318-14 CHAPTER 19. 8. CONCRETE SHALL BE TESTED PER CBC 1903A, TABLE 1705A.3. AND ACI 318-14

STEP 10: IDENTIFY PROJECT NAME AND SCHOOL DISTRICT

|             |       | PROJEC T NAME:                     |      |             |          |          |           | SCHOOL  | DISTRIC T:   |
|-------------|-------|------------------------------------|------|-------------|----------|----------|-----------|---------|--------------|
|             |       | SHADE STRUCTURE AT S               |      |             | SAC      |          |           |         |              |
|             |       | ELEMENTARY SCHO                    |      |             | SCHOOL   | DISTRCIT |           |         |              |
|             |       |                                    |      |             | FR       |          | DIMENSION | <u></u> |              |
| -           | -     |                                    |      |             |          |          | ESTED     | 5       |              |
| STFP        |       | FRAME WIDTH                        | [] 2 | 0' <b>N</b> |          | 30°      | [] 40'    |         |              |
| ייט  <br>ער | י 📃   | FRAME LENGTH                       |      |             |          | 64'      | [] 4'     | [] 104' |              |
|             |       |                                    |      |             | $\sim$   | 0-       |           |         |              |
|             | ~ ~ ~ |                                    |      |             |          | PO       | OF PANEL  |         |              |
|             |       |                                    |      |             | <u> </u> |          |           |         |              |
|             | STEP  | ROOF PANEL TYPE                    |      |             | []       | М        | [] G      | X s     |              |
|             |       |                                    |      |             |          |          |           |         |              |
|             |       | PROJECT SITE - SS ACCELERATION (g) |      |             |          |          | g)        |         |              |
|             | ו     |                                    |      |             |          |          | 0.496     |         |              |
|             | 1     |                                    |      |             |          |          |           |         |              |
|             |       |                                    |      |             |          | Ss       | REGION    |         |              |
|             |       |                                    |      |             |          |          |           | S       | s REGIONS    |
| 4           |       |                                    |      |             |          |          | Х         | 0 <     | Ss <= 2.14   |
| STEP        |       |                                    |      |             |          |          |           | 2.14    | < Ss <= 2.5  |
| N.          |       | DESC RIP TION                      |      |             |          |          |           | 2.50    | < Ss <= 2.7  |
|             |       |                                    |      |             |          |          |           | 2.75    | < Ss <= 3.0  |
|             |       |                                    |      |             |          |          |           | Ss      | > 3.73 MAX   |
|             |       |                                    |      |             |          |          |           |         |              |
|             |       |                                    |      | TO          | TAL      | ROC      | F DEAD LO | AD      |              |
|             |       |                                    |      |             | DE       | EAD I    | LOAD      |         | E)           |
| Ъ<br>5      |       | ROOF DECK                          |      |             | _1       | .3       | _ PSF     | M=1.1PS | SF; G=1.2PSF |
| STEP        |       | COLLATERAL                         |      |             | 0        |          | PSF       |         | LIGH         |
|             |       |                                    |      |             |          |          |           |         |              |

CONSTRUCTION NOTES

TOTAL


1. A DSA-CERTIFIED CLASS 3 PROJECT INSPECTOR IS REQUIRED FOR TH 2. CHANGES TO THE APPROVED DRAWINGS AND SPECIFICATIONS SHALL


<u>1.3</u> PSF

ADD ROOF DECK

- DOCUMENT (CCD) APPROVED BY DSA, AS REQUIRED BY SECTION 4-3. A "DSA CERTIFIED" PROJECT INSPECTOR EMPLOYED BY THE DISTRICT CONTINUOUS INSPECTION OF WORK. THE DUTIES OF THE INSPECTOR
- 4. A DSA ACCEPTED TESTING LABORATORY DIRECTLY EMPLOYED BY THE TESTS AND INSPECTIONS FOR THE PROJECT. 5. THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS ARE THAT ALL RECONSTRUCTION IS TO BE IN ACCORDANCE WITH TITLE 24, CCR. SH OR NON-COMPLYING CONSTRUCTION BE DISCOVERED WHICH IS NOT ( FINISHED WORK WILL NOT COMPLY WITH TITLE 24, CCR, A CONSTRUCT
- PLANS AND SPECIFICATIONS, DETAILING AND SPECIFYING THE REQUIRED BEFORE PROCEEDING WITH THE WORK, (SECTION 4-317(c), PART 1, TI 6. GRADING PLANS, DRAINAGE IMPROVEMENTS, ROAD AND ACCESS REQUI SHALL COMPLY WITH ALL LOCAL ORDINANCES


|   | REINFORCING S      | TEEL:   |                      |                                    |                                |   |  |
|---|--------------------|---|----------------------|------------------------------------|--------------------------------|---|--|
|   | 1. REINFORG        | CING STEEL SHALL BE DEFOR   | MED STEEL CONFORM    | ING TO THE RE                      | QUIREMENTS OF ASTM A           | 4-615,  |  |
| ALIFIED WELDERS   | AS FOL<br>GF       | LOWS:<br>R 60: (#4 BARS AND LARGEF  | ۶)                   |                                    |                                |   |  |
| ORE ARC WELD  | GF                 | R 40: (#3 BARS)   |                      |                                    | ONFORM TO THE ACL              |   |  |
| SA, TO ENSURE   | "MANUAI            | G, FABRICATION, AND ERECT<br>L OF STANDARD PRACTICE FO<br>VER FOR CAST-IN-PLACE CO        | OR DETAILING REINFOR | CING CONCRET                       |                                |   |  |
| WITH CODE AND   | A. C               | AST AGAINST EARTH   |                      |                                    |                                |   |  |
|   | C.F                | ORMED SLABS (#11 BAR & S  | SMALLER)3/           | /4"                                |                                |   |  |
|   | 4. BARS SH         | LABS ON GRADE (FROM TOP<br>HALL BE CLEAN OF RUST, GF                                      |                      | ERIAL LIKELY T                     | O IMPAIR BOND.                 |   |  |
| OLTS (UNO), WITH THE NUTS   | 5. REINFOR         | SHALL BE MADE COLD.<br>CING SHALL BE LAP SPLICED  |                      |                                    |                                |   | ICON STD RH/DSA-PC   |
|   | 7. WELDING         | O PLACING OF CONCRETE, R<br>OF REINFORCING IS NOT ALI<br>CING STEEL SHALL BE INSPE        | OWED.                |                                    | IEMS SHALL BE WELL S           | ECURED IN POSITION.                                     | DRAWN BY ANGEL   |
| BURRS — INCLUDING<br>AND NUTS MAY BE  |                    | AT FINISH SYSTEM:   | CIED PER CBC 1703    | ч.J.                               |                                |   | DATE 4/2/2021<br>REV   |
|   |                    | S THAT HAVE A POWDER-CO<br>EL FRAME SHALL BE SHOT-E                                       |                      |                                    |                                |   | REV DATE   |
| TURE'S DESIGN AND<br>NN WITH THE SPECIAL                                      | 2. THE STE         | EL SHALL BE WASHED IN A<br>REATEMENT PROCESS.   |                      |                                    |                                |   | I  |
| AME. ALL BOLTS SHALL<br>FOR STRUCTURAL JOINTS                                 | 3. IMMEDIA         | TELY FOLLOWING PRE-TREATM<br>(E-COAT) AND COATED TO A                                     |                      |                                    |                                |   |  |
| DLLOWING REQUIREMENTS:  | PROVIDI            | E A MINIMUM OF 1000 HOUR:<br>EL SHALL THEN HAVE A TGK                                     | S OF SALT SPRAY CO   | RROSION PROTE                      | ECTION TO THE STEEL.           |   |  |
|   | 5. THE COI         | LOR COAT SHALL THEN HAVE A TGIN<br>LOR COAT SHALL THEN HAVE<br>MOLET LIGHT, TO HELP PREVE | A CLEAR TGIC COA     | · · · ·                            |                                |   |  |
| R PURCHASE OF   | 6. THE FINI        | SH THICKNESS OF THESE TH  | REE APPLICATIONS SH  |                                    |                                |   |  |
|   | COAT F             | RBON STEEL MEMBERS (COLU<br>PER THE "AISC CODE OF STA                                     |                      |                                    |                                |   |  |
| A, UNLESS NOTED   | OTHERV<br>ABBREVIA |   |                      |                                    |                                |   |  |
| LIGHT-STEEL FRAME<br>AND NOT LOCATED WITHIN                                   | ACI                | AMERICAN CONCRE   |                      | MPH                                |                                | PER HOUR  | ARCHITECTS ENGINEERS<br>2700 SATURN ST I BREA, CA 92821                            |
| MAPS PUBLISHED BY THE<br>FROM TABLE 1806A.2.                                  | AISC               | AMERICAN INSTITUTE OF ST<br>ASSEMBLY (INTERNAL  |                      | M<br>NTS                           | MULTI-RIB ROOF I               | PANEL (MCELROY)<br>0 SCALE                              | T. 714.524.1870   F. 714.524.1875<br>WWW.JRMA.COM                                  |
| H ASTM TEST METHOD  | ASTM               | AMERICAN SOCIETY FOR TE   | •                    | NO                                 |                                | IMBER   | ED PROFESS/ONAL  |
| RT CUT AND/OR FILL  | AWS<br>CBC         | AMERICAN WELDIN<br>CALIFORNIA BUILE   |                      | OC<br>OSHA                         | ON (                           | CENTER<br>H AND SAFETY ADMIN                            |  |
| MINIMUM SETBACK   | CJP                | COMPLETE JOINT F  |                      | PCF                                |                                | CUBIC FOOT  |  |
| HT-STEEL FRAME BUILDINGS  | C LR<br>DEG        | CLEAF   |                      | PJ<br>PLC S                        |                                | IONED JOINT   | - PUCTURE T  |
| CATED WITHIN EARTHQUAKE<br>ED BY THE CGS.                                     | DIA                | DIAMET  |                      | PLT                                |                                | LATE  | 07/29/   |
| SING OTHER THAN   | DIM<br>DSA         | DIMENS  | -                    | PSF<br>PSI                         |                                | SQUARE FOOT<br>SQUARE INCH                              |  |
| P-DELTA EFFEC TS  | EQ                 | EQUA  |                      | QTY                                |                                | ANTITY  | -  |
|   | FT<br>GA           | FEET  |                      | REF<br>SQ                          |                                | ERENCE<br>QUARE   | -  |
|   |                    | INCHE   |                      | SS                                 |                                | DF PANEL (MCELROY)                                      | -  |
| ") UNIT WEIGHT<br>(NORMAL WEIGHT)   | KSI<br>MAX         | KIPS PER SQUAF<br>MAXIMU  |                      | TYP<br>UNO                         | TYPIC AL<br>UNLESS NOTED OTHER |   |  |
| 150 PCF   | MIN                | MINIMU  |                      | USGS                               | U.S. GEOLOGICAL SURV           |   |  |
| 1 & F2. THE AIR<br>-6<br>RACTERISTICS OF LESS THAN (                          | MISC               | MISCELLAN   | EOUS                 | ₩/                                 | WITH                           |   | APPROVED<br>THE STATE ARCHITECT  |
| SECTION 26.12.  |                    |   |                      |                                    |                                |   |  |
| IED   |                    |   |                      |                                    |                                |   |  |
|   |                    |   |                      | ON REQUIREMEN                      |                                |   |  |
| OTHER<br>[ ] (40' MAX)  | N                  | OIL CLASS 5 (BEARING)-1500 PS<br>CLASS 5 (LATERAL BEARING)-10                             |                      | 4 (BEARING)-200<br>(LATERAL BEARIN |                                | 3 (BEARING)-3000 PSF [ ]<br>3 (LATERAL BEARING)-200 PSF |  |
| [] (NO MAX)   |                    |   | MISC                 | CELLANEOUS                         |                                |   | INFO<br>INFO   |
|   |                    | CLEAR HE  |                      |                                    | DESIGN C<br>8' 🗙 10' [] 12'    | DPTIONS [] ' (12' MAX)                                  |  |
|   | STEP               | ELEC TRIC AL C  |                      |                                    |                                | [] ' (12' MAX)<br>[] NO                                 | GENERAL  |
|   |                    | GUTTER  | S                    |                                    | 🗙 Yes                          | [ ] NO  |  |
|   |                    | BASE FRAME  | S⊢<br>RG 20          | EET INDEX                          | RG 30                          | RG 40   | CE CE  |
|   |                    | ROOF PANEL TYPE   |                      | S N                                |                                | M G S   |  |
| MAX DEAD LOAD<br>5 PSF  |                    | SELEC T ONE<br>GENERAL NOTES  |                      | [] [<br>51.0 LS <sup>7</sup>       |                                | [] [] []<br>LS1.0 LS1.0 LS1.0                           |  |
| 50 5 PSF  |                    | DSA 103 EXAMPLE   |                      | 51.1 LS1                           |                                | LS1.1 LS1.1 LS1.1                                       |  |
| 75 5 PSF<br>00 4 PSF  | STEP 8             | FOUNDATION PLAN<br>FRAMING PLAN   |                      | 52.0 LS3                           |                                | LS4.0 LS4.0 LS4.0<br>LS4.1 LS4.1 LS4.1                  | l  |
| 3 PSF   | FRAM               | E CONNECTION DETAILS  | LS2.1 LS2.1 LS       | 52.1 LS                            | 3.1 LS3.1 LS3.1                | LS4.2 LS4.2 LS4.2                                       | SE SE  |
|   | ROOF               | TING LAYOUT & DETAILS   |                      | 52.4 LS                            |                                | LS4.3 LS4.4 LS4.5<br>LS5.0 LS5.0 LS5.0                  |  |
| XAMPLES   |                    |   |                      |                                    | SEMONT DRIVE, SACRA            |   |  |
| F ;S=1.3PSF (SEE STEP 2)  |                    |   |                      |                                    |                                |   |  |
| AND COLLATERAL LOADS<br>AX 5 PSF)   |                    |   |                      | DESCRIPTIO                         | <u>N</u>                       | DESIGN VALUES   |  |
|   |                    |   | BASIC WIND SPE       | WIND DESIG                         |                                | 94 MPH  |  |
|   |                    |   | <b>RISK CATEGORY</b> |                                    | - // <sup>-</sup> UIL          |   | DISTINCTIVE STEEL SHELTERS<br>WWW.ICONSHELTERS.COM<br>COPYRIGHT 2004, ICON SHELTER |
|   |                    |   | EXPOSURE CATE        | GORY                               |                                | C   | SYSTEMS, INC.<br>1455 LINCOLN AVE  |
| HIS PROJECT.<br>BE MADE BY ADDENDA OR<br>-338, PART 1, TITLE 24, CC           |                    | CHANGE  | SEISMIC SITE CL      | <u>SEISMIC DESIGI</u><br>ASS       | N                              | D   | HOLLAND MI, 49423  |
| OWNER) AND APPROVED I<br>ARE DEFINED IN SECTION 4                             | BY DSA SHALL I     |   | Ss                   |                                    |                                | 0.496   | 616.396.0919   |
| E DISTRICT (OWNER) SHALL  | CONDUCT ALL        | THE REQUIRED  | *All information pro | ovided by https://a                | isce7hazardtool.online/and h   | ntps://seismicmaps.org/                                 | 800.748.0985<br>616.396.0944 FX  |
| L THE WORK OF THE ALTER<br>HOULD ANY EXISTING CONDI<br>COVERED BY THE CONTRAC | TIONS SUCH AS      | DETERIORATION   |                      |                                    |                                |   |  |
| TION CHANGE DOCUMENT (<br>TION CHANGE DOCUMENT (<br>D WORK SHALL BE SUBMIT    | CCD), OR A SEF     | PARATE SET OF   |                      |                                    |                                |   |  |
| ITLE 24, CCR)   |                    |   |                      |                                    |                                | IECK (PC) DOCUMENT<br>Code: 2019 CBC                    | LS1.0  |
|   |                    |   |                      |                                    |                                | plication for construction is r                         | equired.   |
|   |                    |   |                      |                                    | 1                              |   | PRINTED ON :   |
|   |                    |   |                      |                                    |                                |   |  |








| Order Development<br>In the second composition of the second composi   | D4-00000 ICON<br>DSA File Number: Incre<br>5. RETAINING WALLS<br>Test or Special Inspection  | N Shelter Systems                      |                  | TIONS (SOILS), 2019 CBC<br>School District:  | -     |  |  |               |
|--|--|--|------------------|--|-------|--|--|---------------|
|  | 5. RETAINING WALLS<br>Test or Special Inspection   | ement Number:                          |                  | PC Submittal   |       |  |  |               |
| The or Special Inspection     Type     Type Type Type Type Type Type Type Type   | Test or Special Inspection   |  |                  |  | -     |  |  |               |
| $\frac{1}{1} + P \operatorname{arrest}_{2} \operatorname{currates end}_{2} \operatorname{currates}_{2} \operatorname{currate}_{2} \operatorname{currate}_{2} \operatorname{currates}_{2} $ |  |  |                  |  | ۱     |  |  |               |
|  | a. Placement, compaction and inspe   | Туре                                   |                  | Code References and Notes  |       |  |  |               |
| Experient and solutions and proper Status and Provide care Version And Prove Version And Provide Care Version And Provide Care Version And Pr  |  | ection of backfill. Continuou          |                  |  |       |  |  |               |
| Unit-documents       ECV 310         Concentration press       Productions press (Concentration press)         Concentration press       Productions (Concentration press)         Concentration press       Productions (Concentration press)         Concentration press       Contentration press (Concentration press)         Concentration press       Contentration press (Concentration press)         Concentration press       Contentration press (Concentration press)         Contentration press       School press (Concentration press)         Contentration press (Concentration press)       School press (Concentration press)         Contentration press (Concentratio  |  | and/or drainage Continuo               | JS GE*           | * By geotechnical engineer or his or her qualified representative  |       |  |  |               |
| E Concerner example with Provide exchange of COCRETE exclusions and SC     EAdowner within paths     Provide exchange of SC CRETE exclusions     Provide exchange of SC CRETE exclusions     Provide exchange of SC CRETE exclusions     EAdowner within paths     Provide exchange of SC CRETE exclusions     EAdowner within paths     Provide exchange of SC CRETE exclusions     EAdowner within paths     Provide exchange of SC CRETE exclusions     EAdowner within paths     Provide exchange of SC CRETE exclusions     EAdowner within paths     Provide exchange of SC CRETE exclusions     EAdowner within paths     Provide exchange of SC CRETE exclusions     EAdowner within paths     EAdowner w  |  | t placement of Continuou               | JS GE*           |  | i L   |  |  |               |
| Contract State     Contract  |  | Provide tes                            | ts and inspectio |  |       |  | ICON STD                                       | RH/DSA        |
| Description         Description <thdescription< th=""> <thdescription< th=""></thdescription<></thdescription<>  | e. Masonry retaining walls.  | Provide test                           | ts and inspectio | ns per MASONRY section below.  | j     |  | DRAWN BY                                       | AN            |
| Inter & Special Inspection     Vpc     Perform     Gali Neuroneses and Batters       a. Solid Ingrovements     Test     BC     Solid Ingrovements     Ext Solid Ingrovements       b. Inspection of Solid Ingrovements     Continuous     GF     * Solid Ingrovements     Ext Solid Ingrovements       b. Inspection of Solid Ingrovements     Continuous     GF     * Solid Ingrovements     Ext Solid Ingrovements       c.     Development     Continuous     GF     * Solid Ingrovements     Ext Solid Ingrovements       c.     Development     Continuous     GF     * Solid Ingrovements     Ext Solid Ingrovements       c.     Development     Continuous     GF     * Solid Ingrovements     Ext Solid Ingrovements       c.     Development     Continuous     GF     * Solid Ingrovements     Ext Solid Ingrovements       Solid Ingrovement     Continuous     GF     * Solid Ingrovements     Ext Solid Ingrovements       Solid Ingrovement     Development     Solid Information     * Solid Information     * Solid Information       Solid Information     Ext Solid Information     Solid Information     * Solid Information     * Solid Information       Solid Information     Ext Solid Information     Ext Solid Information     * Solid Information     * Solid Information       Solid Information     Ext Solid Infore  | 6. OTHER SOIL  |  |                  |  | ]     |  | DATE   | 4/2/          |
| b. Soll increase reacts     194     0     3 data as concensusing respect to concentration find to the increase runner increases to solve result in concentration in the solution and increases and i   |  | Туре                                   |                  | Code References and Notes  | -     |  | REV  |               |
| 1     1000 Test Status     1000  | a. Soil Improvements   | Test                                   |                  | Submit a comprehensive report documenting final soil improvements  | -     |  |  |               |
| C      |  |  |                  | constructed, construction observation and the results of the confirmation testing and analysis to COS for final acceptance.  |       |  |  |               |
| DSA 110 Review 07/05/2020<br>EN OF DE STATE AGCIENT     DEMARTINENT OF CARSALL STRACES<br>Page 4.0f 11     STATE OF CARSAND<br>Page 4.0f 11       N103-19: LISTING OF STRUCTURAL TESTS & SPECIAL INSPECTIONS (Concrete), 2019 CBC     Concrete), 2019 07 00 07 00 07 00 07 00 00 00 00 00 00   | b. Inspection of Soil Improvements   | Continuor                              | us GE*           | * By geotechnical engineer or his other qualified representative   |       |  |  |               |
| Index of the State accurate:     Description       Page 4 of 11     Description         Index of the State accurate:     State of CAUPING         Index of the State accurate:     School Description       Index Number:     School Description       Index of the State accurate:     School Description       Index Number:     School Description       Index of the State accurate:     School Description       Index of the State accurate ac   | ] c.   |  |                  |  | 1     |  |  |               |
| 2021-07-14 05:50:33         19.1 SHOP WELDING:         Test or Special Inspection       Type       Performed       Code References and Notes         By       a. Inspect groove welds, multi-pass fillet webs single pass       Continuous       Sil       Table 1705A.2.1 Items 5n-1-4; AISC 360-16 (and AISC 341-16 as applicable;) SAR IR 173.         b. Inspect single-pass fillet webs s 5/16°, floor and rot       Periodic       Sil       1705A.2.2, Table 1705A.2.1 Items 5n-5 & 5n.6; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; D4 R 17-3.         c. Inspect welding of stairs and railing systems.       Periodic       Sil       1705A.2.1 Items 5n.1-6 as applicable); AWS D1.1 & D1.3; D4 R 17-3.         d. Veiffcation of reinforcing steel       Continuous       Sil       1705A.2.1 Items 5n.1-6 as applicable); AWS D1.1 & D1.3; D4 R 17-3.         z. AncHOR BOLTS AND ANCHOR RODS:       Test       Code References and Notes       Notes Note   | e 705A.3; ACI 318-14 Sections 26.12 a<br>lication Number: Schoo<br>200000 ICON S   | & 26.13<br>DI Name:<br>Shelter Systems | L INSPECTI       | School District:<br>PC Submittal   | ,<br> |  | T. 714.524.1870   F                            | F. 714.524.18 |
| Test or Special Inspection       Type       Performed<br>By       Code References and Notes<br>By         a. Inspect groove welds, multi-pass fillet welds, single pass       Continuous       SI       Table 1705A.2.1 Items 5ut-4; AISC 360-16 (and AISC 341-16 as<br>applicable;) DSA IR 17:2.         b. Inspect single-pass fillet welds ≤ 5/16°, floor and robt<br>deck welds.       Periodic       SI       1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC<br>341-16 as applicable;) DSA IR 17-3.         c. Inspect welding of stairs and railing systems.       Periodic       SI       1705A.3.1; AWS D1.4; DSA IR 17-3.         d. Verification of reinforcing steel weldability       Periodic       SI       1705A.2.2; Item 5b, 1705A.3.1; Table 1705A.3.1; Tabl  |  |  |                  |  |       |  | OF PROF  | ESS/ON        |
| By       By         al. Inspect groove welds, multi-pass fillet welds, single pass       Continuous       SI       Table 1705A.2,1 Items 5arl -4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         b. Inspect single-pass fillet welds ≤ 5/16", floor and rot       Periodic       SI       1705A.2,1 Tems 5arl -4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         c. Inspect welding of stairs and railing systems.       Disionic       SI       1705A.2,1 AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DFR 17-3.         d. Verification of reinforcing steel weldability       Periodic       SI       1705A.2,1 Item 5b, 1705A.3,1 AWS D1.4; DSA IR 17-3.         d. Verification of reinforcing steel.       Continuous       SI       Table 1705A.2,1 Item 5b, 1705A.3,1 Table 1705A.3,1 Table 1705A.3, Item 2, 1903A.8; ANS D1.4; DSA IR 17-3.         e.Inspect welding of reinforcing steel.       Continuous       SI       Table 1705A.3,1 Item 5b, 1705A.3,1 Table 1705A.3, Item 2, 1903A.8; ANS D1.4; DSA IR 17-3.         z.3. ANCHOR BOLTS AND ANCHOR RODS:       Test       LOR       Sample and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-1.   | 19.1 SHOP WELDING:   |  |                  |  |       | 1  |  | , fo          |
| a. Inspect groove welds, multi-pass fillet welds, single pass       Continuous       SI       Table 1705A.2.1 Items 5ar 1-4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         b. Inspect single-pass fillet welds = 5/16°, floor and rot       Periodic       SI       1705A.2.2, Table 1705A.2.1 Items 5ar 5a 5a,6; AISC 360-16 (and AISC 344-16 as applicable); DSA IR 17-3.         c. Inspect welding of stairs and railing systems.       Periodic       SI       1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3.         d. Vertification of reinforcing steel weldability       Periodic       SI       1705A.3.1; AWS D1.4; DSA IR 17-3.         e. Inspect welding of reinforcing steel.       Continuour       SI       1705A.3.1; AWS D1.4; DSA IR 17-3.         z.3. ANCHOR BOLTS AND ANCHOR RODS:       Test       Code References and Notes By and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-11.   | Test or Special Inspection   | Туре                                   |                  | Code References and Notes  |       |  |  | 4092          |
| b. Inspect single-pass fillet welds ≤ 5/16", floor and rot deck welds.       Periodic       SI       1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         c. Inspect welding of stairs and railing systems.       Periodic       SI       1705A.2.1 AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; Dirk IR 17-3.         d. Verification of reinforcing steel weldability       Periodic       SI       1705A.2.1 AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; Dirk IR 17-3.         e. Inspect welding of reinforcing steel.       Continuou       SI       1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3.1 tam 2, 1903A.8; ANS D1.4; DSA IR 17-3.         z. ANCHOR BOLTS AND ANCHOR RODS:       Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3.1 tam 2, 1903A.8; ANS D1.4; DSA IR 17-3.         z. Anchor Bolts and Anchor Rods       Test       LOR       Sample and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-11.  |  |  | -                |  |       | _  | S. AU  | CTUR          |
| c. Inspect welding of stairs and railing systems.       Pociodic       SI       17051/2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; Dix IR 17-3.         d. Verification of reinforcing steel weldability       Periodic       SI       1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates.         e. Inspect welding of reinforcing steel.       Continuour       SI       Table 1705A.2.1 Item 5b, 1705A.3.1; Table 1705A   | <b>b.</b> Inspect single-pass fillet welds $\leq 5/$   |  |                  | 1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC  |       |  | TE OF  | CALIFO        |
| A. Verification of reinforcing steel weldability       Periodic       \$1       1705A.3.1; AWS D1.4; D5A IR 17-3. Verify carbon equivalent reported on mill certificates.         B. Inspect welding of reinforcing steel.       Continuou       SI       Table 1705A.3.1; Tab   |  | a systems. Pacio dic                   |                  | <b>1705 1</b> |       |  |  | 07/           |
| e. Inspect welding of reinforcing steel.       Continuour       SI       Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8;         23. ANCHOR BOLTS AND ANCHOR RODS:  |  | Idability Periodic                     |                  | 1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on   |       |  |  |               |
| 23. ANCHOR BOLTS AND ANCHOR RODS:         Test or Special Inspection       Type       Performed<br>By       Code References and Notes         a. Anchor Bolts and Anchor Rods       Test       LOR       Sample and test anchor bolts and anchor rods not readily identifiable per<br>procedures noted in DSA IR 17-11.  |  | I. Continuou                           | SI               | Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8;   |       |  |  |               |
| Test or Special Inspection       Type       Performed By       Code References and Notes         a. Anchor Bolts and Anchor Rods       Test       LOR       Sample and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-11.  | other than ASTM A706.  |  |                  | лю U1.4, U3.4 Ги-3.  |       |  |  |               |
| By     By       a. Anchor Bolts and Anchor Rods     Test     LOR     Sample and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-11.   | other than ASTM A706.  |  |                  |  | г     |  |  |               |
| procedures noted in DSA IR 17-11.  | other than ASTM A706.<br>e. Inspect welding of reinforcing steel<br>23. ANCHOR BOLTS AND ANCHOR R  |  | Performed        | Code References and Notes  |       |  |  |               |
|  | other than ASTM A706.<br>e. Inspect welding of reinforcing steel<br>23. ANCHOR BOLTS AND ANCHOR R<br>Test or Special Inspection  | Туре                                   | Ву               |  | I     |  |  |               |
| b. Threaded rod not used for buildation anchorage. Test LOR Sample and test threaded rods not readily dentifiable per procedures noted in DSA IR 17-11.  | other than ASTM A706.<br>e. Inspect welding of reinforcing steel<br>23. ANCHOR BOLTS AND ANCHOR R<br>Test or Special Inspection  | Туре                                   | Ву               | Sample and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-11.  |       |  |  |               |
| APP: 04-120013 PC  | other than ASTM A706.<br>e. Inspect welding of reinforcing steel<br>23. ANCHOR BOLTS AND ANCHOR R<br>Test or Special Inspection  | Type<br>Test                           | Ву               | procedures noted in DSA IR 17-11.<br>Sample and test threaded rods not readily identifiable per procedures   |       |  |  | $\mathbf{X}$  |
| REVIEWED FOR   | other than ASTM A706.<br>e. Inspect welding of reinforcing steel<br>23. ANCHOR BOLTS AND ANCHOR R<br>Test or Special Inspection<br>a. Anchor Bolts and Anchor Rods   | Type<br>Test                           | By<br>LOR        | procedures noted in DSA IR 17-11.<br>Sample and test threaded rods not readily identifiable per procedures   |       | DIV. OF THE ST   | ATE ARCHITEC                                   | CT            |
| SS 🖉 DES 🖉 ACS 🖻 CG 🗋  | other than ASTM A706.         e. Inspect welding of reinforcing steel         23. ANCHOR BOLTS AND ANCHOR R         Test or Special Inspection         a. Anchor Bolts and Anchor Rods         b. Threaded rod not used for foundation         | Type<br>Test                           | By<br>LOR        | procedures noted in DSA IR 17-11.<br>Sample and test threaded rods not readily identifiable per procedures   |       | DIV: OF THE ST<br>APP: 04-1200                         | ATE ARCHITEC                                   |               |
| Page 8 of 11 DATE: 08/06/2021  | other than ASTM A706.<br>e. Inspect welding of reinforcing steel<br>23. ANCHOR BOLTS AND ANCHOR R<br>Test or Special Inspection<br>a. Anchor Bolts and Anchor Rods<br>b. Threaded rod not used for foundati<br>DSA 193-19 (Revised 07/16/2020) | Type<br>Test<br>tion anchorage. Test   | By<br>LOR<br>LOR | procedures noted in DSA IR 17-11.<br>Sample and test threaded rods not readily identifiable per procedures<br>noted in DSA IR 17-11.   |       | DIV. OF THE ST<br>APP: 04-1200<br>REVIEW<br>SS I FLS I | ATE ARCHITEC<br>D13 PC<br>PD FOR<br>ACS D CG [ |               |


INSPECTION ITEMS SEE THE DSA APPROVED 103 FOR THIS PROJECT.




















*⊾123* 

-


•

~~--~~

99.9

99.99

x-----x-----x--



- \_\_\_\_ = EASEMENT
  - = PROPERTY CORNER FOUND AS NOTED
  - = PROPERTY CORNER NOTHING FOUND OR SET
  - = TEMPORARY BENCHMARK (SEE TBM LIST FOR INFO)
- = SWALE OR DRAINAGE FLOW
  - = DRAINAGE FLOW = FENCE (TYPE NOTED)
  - = TREE (SIZE/TYPE INDICATED)

  - = SLOPE
- \_\_\_\_\_ 100 \_\_\_\_\_ = CONTOUR
  - = CONCRETE SURFACE
  - = EDGE OF ASPHALT = EDGE OF BUILDING
  - = SIGN
  - = POST OR BOLLARD
  - = GROUND ELEVATION
  - = HARD SURFACE ELEVATION

## FXISTING LITHITIES

| <u>EXISTIN</u>       | 1( | <u>g utilities</u>                                  |
|----------------------|----|---|
| 12"SD                | =  | STORM DRAIN LINE<br>(SIZE & DIRECTION OF FLOW)      |
| 12"SD                | =  | STORM DRAIN LINE<br>(RECORD INFORMATION)            |
| 12"SD                | =  | STORM DRAIN LINE                                    |
| SD                   | _  | (UNDERGROUND LOCATING)<br>STORM DRAIN MANHOLE       |
| 0                    |    | STORM DRAIN CLEANOUT                                |
|                      |    | DROP INLET  |
|                      |    | AREA DRAIN  |
| ∘ <i>RW</i> L        |    | RAIN WATER LEADER                                   |
| ∘ <i>DS</i>          |    | DOWNSPOUT   |
| 12 <b>*</b> SS       | =  | SANITARY SEWER LINE                                 |
| 12"SS                | _  | (SIZE & DIRECTION OF FLOW)<br>SANITARY SEWER LINE   |
|                      |    | (RECORD INFORMATION)                                |
| <u> </u>             | =  | SANITARY SEWER LINE<br>(UNDERGROUND LOCATING)       |
| 63                   | =  | SANITARY SEWER MANHOLE                              |
| Ø                    | =  | SANITARY SEWER CLEANOUT                             |
| — <i>w</i> —         | =  | WATER LINE (SIZE INDICATED)                         |
| - — -W— —            | =  | WATER LINE (RECORD INFORMATION)                     |
| — — <i>W</i> — —     | =  | WATER LINE (UNDERGROUND LOCATING)                   |
| $\bigotimes$         | =  | WATER MANHOLE                                       |
|                      | =  | WATER VALVE   |
| [wM]                 | =  | WATER METER   |
| W                    |    | WATER BOX   |
| Ø                    | =  | IRRIGATION CONTROL VALVE                            |
| Q                    | =  | FIRE HYDRANT  |
|                      |    | BACKFLOW PREVENTER                                  |
| Φ                    |    | SPRINKLER   |
| φ                    |    | HOSE BIBB   |
| — ОН - Е—<br>—— Е —— |    | OVERHEAD ELECTRIC LINE<br>UNDERGROUND ELECTRIC LINE |
| E<br>———E———         |    |   |
| -                    |    | UNDERGROUND ELECTRIC LINE<br>(RECORD INFORMATION)   |
| — —E— —              | =  | UNDERGROUND ELECTRIC LINE<br>(UNDERGROUND LOCATING) |
| E                    | =  | ELECTRIC MANHOLE                                    |
| -0-                  | =  | UTILITY POLE (WITH GUY WIRE)                        |
| EM                   | =  | ELECTRIC METER                                      |
| E                    | =  | ELECTRIC BOX  |
| 5LB                  | =  | STREET LIGHTING BOX                                 |
| □¤ <i>OR</i> ×       | =  | LIGHT STANDARD                                      |
|                      | =  | SIGNAL LIGHT  |
|                      |    | FLOOD LIGHT   |
|                      |    | ELECTRICAL OUTLET                                   |
|                      |    | GAS LINE (SIZE INDICATED)                           |
|                      |    | GAS LINE (RECORD INFORMATION)                       |
| -                    |    | GAS LINE (UNDERGROUND LOCATING)                     |
| -                    |    | GAS MANHOLE   |
|                      |    | GAS VALVE   |
|                      |    | GAS METER   |
|                      |    | TELEPHONE LINE (DECODD INFORMATION)                 |
|                      |    | TELEPHONE LINE (RECORD INFORMATION)                 |
|                      |    | TELEPHONE LINE (UNDERGROUND LOCATING                |
|                      | -  | STORM DRAIN BOX                                     |

= TRAFFIC SIGNAL BOX

TS

# A.P.N. 021-0342-028 BENCHMARK NO. <u>318–C3E</u> \_ ELEV. <u>35.095</u> HILTI NAIL LIGHT BASE SE CORNER 21ST AVENUE AND QUONSET DRIVE. TRM LIST

| NUMBE | ER DESCRIPTION          | NORTHING | EASTING  | ELEV  |
|-------|-------------------------|----------|----------|-------|
| 1     | CPS CHISELED "+"        | 10000.00 | 10000.00 | 38.99 |
| 2     | CPS PK+WASHER@4 SQ.     | 9537.59  | 10000.00 | 36.20 |
| 3     | CPS PK+WASHER           | 9791.13  | 9999.31  | 37.92 |
| 4     | CPS CHISELED "+"        | 9873.48  | 9999.56  | 39.06 |
| 5     | CPS CHISELED "+"        | 10000.37 | 9895.17  | 37.93 |
| 6     | CPS CHISELED "+"        | 9993.27  | 9725.14  | 35.57 |
| 7     | CPF BM318-C3E EL=35.095 | 9206.53  | 10359.58 | 35.10 |
|       |                         |          |          |       |

### CIVIL ABBREVIATIONS AND LEGEND

NOTE:

MAY BE

AR

AC

AD

APN

ARV

ASB

BO

BV

BW

C/L

CMP

CO

CR

CS

DC

DDC

DG

DIA

DIP

DS

FP

EX

FS

FDC

GRD

GV

HB

HP

INV

NTS

P/L

PUE

PVC

RCP

RIM

RP

RW SCH

SD

SG

SS

SDMH

SSMH

TDCB

TP

TRW

TSW

ΤW

UG

UON

VCP

w

W/

WV

W/0

STD S/W

HBD

HDPE

ESMT

DWG

CATV

COMM

CONC.

CONST.

CB

|  | LE                | GEND   |
|--|-------------------|--|
| ABBREVIATIONS  |                   | L SYMBOLS MAY                                |
| BE USED ON THESE PLANS.<br>AGGREGATE BASE                                  |                   | THESE PLANS.<br>& DRAINAGE SYMBOLS:          |
| ASPHALTIC CONCRETE<br>AREA DRAIN   | 8" SD             | STORM DRAIN LINE                             |
| ASSESSOR'S PARCEL NUMBER<br>AIR RELEASE VALVE                              |                   | (SIZE AND FLOW SHOWN)                        |
| AGGREGATE SUB-BASE<br>BLOW-OFF VALVE                                       |                   | STORM DRAIN MANHOLE<br>(SDMH)                |
| BUTTERFLY VALVE<br>BACK OF WALK  | <b>_</b>          | CATCH BASIN (CB)                             |
| CENTERLINE<br>CATCH BASIN  | <b>_</b>          | DROP INLET (DI)                              |
| CLASS<br>CORRUGATED METAL PIPE   | <b>_</b>          | AREA DRAIN (AD)                              |
| CABLE TELEVISION<br>CLEANOUT<br>COMMUNICATION                              | <b>_</b>          | PLANTER DRAIN (PD) OR<br>FLOOR DRAIN (FD)    |
| CONCRETE<br>CONSTRUCT  | <b>o</b> co       | STORM DRAIN CLEANOUT                         |
| CURB RETURN<br>CONCRETE SURFACE  | 99.99             | ELEVATION                                    |
| DOUBLE CHECK VALVE<br>DOUBLE DETECTOR CHECK VALVE                          | FF=100.00         | FINISHED FLOOR ELEVATION                     |
| DECOMPOSED GRANITE<br>DROP INLET   | PAD=99.33         | BUILDING PAD ELEVATION                       |
| DIAMETER<br>DUCTILE IRON PIPE  |                   | CONCRETE SIDEWALK                            |
| DRAWING<br>DOWNSPOUT<br>ELECTRIC   |                   | GRADED DIRECTION FOR<br>DRAINAGE FLOW        |
| EDGE OF PAVEMENT<br>EASEMENT   |                   | SWALE  |
| EXISTING<br>FIRE SERVICE LINE  | <b>•</b>          | SUOPE  |
| FIRE DEPARTMENT CONNECTION<br>FLOWLINE                                     |                   | TREE TO BE REMOVED                           |
| SANITARY SEWER FORCE MAIN<br>FINISHED FLOOR ELEVATION                      |                   | RETAINING WALL                               |
| FIRE HYDRANT<br>GAS  |                   | RETAINING WALL                               |
| GRATE ELEVATION<br>GRADE ELEVATION   | PROPOSED SANITARY |  |
| GATE VALVE<br>HOSE BIBB<br>HEADER BOARD                                    | <u>6" SS</u>      | SANITARY SEWER LINE<br>(SIZE AND FLOW SHOWN) |
| HIGH DENSITY POLYETHYLENE PIPE<br>HIGH POINT                               |                   | SANITARY SEWER<br>MANHOLE (SSMH)             |
| PIPE INVERT ELEVATION<br>JOINT UTILITY POLE<br>LINEAL FEET                 | <b></b> CO        | SEWER CLEANOUT<br>FLUSHER BRANCH             |
| LIP OF GUTTER<br>LEFT  | PROPOSED WATER SY | YMBOLS:                                      |
| MOWSTRIP<br>NOT TO SCALE   | —[8" W]—          | WATER LINE & SIZE                            |
| OVERHEAD<br>PORTLAND CEMENT CONCRETE                                       | [8" FS]           | FIRE LINE & SIZE                             |
| PLANTER DRAIN<br>POST INDICATOR VALVE                                      | [8" DW]           | DOMESTIC WATER LINE & SIZE                   |
| PROPERTY LINE<br>POWER POLE  | [8" RW]           | RECLAIMED WATER LINE & SIZE                  |
| PUBLIC UTILITY EASEMENT<br>POLYVINYL CHLORIDE                              | [8" IRR           | IRRIGATION SERVICE LINE & SIZE               |
| REINFORCED CONCRETE PIPE<br>RADIUS   | 8" NP             | NON POTABLE WATER LINE & SIZE                |
| MANHOLE RIM ELEVATION (SOLID COVER)<br>REDUCED PRESSURE BACKFLOW PREVENTER |                   | FIRE SPRINKLER SERVICE LINE & SIZE           |
| RIGHT OF WAY<br>SCHEDULE   |                   | GATE VALVE                                   |
| STORM DRAIN<br>STORM DRAIN MANHOLE   | M                 | WATER METER                                  |
| SUBGRADE ELEVATION<br>SANITARY SEWER                                       | €FH               | FIRE HYDRANT ASSEMBLY                        |
| SANITARY SEWER MANHOLE<br>STANDARD   | Y FDC             | FIRE DEPARTMENT CONNECTION                   |
| SIDEWALK<br>TELEPHONE  | DC                | DETECTOR CHECK VALVE                         |
| TOP OF CURB<br>TRENCH DRAIN  | DDC               | DOUBLE DETECTOR CHECK VALVE                  |
| TRENCH DRAIN<br>TRENCH DRAIN CATCH BASIN<br>TELEPHONE POLE                 | RP                | REDUCED PRESSURE                             |
| TOP OF RAMP ELEVATION<br>TOP OF RETAINING WALL                             |                   | BACKFLOW PREVENTER                           |
| TOP OF RETAINING WALL<br>TOP OF SEAT WALL<br>TOP OF WALK ELEVATION         |                   | BUTTERFLY VALVE                              |
| UTILITY<br>UNDERGROUND   | <b>↓</b> 1"       | AIR RELEASE VALVE + SIZE                     |
| UNDERGROUND<br>UNIESS OTHERWISE NOTED                                      | <b>_</b> 1"       | BLOW-OFF VALVE + SIZE                        |

UNLESS OTHERWISE NOTED VITRIFIED CLAY PIPE WATER

WITHOUT WATER VALVE

WITH

# SHALL BE IMMEDIATELY NOTIFIED FOR DIRECTIONS.

- 2. NO BURNING OR BLASTING SHALL BE PERMITTED. ADDITIONAL DEMOLITION INFORMATION MAY BE SHOWN ON THE GRADING, DRAINAGE, AND UTILITY PLANS, AND THOSE PLANS PREPARED BY OTHER DISCIPLINES FOR THIS PROJECT.
- 4. ALL DEMOLISHED ITEMS SHALL BE DISPOSED OF OFFSITE AT A SUITABLE, LEGAL, DUMP SITE OR OTHER FACILITY.
- 5. ALL DISPOSED OF MATERIALS SHALL BE RECYCLED IF POSSIBLE.
- 6. THE TYPES, LOCATIONS, SIZES AND/OR DEPTHS OF EXISTING UNDERGROUND UTILITIES AS SHOWN IN THESE PLANS WERE OBTAINED FROM EFFORT HAS BEEN MADE TO LOCATE AND DELINEATE ALL KNOWN UNDERGROUND UTILITIES. HOWEVER, WARREN CONSULTING ENGINEERS CAN
- EXTEND.
- NOTED OTHERWISE.
- FROM DAMAGE DURING CONSTRUCTION.
- TO BE REMOVED SHALL REMAIN AND BE PROTECTED.

# UTILITY VERIFICATION NOTE DIRECTION.

IRRIGATION DEMOLITION NOTE WITHIN LANDSCAPE AREAS TO BE DEMOLISHED THERE MAY BE EXISTING IRRIGATION LINES NOT SHOWN ON THIS PLAN. CONTRACTOR SHALL REMOVE LATERAL LINES AND HEADS ENCOUNTERED. MAIN LINES AND CONTROL WIRES MAY ONLY BE REMOVED PROVIDED THAT ROUTING IS KNOWN AND REMOVAL WILL NOT DEACTIVATE AN IRRIGATION SYSTEMS INTENDED TO REMAIN. IF CONFLICT IS FOUND, CONTACT THE ENGINEER FOR DIRECTION.

BLOW-OFF VALVE + SIZE POST INDICATOR VALVE

### DEMOLITION GENERAL NOTES

IN THE EVENT THAT ANY UNUSUAL CONDITIONS NOT COVERED BY THE GEOTECHNICAL INVESTIGATION REPORT OR ARE ENCOUNTERED DURING GRADING OPERATIONS THE GEOTECHNICAL ENGINEER AND THE ARCHITECT

SOURCES OF VARYING RELIABILITY. THE CONTRACTOR IS CAUTIONED THAT ONLY ACTUAL EXCAVATION WILL REVEAL THE TYPES, EXTENT, SIZES, LOCATIONS, AND DEPTHS OF SUCH UNDERGROUND UTILITIES. A REASONABLE

ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF ITS DELINEATION OF SUCH UNDERGROUND UTILITIES, NOR FOR THE EXISTENCE OF OTHER BURIED OBJECTS OR UTILITIES WHICH MAY BE ENCOUNTERED BUT WHICH ARE NOT SHOWN ON THESE DRAWINGS. THE CONTRACTOR OR ANY SUBCONTRACTOR FOR THIS CONTRACT SHALL NOTIFY THE DISTRICT TWO (2) WORKING DAYS IN ADVANCE OF PERFORMING ANY EXCAVATION WORK IN ORDER TO VERIFY TO THE GREATEST EXTENT POSSIBLE THE EXISTING UTILITY LINES, CONFLICTS AND PROPOSED UTILITY CONNECTION POINTS.

7. THE SCHOOL DISTRICT SHALL HAVE SALVAGE RIGHTS TO ANY DEMOLISHED ITEMS SHOWN HEREON. THE CONTRACTOR SHALL GIVE THE DISTRICT NOTICE 7 DAYS PRIOR TO THE START OF DEMOLITION. THE DISTRICT SHALL MOVE ANY RETAINED ITEMS OUT OF THE CONTRACTORS WORK AREA. UNLESS ANOTHER ARRANGEMENT IS MADE WITH THE CONTRACTOR. ANY REMAINING ITEMS BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE. ANY ITEMS NOT SHOWN FOR REMOVAL SHALL REMAIN AND SHALL BE PROTECTED FROM DAMAGE DURING CONSTRUCTION TO A REASONABLE

8. EXISTING UTILITY STRUCTURES IN AREAS OF NEW PAVING SHALL BE REMOVED AND REPLACED WITH NEW BOX/COVER AT NEW GRADE UNLESS SPECIFICALLY

9. ITEMS OUTSIDE THE LIMITS OF DEMOLITION SHALL REMAIN AND BE PROTECTED

10. EXISTING UTILITY STRUCTURES AND PIPING NOT SHOWN ON DEMOLITION PLAN

PRIOR TO THE START OF CONSTRUCTION. VERIFY AND POTHOLE ALL UTILITY POINTS OF CONNECTION FOR LOCATION, DEPTH, AND SIZE. IF CONFLICT IS FOUND, CONTACT THE ENGINEER IMMEDIATELY FOR

### GENERAL NOTES:

APPLICATION.

1. THE TYPES, LOCATIONS, SIZES, AND/OR DEPTHS OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THESE PLANS WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. THE CONTRACTOR IS CAUTIONED THAT ONLY ACTUAL EXCAVATION WILL REVEAL THE TYPES, EXTENT, SIZES, LOCATIONS AND DEPTHS OF SUCH UNDERGROUND UTILITIES. A REASONABLE EFFORT HAS BEEN MADE TO LOCATE AND DELINEATE ALL KNOWN UNDERGROUND UTILITIES. HOWEVER. WARREN CONSULTING ENGINEERS CAN ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF ITS DELINEATION OF SUCH UNDERGROUND UTILITIES, NOR FOR THE EXISTENCE OF OTHER BURIED OBJECTS OR UTILITIES WHICH MAY BE ENCOUNTERED BUT WHICH ARE NOT SHOWN ON THESE PLANS. THE CONTRACTOR OR ANY SUBCONTRACTOR FOR THIS CONTRACT SHALL NOTIFY MEMBERS OF UNDERGROUND SERVICE ALERT (USA) TWO (2) WORKING DAYS IN ADVANCE OF PERFORMING ANY EXCAVATION WORK BY CALLING TOLL FREE 1-800-227-2600, OR 811.



- 2. WARREN CONSULTING ENGINEERS, INC. (WCE) ASSUMES NO RESPONSIBILITY FOR ERRORS IN PHYSICAL LOCATION OF IMPROVEMENTS, HORIZONTAL OR VERTICAL, IF STAKED BY OTHERS. IN ADDITION, ANY SUCH ERRORS IN PHYSICAL LOCATION MAY AFFECT THE INTENDED DESIGN OF SUCH IMPROVEMENTS AND WCE CANNOT BE HELD RESPONSIBLE FOR SUCH CONDITIONS WHICH ARE A RESULT OF ERRORS IN SURVEYING, OR IMPROPER CONSTRUCTION.
- 3. IF SUBSURFACE CULTURAL RESOURCES, REMAINS, AND/OR ARTIFACTS ARE UNCOVERED DURING PROJECT CONSTRUCTION, ALL WORK IN THE VICINITY SHALL BE STOPPED UNTIL SUCH ITEMS CAN BE ASSESSED BY AN APPROPRIATE MEMBER OF THE COUNTY ENVIRONMENTAL IMPACT SECTION STAFF.
- 4. CONTRACTOR AGREES THAT HE/SHE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY: THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND SHALL NOT BE LIMITED TO NORMAL WORKING HOURS: AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER AND ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT. EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.
- 5. THE CONTRACTOR SHALL OBTAIN AN EXCAVATION PERMIT FROM THE STATE OF CALIFORNIA DEPARTMENT OF INDUSTRIAL SAFETY FOR ALL EXCAVATIONS OF 5 FEET OR MORE IN DEPTH.
- 6. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO MAKE ALL NECESSARY PRE-BID AND PRE-CONSTRUCTION SITE INSPECTION, AND/OR OBSERVATIONS ON THE SITE TO PRE-DETERMINE ALL HIS/HER MEANS AND METHODS NECESSARY TO COMPLETE THE IMPROVEMENTS SHOWN ON THESE PLANS AND PER THE PROJECT SPECIFICATIONS. IT IS THE CONTRACTORS RESPONSIBILITY TO DETERMINE, AND INCLUDE IN HIS/HER CONTRACT, ALL MEANS AND METHODS NECESSARY TO PERFORM A COMPLETE AND ACCEPTABLE JOB.
- 7. WHERE IMPROVEMENTS LIE WITHIN AN EXISTING DEVELOPED AREA, CONTRACTOR SHALL USE CAUTION WHEN ACCESSING THE SITE THROUGH THESE EXISTING IMPROVEMENTS. IT IS THE CONTRACTORS RESPONSIBILITY TO PROTECT ANY SUCH EXISTING IMPROVEMENTS OUTSIDE THE PROJECT BOUNDARY, OR EXISTING IMPROVEMENTS WITHIN THE BOUNDARY WHICH ARE TO REMAIN. PROPER PRECAUTIONS SHALL BE PROVIDED AND MAINTAINED THROUGHOUT CONSTRUCTION. ANY DAMAGE SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE OWNER.
- 8. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO KEEP DETAILED RECORDS OF MINOR CHANGES OR ADJUSTMENTS MADE DURING CONSTRUCTION (WHICH WERE NOT FORMALLY ISSUED). UPON PROJECT COMPLETION, THESE RECORDS AND/OR INFORMATION SHALL BE PROVIDED TO THE OWNER AND WARREN CONSULTING ENGINEERS. INC. UNLESS AN OFFICIAL "AS-BUILT" SET OF PLANS IS A REQUIREMENT OF THE CONTRACT. IF AS-BUILT PLANS ARE A REQUIREMENT OF THE CONTRACT, REFER TO SPECIFICATIONS FOR AS-BUILT DELIVERABLE REQUIREMENTS.
- 9. IN VEHICULAR PATHWAYS, EXISTING ASPHALTIC AND/OR CONCRETE SURFACES SHALL BE CUT TO A NEAT AND STRAIGHT LINE, PARALLEL OR PERPENDICULAR TO THE VEHICULAR TRAVELED PATH. THIS IS TYPICALLY THE ROADWAY CENTERLINE, BUT MAY VARY. THAT SAWCUT EDGE SHALL BE PROTECTED FROM DAMAGE DURING CONSTRUCTION SO A CLEAN EDGE REMAINS FOR PATCH BACK .. IF EDGE IS DAMAGED, A NEW SAW CUT WILL BE REQUIRED. THE EXPOSED EDGE SHALL BE "TACKED" WITH EMULSION PRIOR TO PAVING.
- 10. NO BURNING OR BLASTING SHALL BE ALLOWED ONSITE UNLESS SPECIFICALLY ADDRESSED ON PLANS, OR SPECIFICALLY APPROVED AND COORDINATED WITH THE ARCHITECT, ENGINEER, AND LOCAL AGENCY OR OTHER ADMINISTRATIVE AUTHORITY.
- 11. SUBGRADE AND RESULTING FINISHED GRADE SHALL BE CONSTRUCTED SMOOTH AND UNIFORM BETWEEN SPOT ELEVATIONS, CONTOURS OR OTHER STRUCTURE ELEVATIONS SHOWN ON GRADING OR OTHER PLANS. NO MOUNDS, RUTS, DEPRESSIONS OR OTHER GRADING DEFICIENCIES WILL BE ALLOWED UNLESS SPECIFICALLY SHOWN ON PLANS.
- 12. ON NEW WATER SYSTEMS, SERVICE LATERALS SHALL BE MADE USING APPROPRIATE "TEE" AND "WYE" FITTINGS. SADDLE TAPS WILL ONLY BE ALLOWED WHEN MAKING CONNECTIONS TO EXISTING WATER MAINS.
- 13. CURING COMPOUND SHALL BE APPLIED IN A CONTINUOUS SOLID WET FLOWING COAT. ANY "SPOTTY" APPLICATIONS SHALL BE RECOATED IMMEDIATELY. APPLICATION SHALL BE INSPECTED BY PROJECT INSPECTOR DURING
- 14. EMBEDMENT OF FEATURES IN CONCRETE PAVING, CURBS, OR WALLS, SUCH AS SQUARE OR ROUND TUBING, POSTS, OR COLUMNS, STEEL BOLTED PLATES, OR OTHER STRUCTURES, SHALL REQUIRE ADDITIONAL SCORE OR EXPANSION JOINTS TO PREVENT UNCONTROLLED CRACKING. THOSE ADDITIONAL JOINTS MAY OR MAY NOT BE SPECIFICALLY SHOWN ON PLANS BUT SHALL BE PROVIDED BY THE CONTRACTOR.
- 15. EMBEDMENT OF FEATURES IN CONCRETE PAVING, CURBS, OR WALLS, SUCH AS SQUARE OR ROUND TUBING, POSTS, OR COLUMNS, STEEL BOLTED PLATES, OR OTHER STRUCTURES, SHALL REQUIRE A MINOR ADJUSTMENT OF REBAR WITHIN CONCRETE TO ALLOW FOR SUCH STRUCTURE. THAT REBAR ADJUSTMENT MAY NOT BE SPECIFICALLY SHOWN ON PLANS. 16. NO MORE THAN 1 GALLON OF WATER PER YARD OF CONCRETE CAN BE ADDED TO THE TRUCK AFTER ARRIVAL TO
- PROJECT SITE. THE ADDITION OF WATER CAN ONLY BE ADDED UNDER THE SUPERVISION OF THE CONCRETE INSPECTOR OR LABORATORY TECHNICIAN. 17. WHEN PUMPING CONCRETE FOR PLACEMENT, ABSOLUTELY NO WATER IS TO BE ADDED TO PUMP HOPPER. ANY
- WATER ADDED TO HOPPER WILL BE REASON FOR CONCRETE REJECTION AT THE CONTRACTORS EXPENSE.
- 18. ALL CONTRACTION/CONSTRUCTION JOINTS "CJ" SHALL BE 1/4 THE SLAB THICKNESS DEEP, BUT NO LESS THAN 1" FOR CONTROLLING OF CRACKING. CONTRACTOR SHALL EXERCISE CAUTION WHEN FINAL TROWELING OF CONCRETE SO AS NOT TO FILL IN THESE JOINTS WITH CONCRETE CREAM. ANY CRACKS OUTSIDE OF JOINTS WHICH WERE CONSTRUCTED LESS THAN 1" DEEP, SHALL BE CAUSE FOR CONCRETE SLAB(S) TO BE REMOVED AND REPLACE AT CONTRACTORS EXPENSE.
- 19. ANY SCREED BOARDS SET WITHIN CONCRETE SLABS SHALL BE AN "OVERHEAD SCREED" SO THERE IS NO INTERFERENCE WITH THE PLACEMENT AND ALIGNMENT OF SLAB REINFORCING.
- 20. 3-1/2" FELT JOINTS WILL NOT BE ACCEPTED. PROVIDE A FULL 4" FELT JOINT FOR 4" SLAB CONSTRUCTION, AND A 6" FELT JOINT FOR A 6" SLAB SLAB CONSTRUCTION.
- 21. SHOULD ANY SHRINKAGE CRACKS OCCUR OUTSIDE OF EITHER THE EXPANSION JOINTS OR CRACK CONTROL JOINTS, THEN THE CONCRETE SLAB SHALL BE SAWCUT AT THE NEAREST JOINTS ON EACH SIDE OF THE CRACK AND THE CONCRETE SECTION SHALL BE, REMOVED AND REPLACED. NEW CONCRETE SHALL BE DOWELED INTO EXISTING CONCRETE PER DRAWING DETAIL.
- 22. ALL AREAS DISTURBED BY GRADING OPERATIONS WHETHER SHOWN ON THE DRAWINGS OR NOT SHALL BE HYDRO SEEDED UNLESS OTHERWISE NOTED. HYDRO SEEDING SHALL CONFORM TO LOCAL CITY/COUNTY STANDARDS.
- 23. REPAIR OR PATCHING OF GALVANIZED METALS, SUCH AS AFTER WELDING GALVANIZED COMPONENTS, SHALL BE MADE USING A ZINC COMPOSITION "HOT STICK" APPLICATION PER ASTM A 780-01. GALVANIZING PAINTS WILL NOT BE ALLOWED.

## **GENERAL PAVING SURFACE NOTES:**

- 1. PROVIDE EQUIVALENT OF MEDIUM BROOM FINISH AT SLOPES UP TO 5.99%, TYPICAL. PROVIDE EQUIVALENT OF HEAVY BROOM FINISH AT SLOPES 6% AND GREATER. REFER TO SPECIFICATIONS.
- 2. ALL NEW PEDESTRIAN WALKWAYS (NON-RAMP) SHALL BE SLOPED NO GREATER THAN 2.0%, AND NO LESS THAN 0.75% IN ANY DIRECTION, UNLESS SPECIFICALLY LABELED OTHERWISE. ALL CONCRETE SHALL MEET THE FOLLOWING SLOPE REQUIREMENTS: - NO GREATER THAN 5% SLOPE IN THE DIRECTION OF TRAVEL.
- NO GREATER THAN 2% SLOPE CROSSING THE DIRECTION OF TRAVEL. - NO GREATER THAN 2% SLOPE IN ANY DIRECTION IN COURTYARD OR PLAZA AREAS.

### CIVIL SHEET INDEX

- CO.1 CIVIL GENERAL NOTES AND ABBREVIATIONS
- C1.1 DEMOLITION PLAN


 $\sqrt{0}$ 

C2.1 GRADING AND PAVING PLAN

### LANDSCAPE/IRRIGATION NOTE:

GENERAL CONTRACTOR IS REQUIRED TO HIRE A LANDSCAPE SUBCONTRACTOR TO PERFORM ALL LANDSCAPE AND IRRIGATION REPAIRS


\_\_\_\_\_



ALL FEATURES, NOTES AND DIMENSIONS NOT SPECIFICALLY SHOWN OR NOTED AS CHANGED SHALL REMAIN AS SHOWN ON PREVIOUSLY ISSUED DOCUMENTS.








|   |          | ADDE            |            |
|---|----------|-----------------|------------|
| ILARGED PLAN  | A1.1.2   | DATE:           | 04/29/22   |
| ADE STRUCTURE AT NEW JOSEPH<br>NNHEIM ELEMENTARY SCHOOL |          | PROJECT<br>NO.: | 21-1504.04 |
| CRAMENTO CITY UNIFIED SCHOOL [                          | DISTRICT | SHEET:          |            |
| CRAMENTO, CA<br>A APP.02-119976                         |          | A               | 0.03       |
|   |          |                 |            |


C-14648


5/31/23 RENEWAL DATE





- **SHEET NOTES:** 1. ALL EXISTING EQUIPMENT, DEVICES, CONDUIT AND WIRING, ETC., SHOWN ON PLANS ARE BASED ON AVAILABLE EXISTING DRAWINGS AND LIMITED
- SITE SURVEYS, AND SHOWN FOR CLARITY ONLY. 2. SEE ONE LINE DIAGRAM AND PANEL SCHEDULE ON SHEET <u>E2.1</u> FOR REFERENCE.


- KEYED NOTES: PROVIDE TRENCH FOR 24 INCH MINIMUM COVER. LOCATE AND PROTECT (E) UTILITIES, I.E. IRRIGATION, SEWER, DRAINAGE PIPES, ETC. SAW CUT AND PATCH BACK (E) ASPHALT. PROVIDE SAND TO COVER CONDUIT TO SIX(6) INCHES, THEN ADD TRACER TAPE. COMPLETE BACKFILL TO GRADE, COMPACTING IN SIX(6)-INCH LIFTS. FINISH TO MATCH EXISTING. SEE DETAIL <u>3/E3.1.</u>
- 2> CONDUIT TO PENETRATE WALL. PATCH BACK TO MATCH (E) BUILDING CONSTRUCTION.
- 3 RUN CONDUIT HIGH AS CLOSE TO EAVE AS POSSIBLE AND PENETRATE WALL. DROP CONDUIT TO BELOW ASPHALT AND TRENCH TO SHADE LOCATION, INTERCEPTING THE CHRISTY BOX ALONG THE WAY. PAINT EXPOSED CONDUIT TO MATCH (E) FINISH.
- 4 PROVIDE AT MINIMUM TWO(2) GROUND RODS, ONE AT THE PULL BOX AND
- PROVIDE AT MINIMUM TWO(2) GROUND RODS, ONE AT THE PULL BOX AND ONE NEAR THE CORNER POST OF THE SHADE STRUCTURE, EACH 5/8" BY TEN(10) FEET LONG, CU, AT LEAST TEN(10) FEET APART. BOND TO METAL OF SHADE STRUCTURE. SEE DETAILS <u>5/E3.1</u> AND <u>2/E3.1</u>.
   LOCKABLE, WEATHERPROOF RECEPTACLE TO HAVE A TWO-GANG BACK BOX WITH 1" THREADED PORT(S). MOUNT RECEPTACLES 36" ABOVE GRADE UNLESS SPECIFIED OTHERWISE. SEE DETAIL <u>4/E3.1</u>.
- 6 PROVIDE 8" BY 6" BY 4" NEMA 3R PULL BOX.
- 7 PROVIDE CHRISTY B1324 PULL BOX WITHIN FIVE(5) FT OF SHADE STRUCTURE. CHRISTY BOX TO HAVE HOLD DOWN BOLTS AND BE LABELED FOR POWER.
- B RUN CONDUIT BELOW SHADE STRUCTURE CONCRETE PAD. L'and the second second











# **Statement of General Conformance**

THE FOLLOWING DRAWINGS OR SHEETS LISTED ON THE COVER OR INDEX SHEET HAVE BEEN PREPARED BY OTHER DESIGN PROFESSIONALS OR CONSULTANTS WHO ARE LICENSED AND/OR AUTHORIZED TO PREPARE SUCH DRAWINGS IN THIS STATE. IT HAS BEEN EXAMINED BY ME FOR:

1) DESIGN INTENT AND APPEARS TO MEET THE APPROPRIATE REQUIREMENTS OF TITLE 24, CALIFORNIA CODE OF REGULATIONS AND THE PROJECT SPECIFICATIONS PREPARED BY ME, AND

2) COORDINATION WITH MY PLANS AND SPECIFICATIONS AND IS ACCEPTABLE FOR INCORPORATION INTO THE CONSTRUCTION OF THIS PROJECT.

THE STATEMENT OF GENERAL CONFORMANCE "SHALL NOT BE CONSTRUED AS RELIEVING ME OF MY RIGHTS, DUTIES, AND RESPONSIBILITIES UNDER SECTIONS 17302 AND 81138 OF THE EDUCATION CODE AND SECTIONS 4-336, 4-341, AND 4-344" OF TITLE 24, PART 1. (TITLE 24, PART 1, SECTION 4-317 (b))

NQ

4/21/22

SIGNATURE

DATE

ARCHITECT OR ENGINEER DESIGNATED TO BE IN GENERAL RESPONSIBLE CHARGE

Jeffrey Grau

PRINT NAME

C-14648 05/31/23

LICENSE NUMBER EXPIRATION DATE

LIST COMPLETELY, ITEMS REVIEWED AND ACCEPTED:

PC SHADE STRUCTURE

| DESIGN CRITERIA   |   |
|---|---|
| DESCRIPTION   | DESIGN VALUES                                 |
| DEAD AND LIVE LOADS   |   |
| ROOF LIVE LOAD  | 20 PSF  |
| ROOF DEAD LOAD (SUPERIMPOSED ON FRAME)  | 5 PSF MAX                                     |
| ROOF PANEL DEAD LOAD  | M=1.1 PSF, G = 1.2 PSF, S = 1.3 PSF           |
| COLLATERAL DEAD LOAD  | M = 3.9 PSF, G = 3.8 PSF, S =3.7 PSF          |
| ROOF SNOW LOAD  |   |
| GROUND SNOW LOAD, Pg  | 20 PSF  |
| RISK CATEGORY   | II  |
| ROOF SNOW LOAD: SLOPED, P <sub>s</sub>  | 20 PSF  |
| SITE APPLICATION DSA REVIEWER SHALL VERIFY THE STRUCTURE BE LOCATED   |   |
| SNOW LOAD SLOPE FACTOR, C <sub>s</sub>  | 1.0   |
| SNOW EXPOSURE FACTOR, C <sub>e</sub>  | 1.0   |
| SNOW LOAD IMPORTANCE FACTOR, $I_s$  | 1.0   |
| THERMAL FACTOR, Ct  | 1.2   |
| WIND DESIGN   |   |
| BASIC WIND SPEED (3 SECOND GUST), V <sub>ult</sub>  | 100 MPH                                       |
| RISK CATEGORY   | ll ll   |
| EXPOSURE CATEGORY   | С   |
| FACTORS: K <sub>z</sub> , K <sub>zt</sub> , K <sub>d</sub>  | 0.85, 1, 0.85                                 |
| $q_{h} = 0.00256 \text{ K}_{z} \text{ K}_{d} \text{ V}^{2} \text{ FOR ALL EAVE HEIGHTS (8', 10' & 12')}$                            | 18.50 PSF                                     |
| C <sub>NW</sub> PER ASCE FIGURE 27.4-5 ROOF ANGLE 18.43 - CLEAR / OBSTRUCTED  | CASE A (1.1 / -1.2) CASE B (0.01 / -0.69)     |
| $C_{NL}$ PER ASCE FIGURE 27.4-5 ROOF ANGLE 18.43 - CLEAR / OBSTRUCTED   | CASE A (-0.17 / -1.09) CASE B (-0.96 / -1.65) |
|   |   |
| C <sub>N</sub> PER ASCE FIGURE 27.4-7 PARALLEL TO RIDGE - CLEAR / OBSTRUCTED  | CASE A (-0.6 / -0.9) CASE B (-0.5 / -0.5)     |
| COMPONENTS & CLADDING - $C_N$ ( PRESSURE/SUCTION) CLEAR / OBSTRUCTED  | ZONE 3 - (2.29 / -2.11) / (1.0 / -3.0)        |
|   | ZONE 2 - (1.77 / -1.63) / (0.8 / -2.3)        |
| SEISMIC DESIGN  | ZONE 1 - (1.15 / -1.05) / (0.5 / -1.5)        |
| LATERAL FORCE RESISTING SYSTEM  | STEEL - ORDINARY CANTILEVER COLUMN            |
| ANALYSIS PROCEDURE  | EQUIVALENT LATERAL FORCE                      |
| SESIMIC IMORTANCE FACTOR, le  | 1.0   |
| SEISMIC SITE CLASS  | D   |
| MCE <sub>R</sub> SPECTRAL RESPONSE ACCELERATION @ 0.2 s, S <sub>s</sub>   | 2.60  |
| MCE <sub>R</sub> SPECTRAL RESPONSE ACCELERATION @ 0.2 s, S <sub>1</sub>   | 0.90  |
| SHORT PERIOD SITE COEFFICIENT, Fa   | 1.20  |
| LONG PERIOD COEFFICIENT, F <sub>v</sub>   | 1.70  |
| FUNDAMENTAL PERIOD OF THE STRUCTURE, T  | 0.152 s                                       |
| TONDAMENTALTERIOD OF THE STRUCTURE, I   | 0.102.3                                       |
| DESIGN SPECTRAL RESPONSE ACCELERATION AT SHORT PERIOD, $S_{DS}$   | 2.08  |
|   | 2100  |
| DESIGN SPECTRAL RESPONSE ACCELERATION AT SHORT PERIOD, SDS - USED   | 2.08 * 0.70 = 1.456                           |
| TO DETERMINE Cs (WITH CAP PER ASCE-7 12.8.1.3)  |   |
|   |   |
| DESIGN SPECTRAL RESPONSE ACCELERATION AT 1-S PERIODS, SD1   | 1.02  |
| SEISMIC DESIGN CATEGORY   | E   |
| RESPONSE MODIFICATION FACTOR, R   | 1.25  |
| OVERSTRENGTH FACTOR, Ω  | 1.25  |
| REDUNDANCY FACTOR, ρ  | 1.0   |
| HORIZONTAL OR VERTICAL IRREGULARITIES   | NONE  |
| SEISMIC RESPONSE COEFFICIENT, Cs (20' WIDE, 30' WIDE, 40' WIDE)   | 1.16,   |
| DESIGN BASE SHEAR, V (20' WIDE, 30' WIDE, 40' WIDE)   | 12.73 PSF, 13.41 PSF, 14.65 PSF               |
| ALLOWABLE SOIL BEARING FOR FOUNDATIONS  | VARIES - SEE FOUNDATION CHARTS                |
|   |   |
| ELOOD DESIGN - DESIGN IS ASSUMED TO NOT BE IN ELOOD HAZARD AREA   |   |
| FLOOD DESIGN - DESIGN IS ASSUMED TO NOT BE IN FLOOD HAZARD AREA   |   |
| FLOOD DESIGN - DESIGN IS ASSUMED TO NOT BE IN FLOOD HAZARD AREA<br>IF PROJECT IS LOCATED IN A FLOOD ZONE OTHERTHAN ZONE X, A LETTER |   |
|   |   |

STRUCTURAL SEPARATION

ALLOWABLE SOIL VALUES SPECIFIED

| ALL DEFLECTIONS SHOWN ALSO INCLUDE THE P-D  | DELTA ROTATION PER IR PC-7 |              | IONS ARE FOR (1) ST<br>CLASSES PER CBC TABLE 18 |                 |
|---|----------------------------|--------------|---|-----------------|
| MAXIMUM DRIFT $\delta_{max}$ SIDE COLUMNS   |                            | Soil Class 5 | <u>Soil Class 4</u>                             | <u>Soil C</u> a |
| 20 WIDE (O' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)  | (INCHES)                   | 2.40         | 2.55  | 2.6             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)   | (INCHES)                   | 2.25         | 2.35  | 2.4             |
| MINIMUM SEPARATION ( $\delta_m = C_d \delta_{max}$ ) $C_d = 1.25$   |                            | 2.20         | 2.25  | 2.2             |
| 20' WIDE (O' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)-  | (INCHEO)                   | 0.00         | 3.19  | 3.3             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)   | (INCHES)                   | 2.81         | 2.94  | 3.0             |
| 10' WIDE (0' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)-  | (INCHES)                   | 2.75         | 2.81  | 2.7             |
| MAXIMUM DRIFT $\delta_{max}$ CORNER COLUMNS   |                            | Soil Class 5 | Soil Clars 4                                    | Soi Cl          |
| 20' WIDE (O' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)-  | (INOLIEC)                  | 2.20         | 43  | 2.4             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)   | (INCHES)                   | 2.30         | 245   | <b>k</b> 9      |
| 10' WHEE (0' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)<br>MINIMUM SEPARATION ( $\delta_m = C_d \delta_{max}$ ) C <sub>d</sub> = 1.25 | (INCHEC)                   | 2.40         | 2.65  | ¥               |
| 20' WIDE (0' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)-  | (INGHES)                   | 2.75         | 1   | A               |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)   | (INCHES)                   | 2.88         | <b>5</b> .06                                    | <u>k</u>        |
| 40 WIDE (0 EAVE HT, 10 EAVE HEIGHT, 12 EAVE HT)-  | (INCHES)                   | 5.66         | 3.19  | 3.3             |
| MAXIMUM DRIFT $\delta_{max}$ END COLUMNS  |                            | Soil Class 5 | <u>Sci Class 4</u>                              | Sai Ci          |
| 20 WIDE (O' EAVE HIT, 10' EAVE HEIGHT, 12' EAVE HT)-  | (INCHES)                   | 1.00         | 1.70  | 1.7             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)   | (INCHES)                   | 2.00         | 2.45  | 2.2             |
| 40 WIDE (0 EAVE HT, 10 EAVE HEIGHT, 12 EAVE HT) MINIMUM SEPARATION ( $\delta_m = C_d \delta_{max}$ ) $C_d = 1.25$                 | (INCHES)                   | 2.50         | 2.30  | 2.8             |
|   | (INOHES)                   | 2.00         | 2.13  | 2.1             |
| 30' WIDE (8' EAVE HT, 10' EAVE HEIGHT, 12' EAVE HT)   | (INCHES)                   | 2.50         | 3.06  | 2.8             |
| 40' MIDE (8' EAVE HT, 10' EAVE HEICHT, 12' EAVE HT)   | (INCHES)                   | 2.12         | 2.88  | 3.5             |

| ARCHITEC TURAL REQUIREMENTS |   |
|-----------------------------|---|
| DESCRIPTION                 | DESIGN VAULES                             |
| TYPE OF CONSTRUCTION        | II-B                                      |
| OCCUPANCY CLASSIFICATION    | A-3                                       |
| NUMBER OF STORIES           | 1   |
| FIRE SPRINKLER SYSTEM       | NOT BY ICON/WEIGHT NOT INCLUDED IN DESIGN |

RELATED BUILDING CODES AND STANDARDS

| TITLE 24 CODES:   |
|---|
| 2019 CALIFORNIA ADMINISTRATIVE CODE (CAC)(PART 1, TITLE 24, CCR)<br>2019 CALIFORNIA BUILDING CODE (CBC), VOLUMES 1, AND 2.(PART 2, TITLE 24,<br>CCR)  |
| 2019 CALIFORNIA ELECTRICAL CODE(PART 3, TITLE 24, CCR)<br>2019 CALIFORNIA MECHANICAL CODE (CMC)(PART 4, TITLE 24, CCR)<br>2019 CALIFORNIA PLUMBING CODE (CPC)(PART 5, TITLE 24, CCR)<br>2019 CALIFORNIA ENERGY CODE(PART 6, TITLE 24, CCR)<br>2019 CALIFORNIA FIRE CODE (CFC) |
| REFERENCE CODE SECTIONS FOR APPLICABLE STANDARDS:<br>2019 CBC, CHAPTER 35<br>2019 CFC, CHAPTER 80   |
| SCOPE OF WORK NARRATIVE   |

THESE DRAWINGS ILLUSTRATE THE FABRICATION AND INSTALLATION REQUIREMENTS FOR A FREE-STANDING PREFABRICATED STEEL SHADE STRUCTURE. THE ENTIRE STRUCTURAL SYSTEM IS COMPRISED OF HOLLOW STRUCTURAL STEEL MEMBERS SUPPORTED BY CONCRETE FOUNDATIONS. THE FLEXIBILITY INCLUDED HEREIN ALLOWS THE STRUCTURE TO COMPLY WITH A WIDE VARIETY OF PROJECT SITES AND LOADING REQUIREMENTS.

### <u>GENERAL:</u>

- WITH ANY WORK INVOLVED.

- 6. ASTM DESIGNATIONS AND ALL STANDARDS REFER TO THE LATEST AMENDMENTS.
- ARCHITEC T/ENGINEER OR OWNER.
- INSTALLATION.
- STRUCTURAL AND MISCELLANEOUS STEEL:
- CALIFORNIA BUILDING CODE.
- DRAWINGS (MAXIMUM INCREASE OF 1/8").

- 10.ALL ROOF DECKS SHALL CONFORM TO ASTM A-792, Fy = 50 KSI.

INSTRUCTIONS FOR ARCHITECTS SUBMITTING THESE PRE-CHECKED DRAWING TO DSA: BEFORE SUBMITTING THESE PRE-CHECKED DRAWINGS FOR YOUR PROJECT, FOLLOW THE STEPS BELOW TO PROPERLY DEFINE THE APPROVED OPTIONS: STEP 1: SELECT FRAME DIMENSIONS FOR YOUR PROJECT

STEP 2: SELECT ROOF DECK FOR YOUR PROJECT -"M" REPRESENTS MCELROY METAL "MULTI-RIB" ROOF PANEL -"G" REPRESENTS MCELROY METAL "MEGA-RIB" ROOF PANEL -"S" REPRESENTS MCELROY METAL "MEDALLION-LOK" 16" STANDING SEAM ROOF PANEL

- -IDENTIFY THE APPLICABLE SHEET INDEX
- CONSTRUCTION, REVIEW OF INSPECTION REPORTS, AND SIGNING OFF OF THE VERIFIED REPORT FOR COMPLETED WORK.

CONSTRUCTION.

#### 1. GENERAL NOTES AND TYPICAL DETAILS SHALL APPLY TO ALL PARTS OF THE JOB EXCEPT WHERE THEY MAY CONFLICT WITH DETAILS AND NOTES ON OTHER SHEETS. WHERE CONDITIONS ARE NOT SPECIFICALLY INDICATED BUT ARE OF SIMILAR CHARACTER TO DETAILS SHOWN, SIMILAR DETAILS OF CONSTRUCTION SHALL BE USED SUBJECT TO REVIEW BY THE STRUCTURAL ENGINEER FOR THIS PROJECT. 2. WORK SHALL CONFORM TO THE REQUIREMENTS, AS AMENDED TO DATE, OF THE LATEST ADOPTED EDITION OF THE CBC, C.A.C. TITLE 24, AND ALL OTHER LOCAL, STATE AND FEDERAL REGULATIONS.

3. OMISSIONS OR CONFLICTS BETWEEN THE VARIOUS ELEMENTS OF THE WORKING DRAWINGS AND/OR SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE STRUCTURAL ENGINEER FOR THIS PROJECT PRIOR TO PROCEEDING 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE WORK OF ALL TRADES AND SHALL CHECK ALL

DIMENSIONS, ALL DISCREPANCIES SHALL BE CALLED TO THE ATTENTION OF THE STRUCTURAL ENGINEER FOR THIS PROJECT AND BE RESOLVED BEFORE PROCEEDING WITH THE WORK.

5. THESE CONSTRUCTION DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE AND DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES, INCLUDING, BUT NOT LIMITED TO, BRACING, TEMPORARY SUPPORTS, AND SHORING. OBSERVATION VISIT TO THE SITE BY FIELD REPRESENTATIVES OF THE ARCHITECT/ENGINEER SHALL NOT INCLUDE INSPECTIONS OF THE PROTECTIVE MEASURES OR THE CONSTRUCTION PROCEDURES. ANY SUPPORT SERVICES PERFORMED BY THE ARCHITECT/ENGINEER DURING THE CONSTRUCTION SHALL BE DISTINGUISHED FROM CONSTRUCTION AND DETAILED INSPECTION SERVICES WHICH ARE FURNISHED BY OTHERS. THESE SUPPORT SERVICES PERFORMED BY THE ARCHITECT/ENGINEER, WHETHER OF MATERIAL OR WORK, ARE FOR THE PURPOSE OF ASSISTING IN QUALITY CONTROL AND IN ACHIEVING CONFORMANCE WITH CONTRACT DOCUMENTS, BUT DO NOT GUARANTEE CONSTRUCTION.

7. CONFORM TO APPLICABLE CAL/OSHA CONSTRUCTION SAFETY REGULATIONS FOR ALL WORK PERFORMED DURING CONSTRUCTION. JOB SITE SAFETY IS STRICTLY THE RESPONSIBILITY OF THE CONTRACTOR AND NOT THE

8. THE ENGINEER AND THEIR CONSULTANTS SHALL HAVE NO RESPONSIBILITY FOR THE DISCOVERY, HANDLING, REMOVAL OR DISPOSAL OF HAZARDOUS MATERIALS AT THE PROJECT SITE, INCLUDING BUT NOT LIMITED TO ASBESTOS, ASBESTOS PRODUCTS, POLYCHLORINATED BIPHENYL (PCB) OR OTHER TOXIC SUBSTANCES. 9. SHOULD ANY CONDITIONS DEVELOP NOT COVERED BY THE CONTRACT DOCUMENTS, OR IF A CHANGE IN THE SCOPE OF WORK IS PROPOSED, A CONSTRUCTION CHANGE DOCUMENT DETAILING AND SPECIFYING THE REQUIRED CHANGE(S) SHALL BE SUBMITTED TO AND APPROVED BY DSA BEFORE PROCEEDING WITH THE WORK. 10. THE SCHOOL DISTRICT INSPECTOR ON RECORD SHALL INSPECT AND APPROVE THE ERECTED FRAME PRIOR TO ROOF

11. SEE REQUIREMENTS FOR LOCATION IN ANY FIRE HAZARD SEVERITY ZONE FOR WILDLAND URBAN INTERFACE AREAS (WUI) AS SPECIFIED IN THE APPLICABLE VERSION OF THE CALIFORNIA BUILDING CODE. PROVIDE PROTECTION AND DETAILS OF ALL AREAS COMPLYING WITH THE WUI REQUIREMENTS.

12. LOCATING THIS STRUCTURE CLOSER THAN 20 FEET TO OTHER STRUCTURES MAY AFFECT THE ALLOWABLE AREA FOR THE EXISTING CONSTRUCTION PER THE APPLICABLE VERSION OF THE CALIFORNIA BUILDING CODE. 13. VIEWS AND DETAILS ARE NOT DRAWN TO SCALE (UNLESS NOTED OTHERWISE). DO NOT SCALE THESE DRAWINGS.

1. ALL STRUCTURAL STEEL SHALL BE DETAILED, FABRICATED AND ERECTED IN ACCORDANCE WITH THE AMERICAN INSTITUE OF STEEL CONSTRUCTION (AISC) SPECIFICATION MANUAL REFERENCED BY THE LATEST EDITION OF THE

2. PIPE SECTIONS SHALL CONFORM TO ASTM A53, Fy = 35 KSI, GRADE B OR A501 UNLESS NOTED OTHERWISE. 3. STRUCTURAL TUBING (HSS SHAPES) SHALL CONFORM TO ASTM A-500, GRADE B (OR C), Fy = 46 KSI (MIN).

4. IF MATERIAL AVAILABILITY IS LIMITED, MEMBER THICKNESS CAN BE INCREASED BEYOND WHAT IS SHOWN IN THESE 5. ALL CHANNELS, ANGLES, AND MISC. STEEL SHALL CONFORM TO ASTM A-36, Fy = 36 KSI.

6. ALL PLATE STEEL SHALL CONFORM TO ASTM A-572, Fy= 50 KSI. 7. ALL COLD FORM STEEL SHALL CONFORM TO ASTM A-653, CS = TYPE B, Fy = 50 KSI.

8. STRUCTURAL STEEL AND DECK SHALL BE IDENTIFIED FOR CONFORMITY PER CBC 2202A.1.

9. ALL ROOF DECKS SHALL HAVE KYNAR 500 METAL COATING.

#### -GABLE STRUCTURES UP TO 20' WIDE USE THE "RG 20" BASE FRAME -GABLE STRUCTURES UP TO 30' WIDE USE THE "RG 30" BASE FRAME -GABLE STRUCTURES UP TO 40' WIDE USE THE "RG 40" BASE FRAME -MAXIMUM WIDTH IS 40' (SEE "ARCHITECTURAL VIEWS" SHEET FOR REFERENCE)

-THE 24', 44', 64', 84' AND 104' LENGTHS ARE SUGGESTED BECAUSE THEY ARE THE MOST COMMON (20' BAYS ARE THE MOST ECONOMICAL) -FRAME LENGTHS ASSUME 2' OVERHANGS (UNO BY ARCHITECT - 2' MAX DIMENSION)

STEP 3: IDENTIFY THE Ss ACCELERATION (g) FOR YOUR PROJECT -Ss VALUE DETERMINES THE REQUIRED SEISMIC DESIGN FORCES -Ss VALUE DEPENDS ON THE PROJECTS GEOGRAPHICAL LOCATION (VALUES RANGE FROM 0.00 TO 3.73)

## STEP 4: IDENTIFY THE Ss REGION FOR YOUR PROJECT

-THE REGIONS ARE DEPENDANT ON THE SS VALUE DETERMINED IN STEP 3 -THE SS REGION DICTATES THE MAXIMUM DEAD LOAD PERMITTED ON THE FRAME (SEE TABLE TO RIGHT) STEP 5: IDENTIFY THE ROOF DEAD LOAD FOR YOUR PROJECT

-THE ROOF DECK DEAD LOAD WILL ALWAYS BE INCLUDED -THE COLLATERAL LOAD REPRESENTS ADDITIONAL LOAD THAT CAN BE SUPPORTED BY THE FRAME -BE SURE THE TOTAL ROOF DEAD LOAD FOR YOUR PROJECT IS LESS THAN OR EQUAL TO THE MAX DEAD LOAD SHOWN IN STEP 4 FOR YOUR SS VALUE -Sds VALUE USED IN CALCULATION IS THE CAPPED Sds (SEE DESIGN CRITERIA)

STEP 6: IDENTIFY THE FOUNDATION REQUIREMENTS FOR YOUR PROJECT

-IDENTIFY SOIL CLASS FOR PROJECT SITE PER SITE SPECIFIC SOIL CONDITIONS -USE THIS TO SELECT CORRECT FOUNDATION SIZE ON FOUNDATION SHEET

#### STEP 7: SELECT MISCELLANEOUS OPTIONS FOR YOUR PROJECT -MAXIMUM CLEAR HEIGHT IS 12'-0"; (SEE "ARCHITECTURAL VIEWS" SHEET FOR REFERENCE) -MARK UP PC DRAWINGS WITH SIZE AND LOCATION OF CUTOUTS BEFORE SUBMITTING TO DSA

STEP 8: SELECT APPLICABLE SHEET INDEX FOR YOUR PROJECT -REFERENCE THE BASE FRAME (STEP 1) AND THE ROOF PANEL TYPE (STEP 2)

STEP 9: INCLUDE APPLICABLE SHEETS WITH YOUR DSA SUBMITTAL

-INCLUDE 'MISC DESIGN OPTIONS' SHEET FOR PROJECTS WITHOUT ELECTRICAL CUTOUTS OR GUTTERS

### NOTICE OF DISCLAIMER FOR STRUCTURAL ENGINEERING RESPONSIBILITY

1. PER TITLE 24, PART 1, SECTION 4-316(e) OF THE CALIFORNIA CODE OF REGULATIONS, THIS NOTICE SHALL BE GIVEN TO DSA PRIOR TO THE APPROVAL OF PLANS AND SPECIFICATIONS. 2. FOR THE SITE SPECIFIC PROJECT, J. R. MILLER & ASSOCIATES IS NOT THE DESIGN PROFESSIONAL IN

GENERAL RESPONSIBLE CHARGE. FOR THE SITE SPECIFIC PROJECT, J.R. MILLER & ASSOCIATES' RESPONSIBILITY IS LIMITED TO THE PREPARATION OF THE PLANS AND SPECIFICATIONS FOR THE SHELTERS OF THIS PC ONLY.

4. STRUCTURAL OBSERVATION OF CONSTRUCTION IS SPECIFICALLY EXCLUDED FROM J.R. MILLER & ASSOCIATES' RESPONSIBILITY FOR THE SITE SPECIFIC PROJECT. 5. ALL CONSTRUCTION ACTIVITIES RELATED TO STRUCTURAL ENGINEERING SHALL BE DELEGATED TO A QUALIFIED ENGINEER BY THE DESIGN PROFESSIONAL IN GENERAL RESPONSIBLE CHARGE. THESE ACTIVITIES INCLUDE, BUT ARE NOT LIMITED TO, APPROVAL OF INSPECTOR QUALIFICATIONS, STRUCTURAL OBSERVATION OF

6. J.R. MILLER & ASSOCIATES WILL BE RESPONSIBLE FOR RESPONDING TO QUESTIONS PERTAINING TO THE PLANS AND SPECIFICATIONS FOR THE SHELTERS OF THIS PC WHICH ARISE DURING PLAN REVIEW AND

#### WELDING:

- 1. ALL WELDING SHALL COMPLY WITH AWS D1.1 SPECIFICATIONS AND SHALL BE DONE BY AWS QUA CERTIFIED FOR THE TYPE OF WELDING TO BE PERFORMED AS REQUIRED BY DSA. 2. ALL WELDING SHALL BE DONE BY GAS METAL ARC PROCESS WITH E70XX ELECTRODES. FLUX CC
- SHALL CONFORM TO CHARPY NOTCH TOUGHNESS RATING OF 20 ft-16 @ (0°F). 3. ALL WELDING SHALL BE DONE IN THE SHOP WITH REQUIRED INSPECTION, PRE-APPROVED BY DS
- PROPER MATERIAL ID AND WELDING. 4. WELD FILLER METAL MANUFACTURER SHALL PROVIDE WRITTEN CERTIFICATION OF COMPLIANCE WI SPECIFIC ATIONS.

#### <u>BOLTING:</u>

- 1. ALL BOLTS SHOWN ON THESE DRAWINGS ARE ASTM F3125 GRADE A325 HIGH STRENGTH BOI CONFORMING TO ASTM A-563.
- 2. HIGH STRENGTH BOLTS SHALL BE VERIFIED AND INSPECTED PER CBC 1705A2.1. 3. BEFORE ERECTING THE FRAME, VERIFY ALL BOLTS AND NUTS ARE CLEAN OF DEBRIS AND
- THE HARDWARE ALREADY FASTENED INSIDE THE MEMBERS. CHASING SOME OF THE BOLTS REQUIRED.
- 4. HARDENED STEEL WASHERS SHALL CONFORM TO ASTM F-436. 5. THE BOLTING INSTALLATION REQUIREMENTS OUTLINED BELOW ARE CRITICAL TO THE STRUCT PERFORMANCE. THE INSTALLER IS REQUIRED TO COORDINATE THIS PHASE OF CONSTRUCTION BOLTING INSPECTOR AND THE INSPECTOR OF RECORD PRIOR TO THE ERECTION OF THE FRA BE INSTALLED AND INSPECTED PER THE APPLICABLE VERSION OF AISC'S "SPECIFICATION FO USING HIGH-STRENGTH BOLTS", CBC 1705A.2.1; AISC 341-16 J7; AISC 360-16 N5.6. A)PRETENSIONED JOINTS MUST BE INSTALLED AND INSPECTED TO MEET ONE OF THE FOL 1. TURN-OF-NUT PRETENSIONING
  - 2. CALIBRATED WRENCH PRETENSIONING

#### 3. DIRECT-TENSION-INDICATOR PRETENSIONING (CONTRACTOR RESPONSIBLE FOR REQUIRED WASHERS)

- FOUNDATIONS: 1. ALLOWABLE SOIL PRESSURES ASSUME CLASS 5 SOIL CLASSIFICATION PER CBC TABLE 1806A OTHERWISE.
- 2. PER CBC SECTION 1803A.2, GEOTECHNICAL REPORTS ARE NOT REQUIRED FOR ONE-STORY BUILDINGS OF TYPE II CONSTRUCTION AND 4,000 SQUARE FOOT OR LESS IN FLOOR AREA EARTHQUAKE FAULT ZONESOR SIESMIC HAZARD ZONES AS SHOWN ON THE MOST RECENT CGS. ALLOWABLE FOUNDATION AND LATERAL SOIL PRESSURE VALUES MAY BE DETERMINED
- 3. FILL AND BACKFILL SHALL BE COMPACTED TO 95% OF MAX. DENSITY IN ACCORDANCE WITH
- D-1557 OR AS RECOMMENDED BY THE GEO-TECH ENGINEER. FLOODING NOT PERMITTED. 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING, ETC. NECESSARY TO SUPPORT
- BANKS DURING EXCAVATION, AND FORMING AND PLACEMENT OF CONCRETE. 5. MINIMUM SETBACK FROM TOE OF SLOPE ON AN ASCENDING SLOPE SHALL BE 15 FEET AND
- FROM TOE OF SLOPE ON A DESCENDING SLOPE SHALL BE 40 FEET 6. PER CBC SECTION 1803A.6, GEOHAZARD REPORTS ARE NOT REQUIRED FOR ONE-STORY LIGH OF TYPE II CONSTRUCTION AND 4,000 SQUARE FOOT OR LESS IN FLOOR AREA AND NOT LOC FAULT ZONESOR SIESMIC HAZARD ZONES AS SHOWN ON THE MOST RECENT MAPS PUBLISHED
- 7. GEOHAZRD REPORTS ARE TO COMPLY WITH DSA IR A-4 PER IR-7 SECTION 1.8
- 8. SITE SPECIFIC GEOTECHNICAL REPORT IS REQUIRED AT THE TIME OF SITE APPLICATION IS US CLASS 5 SOIL, PER DSA IR PC-7 9. LATERAL BEARING HAS BEEN INCREASED PER CBC 1806A.3.4 & HAS BEEN DESIGNED FOR I
- <u>CONCRETE:</u>

| STRENGTH Pc | W/C RATIO           | W/C RATIO       | SLUMP (±1' |
|-------------|---------------------|-----------------|------------|
| (28 DAYS)   | (NON-AIR ENTRAINED) | (AIR ENTRAINED) |            |
| 4500 PSI    | 0.44                | 0.35            | 3"         |

- ENTRAINMENT FOR THESE CATEGORIES SHALL BE AS FOLLOWS: F0-0, F1-4.5, F2-0 3. AGGREGATES SHALL CONFORM TO THE ASTM C-33 WITH PROVEN SHRINKAGE CHAR MAX AGGREGATE SIZE = 1".
- 4. CEMENT SHALL CONFORM TO ASTM C-150 (TYPE V) UNLESS NOTED OTHERWISE ON 5. CONCRETE SHALL BE MAINTAINED IN A MOIST CONDITION FOR A MINIMUM OF FIVE [
- ALTERNATE METHODS WILL BE APPROVED IF SATISFACTORY PERFORMANCE CAN BE 6. CONCRETE SHALL NOT FREE FALL MORE THAN FIVE FEET.
- 7. CONCRETE DURABILITY SHALL BE PER CBC 1904A.1 & ACI 318-14 CHAPTER 19. 8. CONCRETE SHALL BE TESTED PER CBC 1903A, TABLE 1705A.3. AND ACI 318-14

STEP 10: IDENTIFY PROJECT NAME AND SCHOOL DISTRICT

|      |             | PROJEC T NAME:                                |    |       |           |       |            | SCH       | 00L       | DISTRIC T:   |
|------|-------------|---|----|-------|-----------|-------|------------|-----------|-----------|--------------|
|      |             | SHADE STRUCTURE AT NEV<br>BONNHEIM ELEMENTARY |    |       | I         |       | SA         |           |           | D CITY UNIF  |
|      |             |   |    |       | _         |       |            |           |           |              |
|      |             |   |    |       | Ff        | RAME  | DIMENSION  | S         |           |              |
|      |             |   |    |       |           | SUG   | GESTED     |           |           |              |
| STFP |             | FRAME WIDTH                                   | [] | 20'   | $\bowtie$ | 30'   | [] 40'     |           |           |              |
|      |             | FRAME LENGTH                                  | [] | 44'   | X         | 64'   | []84'      | []1       | 04'       |              |
|      |             | 1   |    |       |           |       |            |           |           |              |
|      | 2           |   |    |       |           | RO    | OF PANEL   |           |           |              |
|      | STEP        | ROOF PANEL TYPE                               |    |       | []        | М     | [] G       | $\bowtie$ | S         |              |
|      | _           |   | F  | PROJE | ст s      | ITE - | · Ss ACCE  | LERATIC   | <br>)N (c | <br>a)       |
| N HC | 0<br>1<br>1 |   |    |       |           |       | 0.531      |           |           |              |
|      |             |   |    |       |           |       |            |           |           |              |
|      |             |   |    |       |           | Ss    | REGION     |           |           |              |
|      |             |   |    |       |           |       |            |           | Ss        | REGIONS      |
| 4    |             |   |    |       |           |       | Х          |           | 0 <       | Ss <= 2.14   |
| STEP |             |   |    | Ĩ     |           |       |            | 2         | .14 <     | < Ss <= 2.5  |
| 12   |             | DESC RIPTION                                  |    | Ī     |           |       |            | 2.        | .50 <     | < Ss <= 2.7  |
|      |             |   |    |       |           |       |            | 2.        | .75 <     | < Ss <= 3.0  |
|      |             |   |    |       |           |       |            |           | Ss 2      | > 3.73 MAX   |
|      |             |   |    |       |           |       |            |           |           |              |
|      |             |   |    |       | ΤΟΤΑΙ     | ROC   | OF DEAD LO | ) AD      |           |              |
| 2    |             |   |    |       |           | EAD   |            |           |           | E)           |
|      |             | ROOF DECK                                     |    |       |           |       | _ PSF      | M=1       | I.1PS     | SF; G=1.2PSF |
| STEI |             | COLLATERAL                                    |    |       | <u>_</u>  | )     | _ PSF      |           |           | LIGH         |

CONSTRUCTION NOTES

TOTAL


1. A DSA-CERTIFIED CLASS 3 PROJECT INSPECTOR IS REQUIRED FOR TH 2. CHANGES TO THE APPROVED DRAWINGS AND SPECIFICATIONS SHALL


<u>1.3</u> PSF

ADD ROOF DECK

- DOCUMENT (CCD) APPROVED BY DSA, AS REQUIRED BY SECTION 4-3. A "DSA CERTIFIED" PROJECT INSPECTOR EMPLOYED BY THE DISTRICT CONTINUOUS INSPECTION OF WORK. THE DUTIES OF THE INSPECTOR
- 4. A DSA ACCEPTED TESTING LABORATORY DIRECTLY EMPLOYED BY THE TESTS AND INSPECTIONS FOR THE PROJECT. 5. THE INTENT OF THESE DRAWINGS AND SPECIFICATIONS ARE THAT ALL RECONSTRUCTION IS TO BE IN ACCORDANCE WITH TITLE 24, CCR. SH OR NON-COMPLYING CONSTRUCTION BE DISCOVERED WHICH IS NOT C FINISHED WORK WILL NOT COMPLY WITH TITLE 24, CCR, A CONSTRUCT
- PLANS AND SPECIFICATIONS, DETAILING AND SPECIFYING THE REQUIRED BEFORE PROCEEDING WITH THE WORK, (SECTION 4-317(c), PART 1, TI 6. GRADING PLANS, DRAINAGE IMPROVEMENTS, ROAD AND ACCESS REQUI SHALL COMPLY WITH ALL LOCAL ORDINANCES


|  | REINFORCING STE                   | <u>EL:</u>  |  |                     |   |  |  |
|--|-----------------------------------|---|--|---------------------|---|--|--|
|  | 1. REINFORCIN                     | NG STEEL SHALL BE DEFORM  | IED STEEL CONFORMI                         | NG TO THE REC       | QUIREMENTS OF ASTM A-61                 | 5,   |  |
| ALIFIED WELDERS                                      | AS FOLLO<br>GR (                  | WS:<br>60: (#4 BARS AND LARGER)   | )  |                     |   |  |  |
| ORE ARC WELD   |                                   | 40: (#3 BARS)<br>FABRICATION, AND ERECTIO                               | DN OF REINFORCING E                        | BARS SHALL C        | ONFORM TO THE ACI                       |  |  |
| SA, TO ENSURE  | "MANUAL (<br>3. MIN. COVE         | OF STANDARD PRACTICE FOR<br>R FOR CAST-IN-PLACE CO                      | R DETAILING REINFORC<br>NCRETE SHALL BE AS | NG CONCRET          |   |  |  |
| ITH CODE AND   |                                   | ST AGAINST EARTH<br>ST AGAINST FORM BELOW GI                            |  |                     |   |  |  |
|  |                                   | RMED SLABS (#11 BAR & SN  | ,  | 4"                  |   |  |  |
|  | 4. BARS SHA                       | BS ON GRADE (FROM TOP (<br>ILL BE CLEAN OF RUST, GRE                    |  | ERIAL LIKELY TO     | D IMPAIR BOND.                          |  |  |
| DLTS (UNO), WITH THE NUTS                            | 5. REINFORCI                      | ALL BE MADE COLD.<br>NG SHALL BE LAP SPLICED<br>PLACING OF CONCRETE, RE |  |                     | EMS SHALL BE WELL SECUL                 | RED IN POSITION  | ICON STD RH/DSA-PC<br>DRAWN BY ANGEL                                 |
|  | 7. WELDING O                      | F REINFORCING IS NOT ALLO<br>NG STEEL SHALL BE INSPEC                   | DWED.                                      |                     |   |  | DRAWN BY ANGEL<br>DATE 4/2/2021                                      |
| BURRS — INCLUDING<br>AND NUTS MAY BE                 |                                   | FINISH SYSTEM:  |  |                     |   |  | REV  |
|  |                                   | THAT HAVE A POWDER-COA<br>FRAME SHALL BE SHOT-B                         |  |                     |   | ATIONS.  | REV DATE   |
| URE'S DESIGN AND<br>N WITH THE SPECIAL               |                                   | . SHALL BE WASHED IN A Z<br>ATEMENT PROCESS.                            | INC PHOSPHATE IN A                         | N MINIMUM EIG       | HT STAGE ELECTRO DEPOS                  | ITION  |  |
| <u>AME</u> , ALL BOLTS SHALL<br>OR STRUCTURAL JOINTS | PRIMER(E                          | LY FOLLOWING PRE-TREATME<br>-COAT) AND COATED TO A                      | UNIFORM THICKNESS                          | OF A MINIMUM        | OF 0.7 TO 0.9 MILS. THE                 |  |  |
| LLOWING REQUIREMENTS:                                |                                   | A MINIMUM OF 1000 HOURS<br>. SHALL THEN HAVE A TGIC                     |  |                     |   | ACE.   |  |
|  |                                   | R COAT SHALL THEN HAVE<br>LET LIGHT, TO HELP PREVEN                     |  | ING APPLIED TO      | D SEAL IN THE COLOR COA                 | T AND RESIST   |  |
| R PURCHASE OF  |                                   | H THICKNESS OF THESE THE<br>ON STEEL MEMBERS (COLUM                     |  |                     |   | PAINTED WITH PRIME   |  |
|  |                                   | R THE "AISC CODE OF STAN  |  |                     |   |  |  |
| A, UNLESS NOTED                                      | ABBREVIATIO                       |   |  | 1                   |   |  |  |
| LIGHT-STEEL FRAME<br>AND NOT LOCATED WITHIN          | ACI<br>AISC                       | AMERICAN CONCRETE<br>AMERICAN INSTITUTE OF STE                          |  | MPH<br>M            | MILES PER H<br>MULTI-RIB ROOF PANEI     |  | 2700 SATURN ST I BREA, CA 92821<br>T. 714.524.1870   F. 714.524.1875 |
| MAPS PUBLISHED BY THE<br>FROM TABLE 1806A.2.         | ASM                               | ASSEMBLY (INTERNAL  | REFERENCE)                                 | NTS                 | NOT TO SC.                              | ALE  | WWW.JRMA.COM   |
| H ASTM TEST METHOD                                   | ASTM<br>AWS                       | AMERICAN SOCIETY FOR TES  |  | NO<br>OC            | NUMBE<br>ON CENT                        |  | BED SHEL D. FE   |
| RT CUT AND/OR FILL                                   | CBC                               | CALIFORNIA BUILDI   |  | OSHA                | OCCUPATIONAL HEALTH AN                  |  |  |
| MINIMUM SETBACK                                      | CJP                               | COMPLETE JOINT PE   | NETRATION                                  | PCF<br>PJ           | POUNDS PER CUB                          |  |  |
| T-STEEL FRAME BUILDINGS<br>CATED WITHIN EARTHQUAKE   | DEG                               | DEGREE  |  | PLCS                | PLACES                                  |  | FIF OF CALIFORN  |
| D BY THE CGS.  | DIA                               | DIAMETE   |  | PLT<br>PSF          | PLATE<br>POUNDS PER SQU                 |  | 07/29/:  |
| SING OTHER THAN                                      | DSA                               | DIVISION OF THE STATE   |  | PSI                 | POUNDS PER SQU                          |  |  |
| P-DELTA EFFEC TS                                     | EQ<br>FT                          | EQUAL<br>FEET   |  | QTY<br>REF          | QUANTI<br>REFEREN                       |  |  |
|  | GA                                | GAGE  |  | SQ                  | SQUAR                                   |  |  |
| "、 UNIT WEIGHT                                       |                                   | INC HES<br>KIPS PER SQUARE  |  | SS<br>TYP           | STANDING SEAM ROOF PA                   | ANEL (MCELROY)   |  |
| ) (NORMAL WEIGHT)<br>150 PCF                         | - MAX                             | MAXIMUN   |  | UNO                 | UNLESS NOTED OTHERWISE                  |  |  |
| 1 & F2. THE AIR                                      | MIN<br>MISC                       | MINIMUM   |  | USGS<br>W/          | U.S. GEOLOGIC AL SURVEY<br>WITH         | $\dashv$ $\succ$   | APPROVED   |
| SECTION 26.12.                                       |                                   |   |  |                     |   |  |  |
| ]  |                                   |   | FOUNDATIC                                  | DN REQUIREMEN       | ITS                                     |  |  |
| OTHER  | í∧                                | . CLASS 5 (BEARING)-1500 PSF  |  | (BEARING)-200       |   | BEARING)-3000 PSF [ ]  |  |
| [ ] (40' MAX)<br>[ ] (NO MAX)                        | SOIL CI                           | LASS 5 (LATERAL BEARING)-100  | ) PSF SOIL CLASS 4 (                       | LATERAL BEARIN      | G)-150 PSF SOIL CLASS 3 (LA             | TERAL BEARING)-200 PSF   | 0  |
|  |                                   |   | MISC                                       | ELLANEOUS           | DESIGN OPTIC                            | DNS  | INFO<br>INFO   |
|  | STEP 7                            | CLEAR HEIC  |  | 5 []                |   |  | GENERAL  |
|  |                                   | ELEC TRICAL CU  |  |                     | X YES                                   | [ ] NO<br>[ ] NO   |  |
|  |                                   |   | SHI  | EET INDEX           |   |  |  |
|  |                                   | BASE FRAME  | RG 20                                      | 5 M                 | RG 30                                   | RG 40<br>M G S   |  |
| MAX DEAD LOAD  |                                   | SELEC T ONE   | [] [] []                                   | ] [                 |   |  |  |
| 5 PSF  |                                   | GENERAL NOTES   | LS1.0 LS1.0 LS<br>LS1.1 LS1.1 LS           |                     |   | LS1.0 LS1.0 LS1.0<br>LS1.1 LS1.1 LS1.1                         |  |
| 75 5 PSF   |                                   | FOUNDATION PLAN   | LS2.0 LS2.0 LS2                            | 2.0 LS3             | 0.0 LS3.0 LS3.0                         | LS4.0 LS4.0 LS4.0  |  |
| 00 4 PSF<br>3 PSF                                    | G<br>FRAME                        | FRAMING PLAN<br>CONNECTION DETAILS                                      | LS2.1 LS2.1 LS<br>LS2.1 LS2.1 LS           |                     |   | LS4.1 LS4.1 LS4.1<br>LS4.2 LS4.2 LS4.2                         |  |
|  | ROOFIN                            | IG LAYOUT & DETAILS   | LS2.2 LS2.3 LS2                            |                     |   | LS4.3 LS4.4 LS4.5  |  |
| XAMPLES  |                                   | IISC DESIGN OPTIONS   | LS5.0 LS5.0 LS                             | 5.0 LS5             | 5.0 LS5.0 LS5.0                         | LS5.0 LS5.0 LS5.0  |  |
| F ;S=1.3PSF (SEE STEP 2)                             |                                   |   | DESIGN CRITERIA                            | FOR 7300 MA         | RIN AVENUE, SACRAMENTO                  | D, CA 95820  |  |
| ITING, ETC<br>AND COLLATERAL LOADS                   |                                   |   |  | DESCRIPTION         | <u>I D</u>                              | ESIGN VALUES   |  |
| AND COLLATENAL LOADS                                 |                                   |   |  | WIND DESIGN         | <u>ı</u>                                |  |  |
|  |                                   |   | BASIC WIND SPEE                            | ED (3 SECOND        | GUST), V <sub>ult</sub>                 | 94 MPH   | DISTINCTIVE STEEL SHELTERS<br>WWW.ICONSHELTERS.COM                   |
|  |                                   |   | RISK CATEGORY<br>EXPOSURE CATEC            | GORY                |   | II<br>C  | COPYRIGHT 2004, ICON SHELTER<br>SYSTEMS, INC.                        |
| HIS PROJECT.<br>BE MADE BY ADDENDA OR                | CONSTRUCTION                      | HANGF   | 5  | EISMIC DESIGN       | <u></u>                                 |  | 1455 LINCOLN AVE<br>HOLLAND MI, 49423                                |
| -338, PART 1, TITLE 24, CC<br>(OWNER) AND APPROVED E | R.<br>By DSA Shall Pr             | ROVIDE  | SEISMIC SITE CLA                           |                     | -                                       | D<br>0.531   |  |
| ARE DEFINED IN SECTION 4<br>DISTRICT (OWNER) SHALL   | -342, PART 1, TI                  | TLE 24, CCR.  | Ss<br>*All information prov                | vided by https://as | sce7hazardtool.online/and https:        |  | 616.396.0919<br>800.748.0985   |
| THE WORK OF THE ALTER                                |                                   |   |  |                     |   |  | 616.396.0944 FX  |
| OVERED BY THE CONTRAC<br>TION CHANGE DOCUMENT (C     | T DOCUMENTS WH<br>CCD), OR A SEPA | IEREIN THE<br>RATE SET OF   |  |                     |   |  |  |
| D WORK SHALL BE SUBMIT <sup>-</sup><br>ITLE 24, CCR) | TED TO AND APPF                   | ROVED BY DSA  |  |                     |   |  |  |
| IREMENTS AND ENVIRONMEN                              | ial health con                    | SIDERATIONS   |  |                     |   | K (PC) DOCUMENT<br>e: 2019 CBC<br>ation for construction is re | equired. $ \Box \cup I \bullet \cup $                                |
|  |                                   |   |  |                     | I ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' |  | · 1  |
|  |                                   |   |  |                     |   |  | PRINTED ON :   |





| o · ·  | tion Number:<br>000   | School Name:   |   |  | School District:  | <b>F</b> |          |  |  |
|--|---|--|---|--|---|----------|----------|--|--|
|  | le Number:  | ICON Shelter Systems<br>Increment Number:  |   |  | PC Submittal<br>Date Created:<br>2021-07-14 05:50:33  |          |          |  |  |
|  |   |  |   |  |   |          |          |  |  |
|  | 5. RETAINING WALLS  |  | Ture  | Denferme   |   |          |          |  |  |
|  | Test or Special Inspection  | $\mathbf{i}$   | Туре  | By   | d Code References and Notes   |          |          |  |  |
|  | a. Placement, compaction and  | d inspection of backfill.  | Continuous  | s GE*  | <b>1705A.6.1.</b> * By geotechnical engineer or his or her qualified representative. (See Section 2 above).   |          |          |  |  |
|  | <b>b</b> . Placement of soil reinforcer<br>devices.   | ment and/or drainage   | Continuous  | s GE*  | * By geotechnical engineer or his or her qualified representative   |          |          |  |  |
|  | c. Segmental retaining walls; i<br>units, dowels, connectors, etc.  |  | Continuous  | s GE*  | * By geotechnical engineer or his or her qualified representative See DSA IR 16-3.  |          |          |  | <b>.</b>   |
|  | <b>d</b> . Concrete retaining walls.  |  | Provide tests   | and inspectio  | ons per CONCRETE section below.   |          |          | ICON STD   | RH/DSA-PC  |
|  | e. Masonry retaining walls.   |  | Provide tests   | and inspection   | ons per MASONRY section below.  |          |          | DRAWN BY   | ANGEL  |
|  | 6. OTHER SOIL   |  |   |  |   |          |          | DATE   | 4/2/202  |
|  | Test or Special Inspection  |  | Туре  | Performe<br>By   | d Code References and Notes   |          |          | REV  |  |
|  | a. Soil Improvements  |  | Test  | GE*  | Submit a comprehensive report documenting final soil improvements constructed, construction observation and the results of the confirmatic testing and analysis to COS for final acceptance.  |          |          | REV DATE   |  |
|  | b. Inspection of Soil Improven  | nexts  | Continuou   | s GE*  | * By geotechnical engineer or his or her qualified representative     * By geotechnical engineer or his other qualified representative  | _        |          |  |  |
|  | /   |  |   |  |   |          |          |  |  |
|  |   |  |   |  |   |          |          |  |  |
|  |   |  |   |  |   |          |          |  |  |
|  |   |  |   |  |   |          |          |  |  |
| GS DS  | 193-19 (Revised 07/16/2020)   |  |   |  | $\sim$  |          |          |  |  |
|  | A 193-19 (Revised 07/16/2020)<br>I OF THE STATE ARCHITECT   |  | DEPARTMEN   | IT OF GENERAL  | SERVICES STATE OF CALIFOR   | FORMA    |          |  |  |
|  |   |  | DEPARTMEN   | IT OF GENERAL<br>Page 4 of 11  | SERVICES STATE OF CALIFOR   | FORMA    |          |  |  |
|  |   |  | DEPARTMEN   |  | SERVICES STATE OF CALIFOR   | FORMA    |          |  |  |
| DIVISION   | I OF THE STATE ARCHITECT  |  |   | Page 4 of 11   |   | IFORMA   |          |  | S ENGINEERS  |
| SA 1   | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2   |  |   | Page 4 of 11   | SERVICES STATE OF CALIFOR   | IFORMA   |          | 2700 SATURN ST I   | BREA, CA 92821   |
| SA 1<br>ble<br>pplica  | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:  |  |   | Page 4 of 11   |   | IFORMA   |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821   |
| SA 1<br>ble<br>pplica  | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:  | 26.12 & 26.13<br>School Name:  |   | Page 4 of 11   | IONS (Concrete), 2019 CBC   |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875  |
| SA 1<br>ble<br>pplica  | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:  | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems  |   | Page 4 of 11   | IONS (Concrete), 2019 CBC<br>School District:<br>PC Submittal<br>Date Created:  |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875  |
| SA 1<br>blet<br>pplica<br>-0000<br>SA File   | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:  | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems  |   | Page 4 of 11   | IONS (Concrete), 2019 CBC<br>School District:<br>PC Submittal<br>Date Created:  |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875  |
| SA 1<br>ble 5<br>oplica<br>-0000<br>GA File<br>1   | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:  | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems  | & SPECIAL   | Page 4 of 11   | IONS (Concrete), 2019 CBC<br>School District:<br>PC Submittal<br>Date Created:  |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875  |
| SA 1<br>ble<br>pplica<br>⊳0000<br>SA Fild  | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>Inspect groove welds, multi-p<br>let welds > 5/16", plug and slo  | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet werds, single pass<br>ot welds.  | & SPECIAL   | Page 4 of 11   | IONS (Concrete), 2019 CBC<br>School District:<br>PC Submittal<br>Date Created:<br>2021-07-14 05:50:33<br>Code References and Notes<br>Table 1705A.2.1 Items 5a 1-4; AISC 360-16 (and AISC 341-16 as<br>applicable); DSA IR 17-3   |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875  |
| SA 1<br>ble pplica<br>-0000<br>SA File<br>T<br>T<br>Z<br>a<br>fi<br>fi<br>d  | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:<br>00<br>100 Number:<br>100 | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet welds, single pass<br>ot welds.<br>Is ≤ 5/16″, floor and roo   | & SPECIAL<br>Type<br>Continuous<br>Periodic   | Page 4 of 11<br>INSPECT<br>Performed<br>By<br>SI<br>SI                                       | School District:         PC Submittal         Date Created:         2021-07-14 05:50:33    Code References and Notes          Table 1705A.2.1 Items 5a:1-4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.   |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESS /OW<br>ESS /OU<br>ESS /OU |
| SA 1<br>ble<br>pplica<br>+0000<br>SA File<br>1<br>T<br>T<br>Z<br>b<br>d  | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:<br>00<br>Number<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>Inspect groove welds, multi-p<br>lifet welds > 5/16", plug and sloc<br>Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and i   | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet welds, single pass<br>ot welds.<br>Is ≤ 5/16″, floor and roo<br>railing systems.   | & SPECIAL<br>Type<br>Continuous   | Page 4 of 11<br>INSPECT<br>Performed<br>By<br>SI   | ONS (Concrete), 2019 CBC         School District:<br>PC Submittal<br>Date Created:<br>2021-07-14 05:50:33         Code References and Notes         Table 1705A.2.1 Items 5a:1-4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.2, Table 1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.2, Table 1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.  | .3;      |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESS /ONA<br>ESS /ONA<br>E   |
| SA 1<br>able 1<br>pplica<br>4-0000<br>SA File<br>1<br>T<br>T<br>2<br>a<br>fi<br>fi<br>d<br>0<br>c<br>c   | OF THE STATE ARCHITECT<br>O3-19: LISTING OF S<br>O5A.3; ACI 318-14 Sections 2<br>Number:<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>Inspect groove welds, multi-p<br>let welds > 5/16", plug and slo<br>Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and a<br>. Verification of reinforcing ste<br>ther than ASTM A706.   | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet welds, single pass<br>ot welds.<br>Is ≤ 5/16", floor and root<br>railing systems.<br>el weldability                                | & SPECIAL<br>Type<br>Continuous<br>Periodic<br>Periodic                               | Page 4 of 11<br>INSPECT<br>Performed<br>By<br>SI<br>SI<br>SI<br>SI                           | ONS (Concrete), 2019 CBC         School District:<br>PC Submittal<br>Date Created:<br>2021-07-14 05:50:33         Code References and Notes         Table 1705A.2.1 Items 5a.1–4; AISC 360-16 (and AISC 341-16 as<br>applicable); DSA IR 17-3.         1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1, Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DX IR 17-3.         1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates.   |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | F. 714.524.1875  |
| SA 1<br>bbie<br>pplica<br>4-0000<br>SA File<br>1<br>T<br>T<br>2<br>a<br>fi<br>fi<br>d<br>d<br>c  | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:<br>100<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>Inspect groove welds, multi-p<br>let welds > 5/16", plug and sloc<br>Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and in<br>Verification of reinforcing ste  | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet welds, single pass<br>ot welds.<br>Is ≤ 5/16", floor and root<br>railing systems.<br>el weldability                                | & SPECIAL<br>Type<br>Continuous<br>Periodic   | Page 4 of 11<br>INSPECT<br>Performed<br>By<br>SI<br>SI<br>SI                                 | ONS (Concrete), 2019 CBC         School District:<br>PC Submittal<br>Date Created:<br>2021-07-14 05:50:33         Code References and Notes         Table 1705A.2.1 Items 5a:1-4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.2, Table 1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.2, Table 1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705J.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; D1A IR 17-3.         1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on  |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESS / OHA<br>ESS / OHA<br>CT UEL<br>CT UEL<br>CAL IFORM   |
| SA 1<br>bble<br>pplica<br>pplica<br>4-0000<br>SA File<br>2 a file<br>d<br>d<br>c<br>c<br>c<br>c<br>c<br>c<br>c   | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:<br>00<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>Inspect groove welds, multi-<br>litet welds > 5/16", plug and sloc<br>Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and i<br>. Verification of reinforcing ste<br>ther than ASTM A706.<br>Inspect welding of reinforcing   | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet werds, single pass<br>ot welds.<br>Is ≤ 5/16", floor and root<br>railing systems.<br>el weldability<br>g steel.                    | & SPECIAL<br>Type<br>Continuous<br>Periodic<br>Periodic                               | Page 4 of 11<br>INSPECT<br>Performed<br>By<br>SI<br>SI<br>SI<br>SI                           | School District:         PC Submittal         Date Created:         2021-07-14 05:50:33    Code References and Notes          Table 1705A.2.1 Items 5a:1-4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.    Tros A.2.2, Table 1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.          1705A.2.2, Table 1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.    Tros A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates. Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8;   |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESS / ON<br>ESS / ON<br>E   |
| SA 1<br>able<br>pplica<br>4-0000<br>SA File<br>1<br>T<br>2<br>a a<br>fi<br>fi<br>d<br>c<br>c<br>c<br>2<br>2  | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:<br>20<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>. Inspect groove welds, multi-p<br>liet welds > 5/16", plug and slo<br>. Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and a<br>. Verification of reinforcing stether than ASTM A706.<br>. Inspect welding of reinforcing<br>3. ANCHOR BOLTS AND ANC   | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet werds, single pass<br>ot welds.<br>Is ≤ 5/16", floor and root<br>railing systems.<br>el weldability<br>g steel.                    | & SPECIAL<br>Type<br>Continuous<br>Periodic<br>Periodic<br>Continuous                 | Page 4 of 11<br>INSPECT<br>Performed<br>By<br>SI<br>SI<br>SI<br>SI                           | School District:         PC Submittal         Date Created:         2021-07-14 05:50:33    Code References and Notes          Table 1705A.2.1 Items 5a:1-4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.    Trost.2.2, Table 1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.     Trost.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; DSA IR 17-3.        1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates.        Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AVS D1.4; DSA IR 17-3.  |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESS / ON<br>ESS / ON<br>E   |
| SA 1<br>bbie<br>pplica<br>4-0000<br>SA File<br>1<br>T<br>2<br>a<br>fi<br>fi<br>d<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c       | OF THE STATE ARCHITECT<br>O3-19: LISTING OF S<br>O5A.3; ACI 318-14 Sections 2<br>Number:<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>Inspect groove welds, multi-p<br>let welds > 5/16", plug and slc<br>Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and r<br>Verification of reinforcing ste<br>ther than ASTM A706.<br>Inspect welding of reinforcing<br>3. ANCHOR BOLTS AND ANC<br>est or Special Inspection   | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet welds, single pass<br>ot welds.<br>Is ≤ 5/16", floor and root<br>railing systems.<br>el weldability<br>g steel.<br>HOR RODS:       | & SPECIAL<br>Type<br>Continuous<br>Periodic<br>Periodic<br>Continuous                 | Page 4 of 11<br>INSPECT<br>Performed<br>By<br>SI<br>SI<br>SI<br>SI                           | ONS (Concrete), 2019 CBC         School District:<br>PC Submittal<br>Date Created:<br>2021-07-14 05:50:33         Date Created:<br>2021-07-14 05:50:33         Code References and Notes         Table 1705A.2.1 Items 5a.1-4; AISC 360-16 (and AISC 341-16 as<br>applicable); DSA IR 17-3.         1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC<br>341-16 as applicable); DSA IR 17-3.         1705A.2.1, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC<br>341-16 as applicable); DSA IR 17-3.         1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3;<br>DFA IR 17-3.         1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on<br>mill certificates.         Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8;<br>AVS D1.4; DSA IR 17-3.         Code References ant Notes  |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESS / ON<br>ESS / ON<br>E   |
| SA 1<br>bble 1<br>pplica<br>4-0000<br>SA File<br>2<br>afi<br>fi<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c                             | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>100 Number:<br>20<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>. Inspect groove welds, multi-p<br>liet welds > 5/16", plug and slo<br>. Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and a<br>. Verification of reinforcing stether than ASTM A706.<br>. Inspect welding of reinforcing<br>3. ANCHOR BOLTS AND ANC   | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet welds, single pass<br>ot welds.<br>Is ≤ 5/16", floor and rost<br>railing systems.<br>el weldability<br>g steel.<br>HOR RODS:<br>Is | & SPECIAL<br>Type<br>Continuous<br>Periodic<br>Periodic<br>Continuous                 | Page 4 of 11<br>INSPECT<br>Performed<br>By<br>SI<br>SI<br>SI<br>SI<br>SI<br>SI               | ONS (Concrete), 2019 CBC         School District:         PC Submittal         Date Created:         2021-07-14 05:50:33    Code References and Notes          Table 1705A.2.1 Items 5an -4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-5.         1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1, AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates.         Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AVS D1.4; DSA IR 17-3.         Code References and Notes         Sample and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-11.   |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I<br>WWW.JR<br>PROF<br>Stars Stars<br>PROF | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESS / ON<br>ESS / ON<br>E   |
| SA 1<br>able 4<br>pplica<br>4-0000<br>SA File<br>2<br>a fil<br>c c<br>c<br>c c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c<br>c                             | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>Number:<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>Inspect groove welds, multi-p<br>let welds > 5/16", plug and sloc<br>. Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and the<br>. Verification of reinforcing steace<br>ther than ASTM A706.<br>. Inspect welding of reinforcing<br>3. ANCHOR BOLTS AND ANC<br>est or Special Inspection<br>. Anchor Bolts and Anchor Rod  | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet welds, single pass<br>ot welds.<br>Is ≤ 5/16", floor and rost<br>railing systems.<br>el weldability<br>g steel.<br>HOR RODS:<br>Is | & SPECIAL<br>Type<br>Continuous<br>Periodic<br>Periodic<br>Continuous<br>Type<br>Test | Page 4 of 11<br>IN SPECT<br>Performed<br>By<br>SI<br>SI<br>SI<br>SI<br>SI<br>SI<br>SI<br>LOR | ONS (Concrete), 2019 CBC         School District:<br>PC Submittal<br>Date Created:<br>2021-07-14 05:50:33         Date Created:<br>2021-07-14 05:50:33         Code References and Notes         Table 1705A.2.1 Items 5a:1-4; AISC 360-16 (and AISC 341-16 as<br>applicable); DSA IR 17-3.         1705A.2.2, Table 1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1 Items 5a:5 & 5a:6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3;<br>DSA IR 17-3.         1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on<br>mill certificates.         Table 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8;<br>AIS D1.4; DSA IR 17-3.         Code References and Notes         Sample and test anchor bolts and anchor rods not readily identifiable per |          |          | 2700 SATURN ST I<br>T. 714.524.1870 I  | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESSION<br>CTURE<br>CTURE<br>CALIFORN<br>0 7 / 2 9   |
| SA 1<br>bble -<br>pplica<br>4-0000<br>SA File<br>1<br>T<br>Z<br>a<br>fi<br>c<br>c<br>c<br>c<br>c<br>z<br>z<br>Z<br>z<br>z<br>z<br>z<br>z<br>z<br>z<br>z<br>z<br>z<br>z<br>z<br>z | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>Number:<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>Inspect groove welds, multi-p<br>let welds > 5/16", plug and sloc<br>. Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and the<br>. Verification of reinforcing steace<br>ther than ASTM A706.<br>. Inspect welding of reinforcing<br>3. ANCHOR BOLTS AND ANC<br>est or Special Inspection<br>. Anchor Bolts and Anchor Rod  | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet welds, single pass<br>ot welds.<br>Is ≤ 5/16", floor and rost<br>railing systems.<br>el weldability<br>g steel.<br>HOR RODS:<br>Is | & SPECIAL<br>Type<br>Continuous<br>Periodic<br>Periodic<br>Continuous<br>Type<br>Test | Page 4 of 11<br>IN SPECT<br>Performed<br>By<br>SI<br>SI<br>SI<br>SI<br>SI<br>SI<br>SI<br>LOR | ONS (Concrete), 2019 CBC         School District:         PC Submittal         Date Created:         2021-07-14 05:50:33    Code References and Notes          Table 1705A.2.1 Items 5an -4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-9.         1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; D54 IR 17-3.         1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates.         Iable 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AIS D1.4; DSA IR 17-3.         Code References and Notes         Sample and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-11.         Sample and test threaded rods not readily identifiable per procedures                              |          |          | PPROVED<br>STATE ARCHITE<br>20013 PC   | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESS /OW<br>CTUE<br>CTUE<br>CALIFOR<br>0 7 / 2 9   |
| SA 1<br>pplica<br>4.0000<br>SA File<br>□ 1<br>□ 2<br>a<br>fi<br>0<br>0<br>c<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0                      | OF THE STATE ARCHITECT<br>03-19: LISTING OF S<br>05A.3; ACI 318-14 Sections 2<br>Number:<br>9.1 SHOP WELDING:<br>est or Special Inspection<br>Inspect groove welds, multi-p<br>let welds > 5/16", plug and slo<br>Inspect single-pass fillet weld<br>eck welds.<br>Inspect welding of stairs and the<br>Verification of reinforcing stetcher than ASTM A706.<br>Inspect welding of reinforcing<br>3. ANCHOR BOLTS AND ANC<br>est or Special Inspection<br>Anchor Bolts and Anchor Rod<br>Threaded rod not used for for  | 26.12 & 26.13<br>School Name:<br>ICON Shelter Systems<br>Increment Number:<br>Dass fillet welds, single pass<br>ot welds.<br>Is ≤ 5/16", floor and rost<br>railing systems.<br>el weldability<br>g steel.<br>HOR RODS:<br>Is | & SPECIAL<br>Type<br>Continuous<br>Periodic<br>Periodic<br>Continuous<br>Type<br>Test | Page 4 of 11<br>IN SPECT<br>Performed<br>By<br>SI<br>SI<br>SI<br>SI<br>SI<br>SI<br>SI<br>LOR | ONS (Concrete), 2019 CBC         School District:         PC Submittal         Date Created:         2021-07-14 05:50:33    Code References and Notes          Table 1705A.2.1 Items 5an -4; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-9.         1705A.2.2, Table 1705A.2.1 Items 5a.5 & 5a.6; AISC 360-16 (and AISC 341-16 as applicable); DSA IR 17-3.         1705A.2.1; AISC 360-16 (and AISC 341-16 as applicable); AWS D1.1 & D1.3; D54 IR 17-3.         1705A.3.1; AWS D1.4; DSA IR 17-3. Verify carbon equivalent reported on mill certificates.         Iable 1705A.2.1 Item 5b, 1705A.3.1, Table 1705A.3 Item 2, 1903A.8; AIS D1.4; DSA IR 17-3.         Code References and Notes         Sample and test anchor bolts and anchor rods not readily identifiable per procedures noted in DSA IR 17-11.         Sample and test threaded rods not readily identifiable per procedures                              |          | APP: 04- | PPROVED<br>STATE ARCHITE   | BREA, CA 92821<br>F. 714.524.1875<br>MA.COM<br>ESS /OW<br>CTUE<br>CAL IFORM<br>07 / 2 9  |

FOR ALL TESTING AND INSPECTION ITEMS SEE THE DSA APPROVED 103 FOR THIS PROJECT.



PRE-CHECK (PC) DOCUMENT Code: 2019 CBC A separate project application for construction is required.

